NAME OF WORK :IMPROVEMENTS AND RESTORATION OF ROAD IN WARD NO. 05 (PACKAGE 01) (PACKAGE CONSISTS OF 6 WORKS).

MODIFIED ESTIMATE

BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK:- Improvements and Restoration of Roads in Ward No.05 (Package No.01) (Package Consists of 06 Works)

MODIFIED ESTIMATION

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
Item no. 1		KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(P.No-143 &136 ,I No-19.1&17.4& 17.1) 5km lead= 57+2.0x1.28x5 =69.80										
		C.C Drain										
		Palanahalli Road										
		L.H.S										
		West To East										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
90.00	105.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
105.00	112.35		Cum	1	7.35	1.10	1.10	1.10	0.90	7.28		
112.35	116.75	Culvert	Cum	0	0.00	1.10	1.10	1.10	0.90	0.00		
116.75	126.75		Cum	1	10.00	1.10	1.10	1.10	0.90	9.90		
		R.H.S										
		West To East										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60.00	75.10		Cum	1	15.10	1.10	1.10	1.10	0.90	14.95		
75.10	80.75	Culvert	Cum	0	0.00	1.10	1.10	1.10	0.90	0.00		
80.75	84.90		Cum	1	4.15	1.10	1.10	1.10	0.90	4.11		
84.90	90.35	No Work	Cum	0	0.00	1.10	1.10	1.10	0.90	0.00		
90.35	105.35		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
105.35	120.35		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
120.35	125.35		Cum	1	5.00	1.10	1.10	1.10	0.90	4.95		
125.35	130.15	Existing S.S.M Culvert	Cum	0	0.00	1.10	1.10	1.10	0.90	0.00		
		Katgenahalli, Venkatappa Building To Medical Shop										
		R.H.S										
		West To East										
0.00	14.90		Cum	1	14.90	1.10	1.10	1.10	0.45	7.38		
14.90	21.50		Cum	1	6.60	1.10	1.10	1.10	0.80	5.81		
21.50	31.70		Cum	1	10.20	1.10	1.10	1.10	0.80	8.98		
31.70	46.70		Cum	1	15.00	1.10	1.10	1.10	0.80	13.20		
46.70	50.70		Cum	1	4.00	1.10	1.10	1.10	0.80	3.52		
		From Kamal House To Shiva House										
		R.H.S										
		North To South										
0.00	9.20		Cum	1	9.20	1.00	1.00	1.00	0.75	6.90		
		R.H.S										
		East To West										
0.00	15.00		Cum	1	15.00	1.00	1.00	1.00	0.75	11.25		
15.00	30.00		Cum	1	15.00	1.00	1.00	1.00	0.75	11.25		
30.00	33.75		Cum	1	3.75	1.00	1.00	1.00	0.75	2.81		
		R.H.S										
		South To North										
0.00	9.40		Cum	1	9.40	1.00	1.00	1.00	0.75	7.05		
		Sri Channa Keshava Swami Provision Store										
		L.H.S										
		North To South										
0.00	14.50		Cum	1	14.50	0.95	0.95	0.95	0.75	10.33		
		L.H.S										
		East To West										
0.00	15.00	0.75m Drain	Cum	1	15.00	0.95	0.95	0.95	0.75	10.69		
15.00	26.20		Cum	1	11.20	0.95	0.95	0.95	0.75	7.98		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		L.H.S										
		West To East										
0.00	4.90		Cum	1	4.90	0.95	0.95	0.95	0.75	3.49		
		L.H.S										
		South To North										
0.00	8.50		Cum	1	8.50	0.95	0.95	0.95	0.75	6.06		
		L.H.S										
		West To East										
0.00	13.20		Cum	1	13.20	0.95	0.95	0.95	0.75	9.41		
		Cross Road										
		South To North										
0.00	15.00		Cum	1	15.00	0.95	0.95	0.95	0.75	10.69		
15.00	30.20		Cum	1	15.20	0.95	0.95	0.95	0.75	10.83		
		Cross Road 1										
		LHS										
		(From East to West)										
0.00	12.10		Cum	1	12.10	1.00	1.00	1.00	0.75	9.08		
12.10	27.10		Cum	1	15.00	1.00	1.00	1.00	0.75	11.25		
27.10	30.00		Cum	1	2.90	1.00	1.00	1.00	0.75	2.18		
		RHS										
		(From East to West)										
0.00	15.00		Cum	1	15.00	1.00	1.00	1.00	0.75	11.25		
15.00	29.80		Cum	1	14.80	1.00	1.00	1.00	0.75	11.10		
		Cross Road 2										
		LHS										
		(From East to West)										
0.00	15.00		Cum	1	15.00	1.00	1.00	1.00	0.75	11.25		
15.00	30.00		Cum	1	15.00	1.00	1.00	1.00	0.75	11.25		
30.00	31.70		Cum	1	1.70	1.00	1.00	1.00	0.75	1.28		
		Culvert										
		Sri Channa Keshava Swami Provision Store										
		RHS										
		East To West										
			Cum	1	6.30	1.40	1.40	1.40	0.95	8.38		
		Palanahalli main Road										
		LHS	Cuim	1	4.40	1.40	1.40	1.40	0.95	5.85		
		RHS	Cuim	1	5.65	1.40	1.40	1.40	0.95	7.51		
		Desilt										
		Palenahalli Main Road										
		West To East										
		L.H.S										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	100.90		Cum	1	10.90	0.45	0.45	0.45	0.45	2.21		
		R.H.S										
		West To East										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	72.80		Cum	1	12.80	0.45	0.45	0.45	0.45	2.59		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Vinayak nagar										
		6thB Main Road										
		LHS										
		South to North										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
105.00	107.40		Cum	1	2.40	0.45	0.45	0.45	0.50	0.54		
		LHS										
		South to North										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
105.00	107.60		Cum	1	2.60	0.45	0.45	0.45	0.50	0.58		
		M S Nagar										
		11th A Cross/2nd Main Road										
		LHS										
		(From South to North)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.35	2.36		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.35	2.36		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.35	2.36		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.35	2.36		
60.00	63.20		Cum	1	3.20	0.45	0.45	0.45	0.35	0.50		
		RHS										
		(From South to North)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	65.20		Cum	1	5.20	0.45	0.45	0.45	0.45	1.05		
		11th Cross Road										
		RHS										
		(From South to North)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	70.00		Cum	1	10.00	0.45	0.45	0.45	0.45	2.03		
70.00	75.00		Cum	1	5.00	0.45	0.45	0.45	0.45	1.01		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	135.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
135.00	150.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
150.00	165.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
165.00	168.10		Cum	1	3.10	0.45	0.45	0.45	0.45	0.63		
		10th Cross Road										
		LHS										
		(From North to South)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	108.60		Cum	1	3.60	0.45	0.45	0.45	0.45	0.73		
108.60	117.40		Cum	1	8.80	0.45	0.45	0.45	0.45	1.78		
117.40	120.00		Cum	1	2.60	0.45	0.45	0.45	0.45	0.53		
120.00	135.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
135.00	150.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
150.00	165.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
165.00	167.70		Cum	1	2.70	0.45	0.45	0.45	0.45	0.55		
		RHS										
		(From North to South)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
105.00	108.60		Cum	1	3.60	0.45	0.45	0.45	0.40	0.65		
108.60	117.40		Cum	1	8.80	0.45	0.45	0.45	0.40	1.58		
117.40	120.00		Cum	1	2.60	0.45	0.45	0.45	0.40	0.47		
120.00	135.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
135.00	150.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
150.00	165.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
165.00	167.70		Cum	1	2.70	0.45	0.45	0.45	0.40	0.49		
		10th A Cross										
		LHS										
		(From North to South)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	134.60		Cum	1	14.60	0.45	0.45	0.45	0.45	2.96		
		RHS										
		(From North to South)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
120.00	134.60		Cum	1	14.60	0.45	0.45	0.45	0.40	2.63		
		2nd Main Road										
		LHS										
		(From West to East)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	135.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
135.00	150.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
150.00	165.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
165.00	180.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
180.00	192.60		Cum	1	12.60	0.45	0.45	0.45	0.45	2.55		
		RHS										
		(From West to East)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	135.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
135.00	150.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
150.00	165.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
165.00	180.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
180.00	192.60		Cum	1	12.60	0.45	0.45	0.45	0.45	2.55		
		2nd Main Road To M S Nagar Road										
		LHS										
		(From West to East)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
30.00	32.30		Cum	1	2.30	0.45	0.45	0.45	0.40	0.41		
		LHS										
		(From South to North)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
120.00	135.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
135.00	150.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
150.00	165.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
165.00	180.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
180.00	194.40		Cum	1	14.40	0.45	0.45	0.45	0.40	2.59		
		RHS										
		(From South to North)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	135.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
135.00	150.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
150.00	165.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
165.00	180.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
180.00	194.40		Cum	1	14.40	0.45	0.45	0.45	0.45	2.92		
		LHS										
		(From East to West)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	49.50		Cum	1	4.50	0.45	0.45	0.45	0.45	0.91		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		RHS										
		(From East to West)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	49.50		Cum	1	4.50	0.45	0.45	0.45	0.45	0.91		
		3A Cross Road										
		LHS										
		(From East to West)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	39.60		Cum	1	9.60	0.45	0.45	0.45	0.45	1.94		
		RHS										
		(From East to West)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	41.40		Cum	1	11.40	0.45	0.45	0.45	0.45	2.31		
41.40	45.80		Cum	1	4.40	0.45	0.45	0.45	0.45	0.89		
		LHS										
		(From North to South)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
15.00	18.60		Cum	1	3.60	0.45	0.45	0.45	0.40	0.65		
		RHS										
		(From North to South)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.40	2.70		
15.00	18.60		Cum	1	3.60	0.45	0.45	0.45	0.40	0.65		
		5th Cross Road										
		LHS										
		(From North to South)										
0.00	3.40		Cum	1	3.40	0.45	0.45	0.45	0.45	0.69		
3.40	15.00		Cum	1	11.60	0.45	0.45	0.45	0.45	2.35		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	54.00		Cum	1	9.00	0.45	0.45	0.45	0.45	1.82		
		RHS										
		(From North to South)										
0.00	3.40		Cum	1	3.40	0.45	0.45	0.45	0.45	0.69		
3.40	15.00		Cum	1	11.60	0.45	0.45	0.45	0.45	2.35		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	54.00		Cum	1	9.00	0.45	0.45	0.45	0.45	1.82		
		For Culvert										
		2nd main Bande Road										
			Cum	1	8.40	1.30	1.30	1.30	1.25	13.65		
		Masjid Road										
			Cum	1	3.60	1.60	1.60	1.60	1.25	7.20		
		Kodigenahalli government School Road										
			Cum	1	6.70	1.30	1.30	1.30	1.25	10.89		
		Hegde Nagara										
		Win Field Garden										
		5th Cross Road (W1941)										
		LHS										
		(From South to North)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	135.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
135.00	150.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
150.00	165.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
165.00	180.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
180.00	190.50		Cum	1	10.50	0.45	0.45	0.45	0.45	2.13		
		RHS										
		(From South to North)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	135.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
135.00	150.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
150.00	165.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
165.00	180.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
180.00	190.50		Cum	1	10.50	0.45	0.45	0.45	0.45	2.13		
		6th Cross Road (W1935)										
		LHS										
		(From South to North)										
0.00	15.00		Cum	1	2.00	0.45	0.45	0.45	0.45	0.41		
15.00	30.00		Cum	1	13.00	0.45	0.45	0.45	0.45	2.63		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	135.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
135.00	150.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
150.00	165.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
165.00	181.50		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
		RHS										
		(From South to North)										
0.00	15.00		Cum	1	2.00	0.45	0.45	0.45	0.45	0.41		
15.00	30.00		Cum	1	13.00	0.45	0.45	0.45	0.45	2.63		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	135.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
135.00	150.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
150.00	165.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
165.00	181.50		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
		9th Cross Road										
		LHS										
		(From South to North)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	135.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
135.00	137.90		Cum	1	2.90	0.45	0.45	0.45	0.45	0.59		
		RHS										
		(From South to North)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	135.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
135.00	137.90		Cum	1	2.90	0.45	0.45	0.45	0.45	0.59		
		Win field Garden										
		8th Cross road										
		LHS										
		(From South to North)										
0.00	13.20		Cum	1	13.20	0.45	0.45	0.45	0.45	2.67		
13.20	41.00	No Work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
41.00	48.70		Cum	1	7.70	0.45	0.45	0.45	0.45	1.56		
48.70	59.60	No Work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
59.60	74.60		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
74.60	89.60		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
89.60	104.60		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
104.60	119.60		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
119.60	134.60		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
134.60	145.50		Cum	1	10.90	0.45	0.45	0.45	0.45	2.21		
		RHS										
		(From South to North)										
0.00	4.50		Cum	1	4.50	0.45	0.45	0.45	0.45	0.91		
4.50	23.40	No Work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
23.40	32.20		Cum	1	8.80	0.45	0.45	0.45	0.45	1.78		
32.20	41.70	No Work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
41.70	56.70		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
56.70	71.70		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
71.70	86.70		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
86.70	95.00		Cum	1	8.30	0.45	0.45	0.45	0.45	1.68		
95.00	114.80	No Work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
114.80	129.80		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
129.80	144.80		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
144.80	146.00		Cum	1	1.20	0.45	0.45	0.45	0.45	0.24		
		7th Cross Road										
		LHS										
		(From South to North)										
0.00	23.20	No Work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
23.20	37.60		Cum	1	14.40	0.45	0.45	0.45	0.45	2.92		
37.60	47.20	No Work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
47.20	62.20		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
62.20	77.20		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
77.20	92.20		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
92.20	107.20		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
107.20	122.20		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
122.20	130.20		Cum	1	8.00	0.45	0.45	0.45	0.45	1.62		
130.20	139.00	No Work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
		RHS										
		(From South to North)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
120.00	135.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
135.00	150.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
150.00	165.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
165.00	175.00		Cum	1	10.00	0.45	0.45	0.45	0.45	2.03		
		Katgenahalli										
		Muneshwara Provision Store Beside Road										
		Kalidas Layout										
		3rd Main Road										
		LHS										
		(From North to South)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	66.40		Cum	1	6.40	0.45	0.45	0.45	0.45	1.30		
66.40	75.00		Cum	1	8.60	0.45	0.45	0.45	0.45	1.74		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	113.00		Cum	1	8.00	0.45	0.45	0.45	0.45	1.62		
		RHS										
		(From North to South)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	66.40		Cum	1	6.40	0.45	0.45	0.45	0.45	1.30		
66.40	75.00		Cum	1	8.60	0.45	0.45	0.45	0.45	1.74		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	113.00		Cum	1	8.00	0.45	0.45	0.45	0.45	1.62		
		Cross Road - 1										
		LHS										
		(From South to North)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	51.20		Cum	1	6.20	0.45	0.45	0.45	0.45	1.26		
		RHS										
		(From South to North)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	88.60		Cum	1	13.60	0.45	0.45	0.45	0.45	2.75		
		Cross Road - 2										
		LHS										
		(From North to South)										
0.00	4.30		Cum	1	4.30	0.45	0.45	0.45	0.45	0.87		
4.30	15.00		Cum	1	10.70	0.45	0.45	0.45	0.45	2.17		
15.00	20.60		Cum	1	5.60	0.45	0.45	0.45	0.45	1.13		
20.60	30.00		Cum	1	9.40	0.45	0.45	0.45	0.45	1.90		
30.00	40.60		Cum	1	10.60	0.45	0.45	0.45	0.45	2.15		
40.60	45.00		Cum	1	4.40	0.45	0.45	0.45	0.45	0.89		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	123.00		Cum	1	3.00	0.45	0.45	0.45	0.45	0.61		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		RHS										
		(From North to South)										
0.00	4.30		Cum	1	4.30	0.45	0.45	0.45	0.45	0.87		
4.30	15.00		Cum	1	10.70	0.45	0.45	0.45	0.45	2.17		
15.00	20.60		Cum	1	5.60	0.45	0.45	0.45	0.45	1.13		
20.60	30.00		Cum	1	9.40	0.45	0.45	0.45	0.45	1.90		
30.00	40.60		Cum	1	10.60	0.45	0.45	0.45	0.45	2.15		
40.60	45.00		Cum	1	4.40	0.45	0.45	0.45	0.45	0.89		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	123.00		Cum	1	3.00	0.45	0.45	0.45	0.45	0.61		
		Green Garden Main Road										
		(West to East)										
		LHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	42.70		Cum	1	12.70	0.45	0.45	0.45	0.45	2.57		
42.70	45.00		Cum	1	2.30	0.45	0.45	0.45	0.45	0.47		
45.00	53.70		Cum	1	8.70	0.45	0.45	0.45	0.45	1.76		
53.70	60.00		Cum	1	6.30	0.45	0.45	0.45	0.45	1.28		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	126.90		Cum	1	6.90	0.45	0.45	0.45	0.45	1.40		
126.90	130.00		Cum	1	3.10	0.45	0.45	0.45	0.45	0.63		
130.00	145.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
145.00	154.30		Cum	1	9.30	0.45	0.45	0.45	0.45	1.88		
154.30	160.00		Cum	1	5.70	0.45	0.45	0.45	0.45	1.15		
160.00	171.40		Cum	1	11.40	0.45	0.45	0.45	0.45	2.31		
		RHS										
		(West to East)										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	42.70		Cum	1	12.70	0.45	0.45	0.45	0.45	2.57		
42.70	45.00		Cum	1	2.30	0.45	0.45	0.45	0.45	0.47		
45.00	53.70		Cum	1	8.70	0.45	0.45	0.45	0.45	1.76		
53.70	60.00		Cum	1	6.30	0.45	0.45	0.45	0.45	1.28		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	126.90		Cum	1	6.90	0.45	0.45	0.45	0.45	1.40		
126.90	130.00		Cum	1	3.10	0.45	0.45	0.45	0.45	0.63		
130.00	145.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
145.00	154.30		Cum	1	9.30	0.45	0.45	0.45	0.45	1.88		
154.30	160.00		Cum	1	5.70	0.45	0.45	0.45	0.45	1.15		
160.00	171.40		Cum	1	11.40	0.45	0.45	0.45	0.45	2.31		
		Cross Road-4										
		(South to North)										
		LHS										
0.00	1.60		Cum	1	1.60	0.45	0.45	0.45	0.45	0.32		
1.60	15.00		Cum	1	13.40	0.45	0.45	0.45	0.45	2.71		
15.00	23.50		Cum	1	8.50	0.45	0.45	0.45	0.45	1.72		
23.50	30.00		Cum	1	6.50	0.45	0.45	0.45	0.45	1.32		
30.00	33.70		Cum	1	3.70	0.45	0.45	0.45	0.45	0.75		
		RHS										
		(South to North)										
0.00	1.60		Cum	1	1.60	0.45	0.45	0.45	0.45	0.32		
1.60	15.00		Cum	1	13.40	0.45	0.45	0.45	0.45	2.71		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
15.00	23.50		Cum	1	8.50	0.45	0.45	0.45	0.45	1.72		
23.50	30.00		Cum	1	6.50	0.45	0.45	0.45	0.45	1.32		
30.00	33.70		Cum	1	3.70	0.45	0.45	0.45	0.45	0.75		
		Sri Ganga House Road										
		East to West										
		LHS										
0.00	3.80		Cum	1	3.80	0.45	0.45	0.45	0.45	0.77		
3.80	13.20		Cum	1	9.40	0.45	0.45	0.45	0.45	1.90		
13.20	15.00		Cum	1	1.80	0.45	0.45	0.45	0.45	0.36		
15.00	27.40		Cum	1	12.40	0.45	0.45	0.45	0.45	2.51		
27.40	30.00		Cum	1	2.60	0.45	0.45	0.45	0.45	0.53		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	69.30		Cum	1	9.30	0.45	0.45	0.45	0.45	1.88		
		RHS										
		East to West										
0.00	3.80		Cum	1	3.80	0.45	0.45	0.45	0.45	0.77		
3.80	13.20		Cum	1	9.40	0.45	0.45	0.45	0.45	1.90		
13.20	15.00		Cum	1	1.80	0.45	0.45	0.45	0.45	0.36		
15.00	27.40		Cum	1	12.40	0.45	0.45	0.45	0.45	2.51		
27.40	30.00		Cum	1	2.60	0.45	0.45	0.45	0.45	0.53		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	69.30		Cum	1	9.30	0.45	0.45	0.45	0.45	1.88		
		Cross Road-3										
		(North to South)										
		LHS										
0.00	1.70		Cum	1	1.70	0.45	0.45	0.45	0.45	0.34		
1.70	15.00		Cum	1	13.30	0.45	0.45	0.45	0.45	2.69		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	46.10		Cum	1	1.10	0.45	0.45	0.45	0.45	0.22		
46.10	48.90		Cum	1	2.80	0.45	0.45	0.45	0.45	0.57		
		RHS										
		(North to South)										
0.00	1.70		Cum	1	1.70	0.45	0.45	0.45	0.45	0.34		
1.70	15.00		Cum	1	13.30	0.45	0.45	0.45	0.45	2.69		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	46.10		Cum	1	1.10	0.45	0.45	0.45	0.45	0.22		
46.10	48.90		Cum	1	2.80	0.45	0.45	0.45	0.45	0.57		
		Cross Road 2										
		(South to North)										
		LHS										
0.00	11.80		Cum	1	11.80	0.45	0.45	0.45	0.45	2.39		
11.80	15.00		Cum	1	3.20	0.45	0.45	0.45	0.45	0.65		
15.00	21.10		Cum	1	6.10	0.45	0.45	0.45	0.45	1.24		
21.10	30.00		Cum	1	8.90	0.45	0.45	0.45	0.45	1.80		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	100.30		Cum	1	10.30	0.45	0.45	0.45	0.45	2.09		
100.30	102.40		Cum	1	2.10	0.45	0.45	0.45	0.45	0.43		
		RHS										
		(South to North)										
0.00	11.80		Cum	1	11.80	0.45	0.45	0.45	0.45	2.39		
11.80	15.00		Cum	1	3.20	0.45	0.45	0.45	0.45	0.65		
15.00	21.10		Cum	1	6.10	0.45	0.45	0.45	0.45	1.24		
21.10	30.00		Cum	1	8.90	0.45	0.45	0.45	0.45	1.80		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	100.30		Cum	1	10.30	0.45	0.45	0.45	0.45	2.09		
100.30	102.40		Cum	1	2.10	0.45	0.45	0.45	0.45	0.43		
		Cross Road 1										
		(North to South)										
		LHS										
0.00	2.90		Cum	1	2.90	0.45	0.45	0.45	0.45	0.59		
2.90	15.00		Cum	1	12.10	0.45	0.45	0.45	0.45	2.45		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	102.30		Cum	1	12.30	0.45	0.45	0.45	0.45	2.49		
		RHS										
		(North to South)										
0.00	2.90		Cum	1	2.90	0.45	0.45	0.45	0.45	0.59		
2.90	15.00		Cum	1	12.10	0.45	0.45	0.45	0.45	2.45		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	102.30		Cum	1	12.30	0.45	0.45	0.45	0.45	2.49		
		Pyramid apartment main road										
		(East to West)										
		LHS										
0.00	1.10		Cum	1	1.10	0.45	0.45	0.45	0.45	0.22		
1.10	2.40		Cum	1	1.30	0.45	0.45	0.45	0.45	0.26		
2.40	4.70		Cum	1	2.30	0.45	0.45	0.45	0.45	0.47		
4.70	12.40		Cum	1	7.70	0.45	0.45	0.45	0.45	1.56		
12.40	15.00		Cum	1	2.60	0.45	0.45	0.45	0.45	0.53		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	32.00		Cum	1	2.00	0.45	0.45	0.45	0.45	0.41		
32.00	45.00		Cum	1	13.00	0.45	0.45	0.45	0.45	2.63		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	81.10		Cum	1	6.10	0.45	0.45	0.45	0.45	1.24		
81.10	90.00		Cum	1	8.90	0.45	0.45	0.45	0.45	1.80		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	128.00		Cum	1	8.00	0.45	0.45	0.45	0.45	1.62		
		Cross Road 3 Near Pyramid apartment										
		(North to South)										
		LHS										
0.00	2.90		Cum	1	2.90	0.45	0.45	0.45	0.45	0.59		
2.90	15.00		Cum	1	12.10	0.45	0.45	0.45	0.45	2.45		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	44.00		Cum	1	14.00	0.45	0.45	0.45	0.45	2.84		
		RHS										
		(North to South)										
0.00	2.90		Cum	1	2.90	0.45	0.45	0.45	0.45	0.59		
2.90	15.00		Cum	1	12.10	0.45	0.45	0.45	0.45	2.45		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	44.00		Cum	1	14.00	0.45	0.45	0.45	0.45	2.84		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Cross Road 2 Near Pyramid apartment										
		(North to South)										
		LHS										
0.00	3.60		Cum	1	3.60	0.45	0.45	0.45	0.45	0.73		
3.60	15.00		Cum	1	11.40	0.45	0.45	0.45	0.45	2.31		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	32.80		Cum	1	2.80	0.45	0.45	0.45	0.45	0.57		
32.80	42.30		Cum	1	9.50	0.45	0.45	0.45	0.45	1.92		
42.30	45.10		Cum	1	2.80	0.45	0.45	0.45	0.45	0.57		
45.10	48.30		Cum	1	3.20	0.45	0.45	0.45	0.45	0.65		
		RHS										
		(North to South)										
0.00	3.60		Cum	1	3.60	0.45	0.45	0.45	0.45	0.73		
3.60	15.00		Cum	1	11.40	0.45	0.45	0.45	0.45	2.31		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	32.80		Cum	1	2.80	0.45	0.45	0.45	0.45	0.57		
32.80	42.30		Cum	1	9.50	0.45	0.45	0.45	0.45	1.92		
42.30	45.10		Cum	1	2.80	0.45	0.45	0.45	0.45	0.57		
45.10	48.30		Cum	1	3.20	0.45	0.45	0.45	0.45	0.65		
		Cross Road 1 Near Pyramid apartment										
		(North to South)										
		LHS										
0.00	4.50		Cum	1	4.50	0.45	0.45	0.45	0.45	0.91		
4.50	15.00		Cum	1	10.50	0.45	0.45	0.45	0.45	2.13		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	51.70		Cum	1	6.70	0.45	0.45	0.45	0.45	1.36		
51.70	52.20		Cum	1	0.50	0.45	0.45	0.45	0.45	0.10		
52.20	60.00		Cum	1	7.80	0.45	0.45	0.45	0.45	1.58		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	127.20		Cum	1	7.20	0.45	0.45	0.45	0.45	1.46		
		RHS										
		(North to South)										
0.00	4.50		Cum	1	4.50	0.45	0.45	0.45	0.45	0.91		
4.50	15.00		Cum	1	10.50	0.45	0.45	0.45	0.45	2.13		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	51.70		Cum	1	6.70	0.45	0.45	0.45	0.45	1.36		
51.70	52.20		Cum	1	0.50	0.45	0.45	0.45	0.45	0.10		
52.20	60.00		Cum	1	7.80	0.45	0.45	0.45	0.45	1.58		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	127.20		Cum	1	7.20	0.45	0.45	0.45	0.45	1.46		
		Vidhana Soudha Layout										
		LHS										
		(From East to West)										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
45.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
60.00	75.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
75.00	90.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
90.00	105.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
105.00	120.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
120.00	135.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
135.00	150.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
150.00	165.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
165.00	180.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
180.00	195.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
195.00	210.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
210.00	225.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
225.00	240.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
240.00	255.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
255.00	270.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
270.00	285.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
285.00	300.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
300.00	315.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
315.00	330.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
330.00	345.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
345.00	360.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
360.00	375.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
375.00	390.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
390.00	405.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
405.00	420.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
420.00	435.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
435.00	450.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
450.00	465.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
465.00	480.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
480.00	495.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
495.00	510.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
510.00	525.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
525.00	540.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
540.00	555.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
555.00	562.70		Cum	1	7.70	0.60	0.60	0.60	0.60	2.77		
		RHS										
		(From East to West)										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
45.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
60.00	75.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
75.00	90.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
90.00	105.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
105.00	120.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
120.00	135.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
135.00	150.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
150.00	165.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
165.00	180.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
180.00	195.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
195.00	210.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
210.00	225.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
225.00	240.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
240.00	255.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
255.00	270.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
270.00	285.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
285.00	300.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
300.00	315.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
315.00	330.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
330.00	345.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
345.00	360.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
360.00	375.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
375.00	390.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
390.00	405.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
405.00	420.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
420.00	435.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
435.00	450.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
450.00	465.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
465.00	480.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
480.00	495.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
495.00	510.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
510.00	525.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
525.00	540.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
540.00	555.00		Cum	1	15.00	0.60	0.60	0.60	0.60	5.40		
555.00	562.70		Cum	1	7.70	0.60	0.60	0.60	0.60	2.77		
		Total Executed Quantity								**2138.52**	209.68	448406.00
		Tender Quantity								**3826.79**		
Item no. 2		Removing and refixing stone slabs of drains and pointing in CM (1:3) (P.No-27,I No-5.33)										
		Anand Nagar										
		1st Cross Road										
		Royal ACE Road										
		(From North to South)										
0.00	8.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
14.00	17.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
24.00	29.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
32.00	41.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
46.00	56.00		Sqm	1	10.00	1.35	1.35	1.35		13.50		
62.00	74.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
75.80	90.00		Sqm	1	14.20	1.35	1.35	1.35		19.17		
90.00	95.10		Sqm	1	5.10	1.35	1.35	1.35		6.88		
		M S Nagar										
		11th A Cross/2nd Main Road										
		LHS										
		(From South to North)										
0.00	10.40		Sqm	1	10.40	1.35	1.35	1.35		14.04		
16.00	27.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
30.00	42.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
48.50	58.90		Sqm	1	10.40	1.35	1.35	1.35		14.04		
61.00	63.20		Sqm	1	2.20	1.35	1.35	1.35		2.97		
		RHS										
		(From South to North)										
0.00	13.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
18.00	29.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
32.00	40.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
46.00	55.10		Sqm	1	9.10	1.35	1.35	1.35		12.29		
61.00	65.20		Sqm	1	4.20	1.35	1.35	1.35		5.67		
		11th Cross Road										
		RHS										
		(From South to North)										
0.00	11.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
14.00	22.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
26.00	37.20		Sqm	1	11.20	1.35	1.35	1.35		15.12		
41.00	52.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
60.00	63.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
69.00	73.20		Sqm	1	4.20	1.35	1.35	1.35		5.67		
75.00	80.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
84.00	96.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
105.00	114.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
119.00	134.00		Sqm	1	15.00	1.35	1.35	1.35		20.25		
134.00	146.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
151.00	165.00		Sqm	1	14.00	1.35	1.35	1.35		18.90		
166.00	168.10		Sqm	1	2.10	1.35	1.35	1.35		2.83		
		10th Cross Road										
		LHS										
		(From North to South)										
0.00	9.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
16.00	27.40		Sqm	1	11.40	1.35	1.35	1.35		15.39		
29.00	42.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
45.00	58.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
61.00	66.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
75.00	80.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
90.50	104.00		Sqm	1	13.50	1.35	1.35	1.35		18.23		
105.00	108.60		Sqm	1	3.60	1.35	1.35	1.35		4.86		
108.60	115.00		Sqm	1	6.40	1.35	1.35	1.35		8.64		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
118.00	120.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
122.00	131.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
136.00	149.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
154.00	164.70		Sqm	1	10.70	1.35	1.35	1.35		14.45		
165.00	167.70		Sqm	1	2.70	1.35	1.35	1.35		3.64		
		RHS										
		(From North to South)										
0.00	6.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
15.00	29.00		Sqm	1	14.00	1.35	1.35	1.35		18.90		
32.00	40.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
45.00	52.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
59.00	71.20		Sqm	1	12.20	1.35	1.35	1.35		16.47		
76.00	88.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
90.00	101.30		Sqm	1	11.30	1.35	1.35	1.35		15.26		
105.00	108.60		Sqm	1	3.60	1.35	1.35	1.35		4.86		
109.00	116.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
118.00	120.50		Sqm	1	2.50	1.35	1.35	1.35		3.38		
123.00	135.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
140.00	149.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
154.00	164.60		Sqm	1	10.60	1.35	1.35	1.35		14.31		
165.00	167.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
		10th A Cross										
		LHS										
		(From North to South)										
0.00	13.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
18.00	26.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
33.00	45.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
48.00	54.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
60.00	67.10		Sqm	1	7.10	1.35	1.35	1.35		9.58		
75.00	89.00		Sqm	1	14.00	1.35	1.35	1.35		18.90		
90.00	102.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
105.00	116.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
123.50	134.60		Sqm	1	11.10	1.35	1.35	1.35		14.99		
		RHS										
		(From North to South)										
0.00	11.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
15.00	27.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
34.00	42.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
49.00	57.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
62.00	73.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
79.00	86.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
94.00	107.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
110.50	120.00		Sqm	1	9.50	1.35	1.35	1.35		12.83		
120.00	134.60		Sqm	1	14.60	1.35	1.35	1.35		19.71		
		2nd Main Road										
		LHS										
		(From West to East)										
0.00	13.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
17.00	29.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
33.00	41.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
48.00	56.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
61.00	72.10		Sqm	1	11.10	1.35	1.35	1.35		14.99		
79.00	88.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
118.00	127.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
146.00	155.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
176.00	184.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
191.00	192.60		Sqm	1	1.60	1.35	1.35	1.35		2.16		
		RHS										
		(From West to East)										
0.00	11.20		Sqm	1	11.20	1.35	1.35	1.35		15.12		
17.50	28.00		Sqm	1	10.50	1.35	1.35	1.35		14.18		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
30.00	40.50		Sqm	1	10.50	1.35	1.35	1.35		14.18		
49.20	57.00		Sqm	1	7.80	1.35	1.35	1.35		10.53		
78.00	82.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
94.00	103.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
122.00	133.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
152.00	162.00		Sqm	1	10.00	1.35	1.35	1.35		13.50		
182.00	192.60		Sqm	1	10.60	1.35	1.35	1.35		14.31		
		2nd Main Road To M S Nagar Road										
		LHS										
		(From West to East)										
0.00	9.20		Sqm	1	9.20	1.35	1.35	1.35		12.42		
17.00	28.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
30.00	32.30		Sqm	1	2.30	1.35	1.35	1.35		3.11		
		LHS										
		(From South to North)										
0.00	9.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
16.00	25.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
32.00	44.60		Sqm	1	12.60	1.35	1.35	1.35		17.01		
49.00	56.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
61.00	73.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
77.00	90.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
90.00	100.50		Sqm	1	10.50	1.35	1.35	1.35		14.18		
104.00	115.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
120.00	129.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
136.00	147.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
152.00	160.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
168.20	179.00		Sqm	1	10.80	1.35	1.35	1.35		14.58		
181.50	194.40		Sqm	1	12.90	1.35	1.35	1.35		17.42		
		RHS										
		(From South to North)										
0.00	12.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
14.00	22.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
30.00	41.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
49.00	56.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
63.00	71.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
78.00	85.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
89.00	96.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
103.00	118.00		Sqm	1	15.00	1.35	1.35	1.35		20.25		
120.00	131.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
135.00	148.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
153.00	163.00		Sqm	1	10.00	1.35	1.35	1.35		13.50		
164.50	178.00		Sqm	1	13.50	1.35	1.35	1.35		18.23		
181.00	194.40		Sqm	1	13.40	1.35	1.35	1.35		18.09		
		LHS										
		(From East to West)										
0.00	13.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
19.00	26.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
33.00	44.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
46.00	49.50		Sqm	1	3.50	1.35	1.35	1.35		4.73		
		RHS										
		(From East to West)										
0.00	7.50		Sqm	1	7.50	1.35	1.35	1.35		10.13		
14.00	23.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
31.00	44.50		Sqm	1	13.50	1.35	1.35	1.35		18.23		
45.00	49.50		Sqm	1	4.50	1.35	1.35	1.35		6.08		
		3A Cross Road										
		LHS										
		(From East to West)										
0.00	12.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
19.00	29.00		Sqm	1	10.00	1.35	1.35	1.35		13.50		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
30.50	39.60		Sqm	1	9.10	1.35	1.35	1.35		12.29		
		RHS										
		(From East to West)										
0.00	9.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
15.00	26.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
33.00	41.30		Sqm	1	8.30	1.35	1.35	1.35		11.21		
43.00	45.80		Sqm	1	2.80	1.35	1.35	1.35		3.78		
		LHS										
		(From North to South)										
0.00	10.40		Sqm	1	10.40	1.35	1.35	1.35		14.04		
16.00	18.60		Sqm	1	2.60	1.35	1.35	1.35		3.51		
		RHS										
		(From North to South)										
0.00	8.40		Sqm	1	8.40	1.35	1.35	1.35		11.34		
14.00	18.60		Sqm	1	4.60	1.35	1.35	1.35		6.21		
		5th Cross Road										
		LHS										
		(From North to South)										
0.00	3.40		Sqm	1	3.40	1.35	1.35	1.35		4.59		
7.00	13.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
18.00	29.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
33.00	44.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
46.00	54.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
		RHS										
		(From North to South)										
0.00	5.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
9.00	16.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
19.00	28.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
34.00	45.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
46.50	54.00		Sqm	1	7.50	1.35	1.35	1.35		10.13		
		Hegde Nagara										
		Win Field Garden										
		RHS										
		5th Cross Road (W1941)										
		(From South to North)										
0.00	8.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
13.00	16.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
16.00	29.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
30.00	36.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
44.00	53.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
61.00	74.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
75.00	90.00		Sqm	1	15.00	1.35	1.35	1.35		20.25		
93.00	101.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
105.00	115.00		Sqm	1	10.00	1.35	1.35	1.35		13.50		
122.00	134.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
135.00	142.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
156.00	167.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
170.00	178.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
180.00	185.20		Sqm	1	5.20	1.35	1.35	1.35		7.02		
185.20	188.00		Sqm	1	2.80	1.35	1.35	1.35		3.78		
188.00	190.50		Sqm	1	2.50	1.35	1.35	1.35		3.38		
		LHS										
		(From South to North)										
0.00	8.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
13.00	16.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
16.00	29.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
30.00	36.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
44.00	53.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
61.00	74.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
75.00	90.00		Sqm	1	15.00	1.35	1.35	1.35		20.25		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
93.00	101.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
105.00	115.00		Sqm	1	10.00	1.35	1.35	1.35		13.50		
122.00	134.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
135.00	142.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
156.00	167.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
170.00	178.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
180.00	185.20		Sqm	1	5.20	1.35	1.35	1.35		7.02		
185.20	188.00		Sqm	1	2.80	1.35	1.35	1.35		3.78		
188.00	190.50		Sqm	1	2.50	1.35	1.35	1.35		3.38		
		6th Cross Road (W1935)										
		RHS										
		(From South to North)										
0.00	8.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
11.00	18.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
20.00	25.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
30.00	44.00		Sqm	1	14.00	1.35	1.35	1.35		18.90		
55.00	60.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
71.00	75.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
75.00	90.00		Sqm	1	15.00	1.35	1.35	1.35		20.25		
98.00	104.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
107.00	116.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
119.00	131.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
136.00	144.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
151.80	165.00		Sqm	1	13.20	1.35	1.35	1.35		17.82		
165.00	180.00		Sqm	1	15.00	1.35	1.35	1.35		20.25		
180.00	181.50		Sqm	1	1.50	1.35	1.35	1.35		2.03		
		LHS										
		(From South to North)										
0.00	8.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
11.00	18.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
20.00	25.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
30.00	44.00		Sqm	1	14.00	1.35	1.35	1.35		18.90		
55.00	60.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
71.00	75.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
75.00	90.00		Sqm	1	15.00	1.35	1.35	1.35		20.25		
98.00	104.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
107.00	116.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
119.00	131.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
136.00	144.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
151.80	165.00		Sqm	1	13.20	1.35	1.35	1.35		17.82		
165.00	180.00		Sqm	1	15.00	1.35	1.35	1.35		20.25		
180.00	181.50		Sqm	1	1.50	1.35	1.35	1.35		2.03		
		9th Cross Road										
		RHS										
		(From South to North)										
7.00	12.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
15.90	19.30		Sqm	1	3.40	1.35	1.35	1.35		4.59		
29.00	34.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
43.00	48.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
59.00	66.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
71.00	76.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
87.60	89.60		Sqm	1	2.00	1.35	1.35	1.35		2.70		
94.00	99.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
114.70	118.70		Sqm	1	4.00	1.35	1.35	1.35		5.40		
		LHS										
		(From South to North)										
7.00	12.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
15.90	19.30		Sqm	1	3.40	1.35	1.35	1.35		4.59		
29.00	34.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
43.00	48.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
59.00	66.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
71.00	76.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
87.60	89.60		Sqm	1	2.00	1.35	1.35	1.35		2.70		
94.00	99.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
114.70	118.70		Sqm	1	4.00	1.35	1.35	1.35		5.40		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		Win field Garden										
		8th Cross road										
		LHS										
		(From South to North)										
0.00	8.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
13.20	41.00	No Work	Sqm	1	0.00	1.35	1.35	1.35		0.00		
43.00	47.60		Sqm	1	4.60	1.35	1.35	1.35		6.21		
48.70	59.60	No Work	Sqm	1	0.00	1.35	1.35	1.35		0.00		
63.00	72.10		Sqm	1	9.10	1.35	1.35	1.35		12.29		
77.00	85.60		Sqm	1	8.60	1.35	1.35	1.35		11.61		
89.60	104.70		Sqm	1	15.10	1.35	1.35	1.35		20.39		
107.40	116.70		Sqm	1	9.30	1.35	1.35	1.35		12.56		
119.60	130.80		Sqm	1	11.20	1.35	1.35	1.35		15.12		
136.70	145.50		Sqm	1	8.80	1.35	1.35	1.35		11.88		
		RHS										
		(From South to North)										
0.00	2.30		Sqm	1	2.30	1.35	1.35	1.35		3.11		
4.50	23.40	No Work	Sqm	1	0.00	1.35	1.35	1.35		0.00		
26.40	29.60		Sqm	1	3.20	1.35	1.35	1.35		4.32		
32.20	41.70	No Work	Sqm	1	0.00	1.35	1.35	1.35		0.00		
44.70	54.30		Sqm	1	9.60	1.35	1.35	1.35		12.96		
58.70	69.60		Sqm	1	10.90	1.35	1.35	1.35		14.72		
76.70	84.70		Sqm	1	8.00	1.35	1.35	1.35		10.80		
86.70	95.00		Sqm	1	8.30	1.35	1.35	1.35		11.21		
95.00	114.80	No Work	Sqm	1	0.00	1.35	1.35	1.35		0.00		
117.80	127.80		Sqm	1	10.00	1.35	1.35	1.35		13.50		
129.80	144.80		Sqm	1	15.00	1.35	1.35	1.35		20.25		
144.80	146.00		Sqm	1	1.20	1.35	1.35	1.35		1.62		
		7th Cross Road										
		LHS										
		(From South to North)										
0.00	23.20	No Work	Sqm	1	0.00	1.35	1.35	1.35		0.00		
25.20	33.60		Sqm	1	8.40	1.35	1.35	1.35		11.34		
37.60	47.20	No Work	Sqm	1	0.00	1.35	1.35	1.35		0.00		
51.20	60.30		Sqm	1	9.10	1.35	1.35	1.35		12.29		
63.70	73.20		Sqm	1	9.50	1.35	1.35	1.35		12.83		
78.70	89.90		Sqm	1	11.20	1.35	1.35	1.35		15.12		
95.90	105.70		Sqm	1	9.80	1.35	1.35	1.35		13.23		
109.30	121.60		Sqm	1	12.30	1.35	1.35	1.35		16.61		
122.20	130.20		Sqm	1	8.00	1.35	1.35	1.35		10.80		
130.20	139.00	No Work	Sqm	1	0.00	1.35	1.35	1.35		0.00		
		RHS										
		(From South to North)										
0.00	9.70		Sqm	1	9.70	1.35	1.35	1.35		13.10		
17.00	26.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
32.50	41.00		Sqm	1	8.50	1.35	1.35	1.35		11.48		
47.00	57.00		Sqm	1	10.00	1.35	1.35	1.35		13.50		
64.00	73.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
75.00	90.00		Sqm	1	15.00	1.35	1.35	1.35		20.25		
91.70	103.40		Sqm	1	11.70	1.35	1.35	1.35		15.80		
105.00	120.00		Sqm	1	15.00	1.35	1.35	1.35		20.25		
126.00	133.30		Sqm	1	7.30	1.35	1.35	1.35		9.86		
136.00	148.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
154.30	159.60		Sqm	1	5.30	1.35	1.35	1.35		7.15		
165.00	175.00		Sqm	1	10.00	1.35	1.35	1.35		13.50		
		Katgenahalli										
		Muneshwara Provision Store Beside Road										
		Kalidas Layout										
		3rd Main Road										
		LHS										
		(From North to South)										
0.00	13.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
18.00	24.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
30.00	45.00		Sqm	1	15.00	1.35	1.35	1.35		20.25		
49.00	57.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
60.00	65.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
65.00	73.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
75.00	83.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
89.00	100.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
108.00	113.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
		RHS										
		(From North to South)										
0.00	9.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
14.00	23.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
32.00	45.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
45.00	58.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
60.00	64.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
68.00	72.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
75.00	85.00		Sqm	1	10.00	1.35	1.35	1.35		13.50		
90.00	103.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
109.00	113.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
		Cross Road - 2										
		LHS										
		(From North to South)										
0.00	4.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
8.00	14.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
16.00	20.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
24.00	29.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
30.00	37.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
40.60	44.10		Sqm	1	3.50	1.35	1.35	1.35		4.73		
49.00	60.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
65.00	72.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
75.00	87.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
94.00	104.00		Sqm	1	10.00	1.35	1.35	1.35		13.50		
106.00	119.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
119.50	123.00		Sqm	1	3.50	1.35	1.35	1.35		4.73		
		RHS										
		(From North to South)										
0.00	5.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
10.00	15.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
15.00	20.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
25.00	32.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
36.00	40.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
41.00	46.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
50.00	58.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
63.00	72.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
76.00	87.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
91.00	101.00		Sqm	1	10.00	1.35	1.35	1.35		13.50		
106.00	120.00		Sqm	1	14.00	1.35	1.35	1.35		18.90		
120.00	123.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
		Green Garden Main Road										
		(West to East)										
		LHS										
3.00	12.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
18.60	27.60		Sqm	1	9.00	1.35	1.35	1.35		12.15		
34.20	41.00		Sqm	1	6.80	1.35	1.35	1.35		9.18		
45.00	51.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
55.00	58.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
62.00	72.50		Sqm	1	10.50	1.35	1.35	1.35		14.18		
79.00	88.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
92.40	103.00		Sqm	1	10.60	1.35	1.35	1.35		14.31		
107.00	118.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
121.00	126.90		Sqm	1	5.90	1.35	1.35	1.35		7.97		
127.60	130.00		Sqm	1	2.40	1.35	1.35	1.35		3.24		
133.60	145.00		Sqm	1	11.40	1.35	1.35	1.35		15.39		
145.00	154.30		Sqm	1	9.30	1.35	1.35	1.35		12.56		
154.30	160.00		Sqm	1	5.70	1.35	1.35	1.35		7.69		
161.00	171.40		Sqm	1	10.40	1.35	1.35	1.35		14.04		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		RHS										
		(West to East)										
4.60	13.80		Sqm	1	9.20	1.35	1.35	1.35		12.42		
17.60	27.80		Sqm	1	10.20	1.35	1.35	1.35		13.77		
34.00	41.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
43.60	45.00		Sqm	1	1.40	1.35	1.35	1.35		1.89		
48.00	52.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
54.00	60.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
63.40	73.60		Sqm	1	10.20	1.35	1.35	1.35		13.77		
79.10	88.60		Sqm	1	9.50	1.35	1.35	1.35		12.83		
93.00	103.00		Sqm	1	10.00	1.35	1.35	1.35		13.50		
107.00	118.60		Sqm	1	11.60	1.35	1.35	1.35		15.66		
121.00	126.90		Sqm	1	5.90	1.35	1.35	1.35		7.97		
128.00	130.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
135.10	145.00		Sqm	1	9.90	1.35	1.35	1.35		13.37		
146.00	154.30		Sqm	1	8.30	1.35	1.35	1.35		11.21		
155.20	160.00		Sqm	1	4.80	1.35	1.35	1.35		6.48		
161.00	171.40		Sqm	1	10.40	1.35	1.35	1.35		14.04		
		Cross Road-4										
		(South to North)										
		LHS										
0.00	1.60		Sqm	1	1.60	1.35	1.35	1.35		2.16		
6.00	13.10		Sqm	1	7.10	1.35	1.35	1.35		9.59		
16.00	23.50		Sqm	1	7.50	1.35	1.35	1.35		10.13		
25.00	30.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
31.00	33.70		Sqm	1	2.70	1.35	1.35	1.35		3.65		
		RHS										
		(South to North)										
1.60	11.00		Sqm	1	9.40	1.35	1.35	1.35		12.69		
17.90	22.00		Sqm	1	4.10	1.35	1.35	1.35		5.54		
23.80	30.00		Sqm	1	6.20	1.35	1.35	1.35		8.37		
30.00	33.70		Sqm	1	3.70	1.35	1.35	1.35		5.00		
		Sri Ganga House Road										
		East to West										
		LHS										
1.20	3.80		Sqm	1	2.60	1.35	1.35	1.35		3.51		
6.00	13.20		Sqm	1	7.20	1.35	1.35	1.35		9.72		
18.00	25.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
28.00	30.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
33.00	42.80		Sqm	1	9.80	1.35	1.35	1.35		13.23		
47.90	60.00		Sqm	1	12.10	1.35	1.35	1.35		16.34		
61.40	69.30		Sqm	1	7.90	1.35	1.35	1.35		10.67		
		RHS										
		East to West										
0.00	2.50		Sqm	1	2.50	1.35	1.35	1.35		3.38		
4.30	11.80		Sqm	1	7.50	1.35	1.35	1.35		10.13		
14.30	15.00		Sqm	1	0.70	1.35	1.35	1.35		0.94		
17.60	26.40		Sqm	1	8.80	1.35	1.35	1.35		11.88		
27.90	30.00		Sqm	1	2.10	1.35	1.35	1.35		2.84		
32.80	40.00		Sqm	1	7.20	1.35	1.35	1.35		9.72		
46.80	57.50		Sqm	1	10.70	1.35	1.35	1.35		14.45		
60.00	69.30		Sqm	1	9.30	1.35	1.35	1.35		12.56		
		Cross Road-3										
		(North to South)										
		LHS										
2.30	13.40		Sqm	1	11.10	1.35	1.35	1.35		14.99		
17.60	27.30		Sqm	1	9.70	1.35	1.35	1.35		13.10		
34.00	43.80		Sqm	1	9.80	1.35	1.35	1.35		13.23		
45.00	46.10		Sqm	1	1.10	1.35	1.35	1.35		1.49		
46.10	48.90		Sqm	1	2.80	1.35	1.35	1.35		3.78		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		RHS										
		(North to South)										
0.00	1.70		Sqm	1	1.70	1.35	1.35	1.35		2.30		
3.00	12.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
17.30	28.10		Sqm	1	10.80	1.35	1.35	1.35		14.58		
34.60	43.50		Sqm	1	8.90	1.35	1.35	1.35		12.02		
45.00	46.10		Sqm	1	1.10	1.35	1.35	1.35		1.49		
46.10	48.90		Sqm	1	2.80	1.35	1.35	1.35		3.78		
		Cross Road 2										
		(South to North)										
		LHS										
3.00	10.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
11.80	15.00		Sqm	1	3.20	1.35	1.35	1.35		4.32		
17.90	21.10		Sqm	1	3.20	1.35	1.35	1.35		4.32		
23.40	30.00		Sqm	1	6.60	1.35	1.35	1.35		8.91		
34.00	43.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
47.60	58.00		Sqm	1	10.40	1.35	1.35	1.35		14.04		
63.00	72.60		Sqm	1	9.60	1.35	1.35	1.35		12.96		
77.00	90.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
92.60	100.30		Sqm	1	7.70	1.35	1.35	1.35		10.40		
100.30	102.40		Sqm	1	2.10	1.35	1.35	1.35		2.84		
		RHS										
		(South to North)										
0.00	9.60		Sqm	1	9.60	1.35	1.35	1.35		12.96		
11.80	15.00		Sqm	1	3.20	1.35	1.35	1.35		4.32		
18.00	21.10		Sqm	1	3.10	1.35	1.35	1.35		4.19		
23.40	30.00		Sqm	1	6.60	1.35	1.35	1.35		8.91		
32.70	43.20		Sqm	1	10.50	1.35	1.35	1.35		14.18		
48.60	57.60		Sqm	1	9.00	1.35	1.35	1.35		12.15		
62.40	73.40		Sqm	1	11.00	1.35	1.35	1.35		14.85		
77.90	88.00		Sqm	1	10.10	1.35	1.35	1.35		13.64		
92.60	99.00		Sqm	1	6.40	1.35	1.35	1.35		8.64		
100.30	102.40		Sqm	1	2.10	1.35	1.35	1.35		2.84		
		Cross Road 1										
		(North to South)										
		LHS										
3.40	12.60		Sqm	1	9.20	1.35	1.35	1.35		12.42		
18.60	28.60		Sqm	1	10.00	1.35	1.35	1.35		13.50		
32.80	42.60		Sqm	1	9.80	1.35	1.35	1.35		13.23		
47.00	57.90		Sqm	1	10.90	1.35	1.35	1.35		14.72		
64.60	72.80		Sqm	1	8.20	1.35	1.35	1.35		11.07		
75.60	86.90		Sqm	1	11.30	1.35	1.35	1.35		15.26		
90.00	102.30		Sqm	1	12.30	1.35	1.35	1.35		16.61		
		RHS										
		(North to South)										
0.00	11.60		Sqm	1	11.60	1.35	1.35	1.35		15.66		
18.90	27.60		Sqm	1	8.70	1.35	1.35	1.35		11.75		
32.40	43.60		Sqm	1	11.20	1.35	1.35	1.35		15.12		
48.60	57.90		Sqm	1	9.30	1.35	1.35	1.35		12.56		
63.00	74.30		Sqm	1	11.30	1.35	1.35	1.35		15.26		
78.00	87.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
91.60	102.30		Sqm	1	10.70	1.35	1.35	1.35		14.45		
		Pyramid apartment main road										
		(East to West)										
		LHS										
3.90	12.80		Sqm	1	8.90	1.35	1.35	1.35		12.02		
17.30	27.60		Sqm	1	10.30	1.35	1.35	1.35		13.91		
34.00	43.50		Sqm	1	9.50	1.35	1.35	1.35		12.83		
47.00	56.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0m	74.00		Sqm	1	9.40	1.35	1.35	1.35		12.69		
64.60	81.10		Sqm	1	5.10	1.35	1.35	1.35		6.88		
76.00	90.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
83.00	103.90		Sqm	1	11.40	1.35	1.35	1.35		15.39		
92.50	118.30		Sqm	1	11.10	1.35	1.35	1.35		14.99		
107.20	128.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
120.00												
		Cross Road 3 Near Pyramid apartment										
		(North to South)										
		LHS										
3.60	13.50		Sqm	1	9.90	1.35	1.35	1.35		13.37		
18.70	27.90		Sqm	1	9.20	1.35	1.35	1.35		12.42		
32.20	44.00		Sqm	1	11.80	1.35	1.35	1.35		15.93		
		RHS										
		(North to South)										
0.00	7.90		Sqm	1	7.90	1.35	1.35	1.35		10.67		
15.00	28.00		Sqm	1	13.00	1.35	1.35	1.35		17.55		
34.00	44.00		Sqm	1	10.00	1.35	1.35	1.35		13.50		
		Cross Road 2 Near Pyramid apartment										
		(North to South)										
		LHS										
0.00	3.60		Sqm	1	3.60	1.35	1.35	1.35		4.86		
6.00	13.80		Sqm	1	7.80	1.35	1.35	1.35		10.53		
18.60	27.60		Sqm	1	9.00	1.35	1.35	1.35		12.15		
32.80	40.30		Sqm	1	7.50	1.35	1.35	1.35		10.13		
42.30	45.10		Sqm	1	2.80	1.35	1.35	1.35		3.78		
45.10	48.30		Sqm	1	3.20	1.35	1.35	1.35		4.32		
		RHS										
		(North to South)										
0.00	4.60		Sqm	1	4.60	1.35	1.35	1.35		6.21		
8.00	11.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
17.90	28.60		Sqm	1	10.70	1.35	1.35	1.35		14.45		
30.00	32.80		Sqm	1	2.80	1.35	1.35	1.35		3.78		
34.00	42.30		Sqm	1	8.30	1.35	1.35	1.35		11.21		
42.30	45.10		Sqm	1	2.80	1.35	1.35	1.35		3.78		
46.80	48.30		Sqm	1	1.50	1.35	1.35	1.35		2.03		
		Cross Road 1 Near Pyramid apartment										
		(North to South)										
		LHS										
0.00	4.50		Sqm	1	4.50	1.35	1.35	1.35		6.08		
6.00	11.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
19.30	28.60		Sqm	1	9.30	1.35	1.35	1.35		12.56		
34.60	42.80		Sqm	1	8.20	1.35	1.35	1.35		11.07		
45.00	50.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
52.20	59.00		Sqm	1	6.80	1.35	1.35	1.35		9.18		
62.70	74.20		Sqm	1	11.50	1.35	1.35	1.35		15.53		
79.00	88.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
92.90	103.70		Sqm	1	10.80	1.35	1.35	1.35		14.58		
108.00	119.80		Sqm	1	11.80	1.35	1.35	1.35		15.93		
120.00	127.20		Sqm	1	7.20	1.35	1.35	1.35		9.72		
		RHS										
		(North to South)										
3.20	13.40		Sqm	1	10.20	1.35	1.35	1.35		13.77		
18.00	27.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
32.60	43.70		Sqm	1	11.10	1.35	1.35	1.35		14.99		
48.60	51.70		Sqm	1	3.10	1.35	1.35	1.35		4.19		
54.00	60.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
64.30	74.10		Sqm	1	9.80	1.35	1.35	1.35		13.23		
77.00	87.60		Sqm	1	10.60	1.35	1.35	1.35		14.31		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
m	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
93.00	104.60		Sqm	1	11.60	1.35	1.35	1.35		15.66		
106.00	118.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
121.40	127.20		Sqm	1	5.80	1.35	1.35	1.35		7.83		
		Total Executed Quantity								**5128.52**	**112.41**	**576497.00**
		Tender Quantity								**11256.60**		
Item no. 3		Providing granite slabs of selected quality roughly dressed having a size of 7.5cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete.(P.No.27,I.No.5.31.1)										
		Anand Nagar										
		1st Cross Road										
		Royal ACE Road										
		(From North to South)										
8.00	14.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
17.00	24.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
29.00	32.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
41.00	46.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
56.00	62.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
74.00	75.80		Sqm	1	1.80	1.35	1.35	1.35		2.43		
		M S Nagar										
		11th A Cross/2nd Main Road										
		LHS										
		(From South to North)										
10.40	16.00		Sqm	1	5.60	1.35	1.35	1.35		7.56		
27.00	30.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
42.00	48.50		Sqm	1	6.50	1.35	1.35	1.35		8.78		
58.90	61.00		Sqm	1	2.10	1.35	1.35	1.35		2.84		
		RHS										
		(From South to North)										
13.00	18.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
29.00	32.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
40.00	46.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
55.10	61.00		Sqm	1	5.90	1.35	1.35	1.35		7.97		
		11th Cross Road										
		RHS										
		(From South to North)										
11.00	14.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
22.00	26.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
37.20	41.00		Sqm	1	3.80	1.35	1.35	1.35		5.13		
52.00	60.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
63.00	69.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
73.20	75.00		Sqm	1	1.80	1.35	1.35	1.35		2.43		
80.00	84.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
96.00	105.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
114.00	119.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
146.00	151.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
165.00	166.00		Sqm	1	1.00	1.35	1.35	1.35		1.35		
		10th Cross Road										
		LHS										
		(From North to South)										
9.00	16.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
27.40	29.00		Sqm	1	1.60	1.35	1.35	1.35		2.16		
42.00	45.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
58.00	61.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
66.00	75.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
80.00	90.50		Sqm	1	10.50	1.35	1.35	1.35		14.18		
104.00	105.00		Sqm	1	1.00	1.35	1.35	1.35		1.35		
115.00	118.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
120.00	122.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
131.00	136.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
149.00	154.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
164.70	165.00		Sqm	1	0.30	1.35	1.35	1.35		0.41		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		RHS										
		(From North to South)										
			Sqm	1	9.00	1.35	1.35	1.35		12.15		
6.00	15.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
29.00	32.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
40.00	45.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
52.00	59.00		Sqm	1	4.80	1.35	1.35	1.35		6.48		
71.20	76.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
88.00	90.00		Sqm	1	3.70	1.35	1.35	1.35		5.00		
101.30	105.00		Sqm	1	0.40	1.35	1.35	1.35		0.54		
108.60	109.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
116.00	118.00		Sqm	1	2.50	1.35	1.35	1.35		3.38		
120.50	123.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
135.00	140.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
149.00	154.00		Sqm	1	0.40	1.35	1.35	1.35		0.54		
164.60	165.00											
		10th A Cross										
		LHS										
		(From North to South)										
			Sqm	1	5.00	1.35	1.35	1.35		6.75		
13.00	18.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
26.00	33.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
45.00	48.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
54.00	60.00		Sqm	1	7.90	1.35	1.35	1.35		10.67		
67.10	75.00		Sqm	1	1.00	1.35	1.35	1.35		1.35		
89.00	90.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
102.00	105.00		Sqm	1	7.50	1.35	1.35	1.35		10.13		
116.00	123.50											
		RHS										
		(From North to South)										
			Sqm	1	4.00	1.35	1.35	1.35		5.40		
11.00	15.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
27.00	34.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
42.00	49.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
57.00	62.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
73.00	79.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
86.00	94.00		Sqm	1	3.50	1.35	1.35	1.35		4.73		
107.00	110.50											
		2nd Main Road										
		LHS										
		(From West to East)										
			Sqm	1	4.00	1.35	1.35	1.35		5.40		
13.00	17.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
29.00	33.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
41.00	48.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
56.00	61.00		Sqm	1	6.90	1.35	1.35	1.35		9.32		
72.10	79.00		Sqm	1	3.70	1.35	1.35	1.35		5.00		
114.30	118.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
127.00	129.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
141.00	146.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
184.00	191.00											
		RHS										
		(From West to East)										
			Sqm	1	6.30	1.35	1.35	1.35		8.51		
11.20	17.50		Sqm	1	2.00	1.35	1.35	1.35		2.70		
28.00	30.00		Sqm	1	8.70	1.35	1.35	1.35		11.75		
40.50	49.20		Sqm	1	2.00	1.35	1.35	1.35		2.70		
57.00	59.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
74.00	78.00		Sqm	1	12.00	1.35	1.35	1.35		16.20		
82.00	94.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
103.00	109.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
117.00	122.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
179.00	182.00											

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		2nd Main Road To M S Nagar Road										
		LHS										
		(From West to East)										
9.20	17.00		Sqm	1	7.80	1.35	1.35	1.35		10.53		
28.00	30.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
		LHS										
		(From South to North)										
9.00	16.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
25.00	32.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
44.60	49.00		Sqm	1	4.40	1.35	1.35	1.35		5.94		
56.00	61.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
73.00	77.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
100.50	104.00		Sqm	1	3.50	1.35	1.35	1.35		4.73		
115.00	120.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
129.00	136.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
147.00	152.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
160.00	168.20		Sqm	1	8.20	1.35	1.35	1.35		11.07		
179.00	181.50		Sqm	1	2.50	1.35	1.35	1.35		3.38		
		RHS										
		(From South to North)										
12.00	14.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
22.00	30.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
41.00	49.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
56.00	63.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
71.00	78.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
85.00	89.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
96.00	103.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
118.00	120.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
131.00	135.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
148.00	153.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
163.00	164.50		Sqm	1	1.50	1.35	1.35	1.35		2.03		
178.00	181.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
		LHS										
		(From East to West)										
13.00	19.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
26.00	33.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
44.00	46.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
		RHS										
		(From East to West)										
7.50	14.00		Sqm	1	6.50	1.35	1.35	1.35		8.78		
23.00	31.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
44.50	45.00		Sqm	1	0.50	1.35	1.35	1.35		0.68		
		3A Cross Road										
		LHS										
		(From East to West)										
12.00	19.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
29.00	30.50		Sqm	1	1.50	1.35	1.35	1.35		2.03		
		RHS										
		(From East to West)										
9.00	15.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
26.00	33.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
41.30	43.00		Sqm	1	1.70	1.35	1.35	1.35		2.30		
		LHS										
		(From North to South)										
10.40	16.00		Sqm	1	5.60	1.35	1.35	1.35		7.56		
		RHS										
		(From North to South)										
8.40	14.00		Sqm	1	5.60	1.35	1.35	1.35		7.56		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		5th Cross Road										
		LHS										
		(From North to South)										
3.40	7.00		Sqm	1	3.60	1.35	1.35	1.35		4.86		
13.00	18.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
29.00	33.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
44.00	46.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
		RHS										
		(From North to South)										
5.00	9.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
16.00	19.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
28.00	34.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
45.00	46.50		Sqm	1	1.50	1.35	1.35	1.35		2.03		
		Hegde Nagara										
		Win Field Garden										
		LHS										
		5th Cross Road (W1941)										
		(From South to North)										
8.00	13.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
29.00	30.00		Sqm	1	1.00	1.35	1.35	1.35		1.35		
36.00	44.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
53.00	61.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
74.00	75.00		Sqm	1	1.00	1.35	1.35	1.35		1.35		
90.00	93.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
101.00	105.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
115.00	122.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
134.00	135.00		Sqm	1	1.00	1.35	1.35	1.35		1.35		
142.00	156.00		Sqm	1	14.00	1.35	1.35	1.35		18.90		
167.00	170.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
178.00	180.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
		6th Cross Road (W1935)										
		LHS										
		(From South to North)										
8.00	11.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
18.00	20.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
25.00	30.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
44.00	55.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
60.00	71.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
90.00	98.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
104.00	107.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
116.00	119.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
131.00	136.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
144.00	151.80		Sqm	1	7.80	1.35	1.35	1.35		10.53		
		9th Cross Road										
		LHS										
		(From South to North)										
0.00	7.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
12.00	15.90		Sqm	1	3.90	1.35	1.35	1.35		5.27		
19.30	29.00		Sqm	1	9.70	1.35	1.35	1.35		13.10		
34.00	43.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
48.00	59.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
66.00	71.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
76.00	87.60		Sqm	1	11.60	1.35	1.35	1.35		15.66		
89.60	94.00		Sqm	1	4.40	1.35	1.35	1.35		5.94		
99.00	105.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
105.00	114.70		Sqm	1	9.70	1.35	1.35	1.35		13.10		
118.70	126.90		Sqm	1	8.20	1.35	1.35	1.35		11.07		
126.90	137.90		Sqm	1	11.00	1.35	1.35	1.35		14.85		
		Hegde Nagara										
		Win Field Garden										
		RHS										
		5th Cross Road (W1941)										
		(From South to North)										
8.00	13.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
29.00	30.00		Sqm	1	1.00	1.35	1.35	1.35		1.35		
36.00	44.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
53.00	61.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
74.00	75.00		Sqm	1	1.00	1.35	1.35	1.35		1.35		
90.00	93.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
101.00	105.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
115.00	122.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
134.00	135.00		Sqm	1	1.00	1.35	1.35	1.35		1.35		
142.00	156.00		Sqm	1	14.00	1.35	1.35	1.35		18.90		
167.00	170.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
178.00	180.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
		6th Cross Road (W1935)										
		RHS										
		(From South to North)										
8.00	11.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
18.00	20.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
25.00	30.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
44.00	55.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
60.00	71.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
90.00	98.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
104.00	107.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
116.00	119.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
131.00	136.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
144.00	151.80		Sqm	1	7.80	1.35	1.35	1.35		10.53		
		9th Cross Road										
		RHS										
		(From South to North)										
0.00	7.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
12.00	15.90		Sqm	1	3.90	1.35	1.35	1.35		5.27		
19.30	29.00		Sqm	1	9.70	1.35	1.35	1.35		13.10		
34.00	43.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
48.00	59.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
66.00	71.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
76.00	87.60		Sqm	1	11.60	1.35	1.35	1.35		15.66		
89.60	94.00		Sqm	1	4.40	1.35	1.35	1.35		5.94		
99.00	105.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
105.00	114.70		Sqm	1	9.70	1.35	1.35	1.35		13.10		
118.70	126.90		Sqm	1	8.20	1.35	1.35	1.35		11.07		
126.90	137.90		Sqm	1	11.00	1.35	1.35	1.35		14.85		
		Win field Garden										
		8th Cross road										
		LHS										
		(From South to North)										
8.00	13.20		Sqm	1	5.20	1.35	1.35	1.35		7.02		
41.00	43.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
47.60	48.70		Sqm	1	1.10	1.35	1.35	1.35		1.49		
59.60	63.00		Sqm	1	3.40	1.35	1.35	1.35		4.59		
72.10	77.00		Sqm	1	4.90	1.35	1.35	1.35		6.62		
85.60	89.60		Sqm	1	4.00	1.35	1.35	1.35		5.40		
104.70	107.40		Sqm	1	2.70	1.35	1.35	1.35		3.65		
116.70	119.60		Sqm	1	2.90	1.35	1.35	1.35		3.91		
130.80	136.70		Sqm	1	5.90	1.35	1.35	1.35		7.96		
		RHS										
		(From South to North)										
2.30	4.50		Sqm	1	2.20	1.35	1.35	1.35		2.97		
23.40	26.40		Sqm	1	3.00	1.35	1.35	1.35		4.05		
29.60	32.20		Sqm	1	2.60	1.35	1.35	1.35		3.51		
41.70	44.70		Sqm	1	3.00	1.35	1.35	1.35		4.05		
54.30	58.70		Sqm	1	4.40	1.35	1.35	1.35		5.94		
69.60	76.70		Sqm	1	7.10	1.35	1.35	1.35		9.59		
84.70	86.70		Sqm	1	2.00	1.35	1.35	1.35		2.70		
114.80	117.80		Sqm	1	3.00	1.35	1.35	1.35		4.05		
127.80	129.80		Sqm	1	2.00	1.35	1.35	1.35		2.70		
		7th Cross Road										
		LHS										
		(From South to North)										
23.20	25.20		Sqm	1	2.00	1.35	1.35	1.35		2.70		
33.60	37.60		Sqm	1	4.00	1.35	1.35	1.35		5.40		
47.20	51.20		Sqm	1	4.00	1.35	1.35	1.35		5.40		
60.30	63.70		Sqm	1	3.40	1.35	1.35	1.35		4.59		
73.20	78.70		Sqm	1	5.50	1.35	1.35	1.35		7.43		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
89.90	95.90		Sqm	1	6.00	1.35	1.35	1.35		8.10		
105.70	109.30		Sqm	1	3.60	1.35	1.35	1.35		4.86		
121.60	122.20		Sqm	1	0.60	1.35	1.35	1.35		0.81		
		RHS										
		(From South to North)										
9.70	17.00		Sqm	1	7.30	1.35	1.35	1.35		9.86		
26.00	32.50		Sqm	1	6.50	1.35	1.35	1.35		8.78		
41.00	47.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
57.00	64.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
73.00	75.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
90.00	91.70		Sqm	1	1.70	1.35	1.35	1.35		2.30		
103.40	105.00		Sqm	1	1.60	1.35	1.35	1.35		2.16		
120.00	126.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
133.30	136.00		Sqm	1	2.70	1.35	1.35	1.35		3.64		
148.00	154.30		Sqm	1	6.30	1.35	1.35	1.35		8.51		
159.60	165.00		Sqm	1	5.40	1.35	1.35	1.35		7.29		
		Katgenahalli										
		Muneshwara Provision Store										
		Beside Road										
		Kalidas Layout										
		3rd Main Road										
		LHS										
		(From North to South)										
13.00	18.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
24.00	30.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
45.00	49.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
57.00	60.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
73.00	75.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
83.00	89.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
100.00	108.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
		RHS										
		(From North to South)										
9.00	14.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
23.00	32.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
58.00	60.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
64.00	68.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
72.00	75.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
85.00	90.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
103.00	109.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
		Cross Road - 2										
		LHS										
		(From North to South)										
4.00	8.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
14.00	16.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
20.00	24.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
29.00	30.00		Sqm	1	1.00	1.35	1.35	1.35		1.35		
37.00	40.60		Sqm	1	3.60	1.35	1.35	1.35		4.86		
44.10	49.00		Sqm	1	4.90	1.35	1.35	1.35		6.62		
60.00	65.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
72.00	75.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
87.00	94.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
104.00	106.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
119.00	119.50		Sqm	1	0.50	1.35	1.35	1.35		0.68		
		RHS										
		(From North to South)										
5.00	10.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
15.00	15.00		Sqm	1	0.00	1.35	1.35	1.35		0.00		
20.00	25.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
32.00	36.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
40.00	41.00		Sqm	1	1.00	1.35	1.35	1.35		1.35		
46.00	50.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
58.00	63.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
72.00	76.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
87.00	91.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
101.00	106.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
		Green Garden Main Road										
		(West to East)										
		LHS										
0.00	3.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
12.00	18.60		Sqm	1	6.60	1.35	1.35	1.35		8.91		
27.60	34.20		Sqm	1	6.60	1.35	1.35	1.35		8.91		
41.00	45.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
51.00	55.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
58.00	62.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
72.50	79.00		Sqm	1	6.50	1.35	1.35	1.35		8.78		
88.00	92.40		Sqm	1	4.40	1.35	1.35	1.35		5.94		
103.00	107.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
118.00	121.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
126.90	127.60		Sqm	1	0.70	1.35	1.35	1.35		0.94		
130.00	133.60		Sqm	1	3.60	1.35	1.35	1.35		4.86		
		RHS										
		(West to East)										
0.00	4.60		Sqm	1	4.60	1.35	1.35	1.35		6.21		
13.80	17.60		Sqm	1	3.80	1.35	1.35	1.35		5.13		
27.80	34.00		Sqm	1	6.20	1.35	1.35	1.35		8.37		
41.00	43.60		Sqm	1	2.60	1.35	1.35	1.35		3.51		
45.00	48.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
52.00	54.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
60.00	63.40		Sqm	1	3.40	1.35	1.35	1.35		4.59		
73.60	79.10		Sqm	1	5.50	1.35	1.35	1.35		7.43		
88.60	93.00		Sqm	1	4.40	1.35	1.35	1.35		5.94		
103.00	107.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
118.60	121.00		Sqm	1	2.40	1.35	1.35	1.35		3.24		
126.90	128.00		Sqm	1	1.10	1.35	1.35	1.35		1.48		
130.00	135.10		Sqm	1	5.10	1.35	1.35	1.35		6.88		
145.00	146.00		Sqm	1	1.00	1.35	1.35	1.35		1.35		
154.30	155.20		Sqm	1	0.90	1.35	1.35	1.35		1.21		
160.00	161.00		Sqm	1	1.00	1.35	1.35	1.35		1.35		
		Cross Road-4										
		(South to North)										
		LHS										
1.60	6.00		Sqm	1	4.40	1.35	1.35	1.35		5.94		
13.10	16.00		Sqm	1	2.90	1.35	1.35	1.35		3.92		
23.50	25.00		Sqm	1	1.50	1.35	1.35	1.35		2.03		
30.00	31.00		Sqm	1	1.00	1.35	1.35	1.35		1.35		
		RHS										
		(South to North)										
0.00	1.60		Sqm	1	1.60	1.35	1.35	1.35		2.16		
11.00	17.90		Sqm	1	6.90	1.35	1.35	1.35		9.32		
22.00	23.80		Sqm	1	1.80	1.35	1.35	1.35		2.43		
		Sri Ganga House Road										
		East to West										
		LHS										
0.00	1.20		Sqm	1	1.20	1.35	1.35	1.35		1.62		
3.80	6.00		Sqm	1	2.20	1.35	1.35	1.35		2.97		
13.20	18.00		Sqm	1	4.80	1.35	1.35	1.35		6.48		
25.00	28.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
30.00	33.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
42.80	47.90		Sqm	1	5.10	1.35	1.35	1.35		6.89		
60.00	61.40		Sqm	1	1.40	1.35	1.35	1.35		1.89		
		RHS										
		East to West										
2.50	4.30		Sqm	1	1.80	1.35	1.35	1.35		2.43		
11.80	14.30		Sqm	1	2.50	1.35	1.35	1.35		3.38		
15.00	17.60		Sqm	1	2.60	1.35	1.35	1.35		3.51		
26.40	27.90		Sqm	1	1.50	1.35	1.35	1.35		2.03		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
30.00	32.80		Sqm	1	2.80	1.35	1.35	1.35		3.78		
40.00	46.80		Sqm	1	6.80	1.35	1.35	1.35		9.18		
		Cross Road-3										
		(North to South)										
		LHS										
0.00	2.30		Sqm	1	2.30	1.35	1.35	1.35		3.11		
13.40	17.60		Sqm	1	4.20	1.35	1.35	1.35		5.67		
27.30	34.00		Sqm	1	6.70	1.35	1.35	1.35		9.05		
43.80	45.00		Sqm	1	1.20	1.35	1.35	1.35		1.62		
		RHS										
		(North to South)										
1.70	3.00		Sqm	1	1.30	1.35	1.35	1.35		1.76		
12.00	17.30		Sqm	1	5.30	1.35	1.35	1.35		7.16		
28.10	34.60		Sqm	1	6.50	1.35	1.35	1.35		8.78		
43.50	45.00		Sqm	1	1.50	1.35	1.35	1.35		2.03		
		Cross Road 2										
		(South to North)										
		LHS										
0.00	3.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
10.00	11.80		Sqm	1	1.80	1.35	1.35	1.35		2.43		
15.00	17.90		Sqm	1	2.90	1.35	1.35	1.35		3.92		
21.10	23.40		Sqm	1	2.30	1.35	1.35	1.35		3.11		
30.00	34.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
43.00	47.60		Sqm	1	4.60	1.35	1.35	1.35		6.21		
58.00	63.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
72.60	77.00		Sqm	1	4.40	1.35	1.35	1.35		5.94		
90.00	92.60		Sqm	1	2.60	1.35	1.35	1.35		3.51		
		RHS										
		(South to North)										
9.60	11.80		Sqm	1	2.20	1.35	1.35	1.35		2.97		
15.00	18.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
21.10	23.40		Sqm	1	2.30	1.35	1.35	1.35		3.11		
30.00	32.70		Sqm	1	2.70	1.35	1.35	1.35		3.65		
43.20	48.60		Sqm	1	5.40	1.35	1.35	1.35		7.29		
57.60	62.40		Sqm	1	4.80	1.35	1.35	1.35		6.48		
73.40	77.90		Sqm	1	4.50	1.35	1.35	1.35		6.08		
88.00	92.60		Sqm	1	4.60	1.35	1.35	1.35		6.21		
99.00	100.30		Sqm	1	1.30	1.35	1.35	1.35		1.76		
		Cross Road 1										
		(North to South)										
		LHS										
0.00	3.40											
12.60	18.60		Sqm	1	6.00	1.35	1.35	1.35		8.10		
28.60	32.80		Sqm	1	4.20	1.35	1.35	1.35		5.67		
42.60	47.00		Sqm	1	4.40	1.35	1.35	1.35		5.94		
57.90	64.60		Sqm	1	6.70	1.35	1.35	1.35		9.04		
72.80	75.60		Sqm	1	2.80	1.35	1.35	1.35		3.78		
86.90	90.00		Sqm	1	3.10	1.35	1.35	1.35		4.18		
		RHS										
		(North to South)										
11.60	18.90		Sqm	1	7.30	1.35	1.35	1.35		9.86		
27.60	32.40		Sqm	1	4.80	1.35	1.35	1.35		6.48		
43.60	48.60		Sqm	1	5.00	1.35	1.35	1.35		6.75		
57.90	63.00		Sqm	1	5.10	1.35	1.35	1.35		6.89		
74.30	78.00		Sqm	1	3.70	1.35	1.35	1.35		5.00		
87.00	91.60		Sqm	1	4.60	1.35	1.35	1.35		6.21		
		Pyramid apartment main road										
		(East to West)										
		LHS										
0.00	3.90											
12.80	17.30		Sqm	1	4.50	1.35	1.35	1.35		6.08		
27.60	34.00		Sqm	1	6.40	1.35	1.35	1.35		8.64		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
43.50	47.00		Sqm	1	3.50	1.35	1.35	1.35		4.73		
56.00	64.60		Sqm	1	8.60	1.35	1.35	1.35		11.61		
74.00	76.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
81.10	83.00		Sqm	1	1.90	1.35	1.35	1.35		2.57		
90.00	92.50		Sqm	1	2.50	1.35	1.35	1.35		3.38		
103.90	107.20		Sqm	1	3.30	1.35	1.35	1.35		4.46		
		Cross Road 3 Near Pyramid apartment										
		(North to South)										
		LHS										
0.00	3.60		Sqm	1	3.60	1.35	1.35	1.35		4.86		
13.50	18.70		Sqm	1	5.20	1.35	1.35	1.35		7.02		
27.90	32.20		Sqm	1	4.30	1.35	1.35	1.35		5.81		
		RHS										
		(North to South)										
7.90	15.00		Sqm	1	7.10	1.35	1.35	1.35		9.59		
28.00	34.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
		Cross Road 2 Near Pyramid apartment										
		(North to South)										
		LHS										
3.60	6.00		Sqm	1	2.40	1.35	1.35	1.35		3.24		
13.80	18.60		Sqm	1	4.80	1.35	1.35	1.35		6.48		
27.60	32.80		Sqm	1	5.20	1.35	1.35	1.35		7.02		
40.30	42.30		Sqm	1	2.00	1.35	1.35	1.35		2.70		
		RHS										
		(North to South)										
4.60	8.00		Sqm	1	3.40	1.35	1.35	1.35		4.59		
11.00	17.90		Sqm	1	6.90	1.35	1.35	1.35		9.32		
28.60	30.00		Sqm	1	1.40	1.35	1.35	1.35		1.89		
32.80	34.00		Sqm	1	1.20	1.35	1.35	1.35		1.62		
		Cross Road 1 Near Pyramid apartment										
		(North to South)										
		LHS										
4.50	6.00		Sqm	1	1.50	1.35	1.35	1.35		2.03		
11.00	19.30		Sqm	1	8.30	1.35	1.35	1.35		11.21		
28.60	34.60		Sqm	1	6.00	1.35	1.35	1.35		8.10		
42.80	45.00		Sqm	1	2.20	1.35	1.35	1.35		2.97		
50.00	52.20		Sqm	1	2.20	1.35	1.35	1.35		2.97		
59.00	62.70		Sqm	1	3.70	1.35	1.35	1.35		5.00		
74.20	79.00		Sqm	1	4.80	1.35	1.35	1.35		6.48		
88.00	92.90		Sqm	1	4.90	1.35	1.35	1.35		6.62		
		RHS										
		(North to South)										
0.00	3.20		Sqm	1	3.20	1.35	1.35	1.35		4.32		
13.40	18.00		Sqm	1	4.60	1.35	1.35	1.35		6.21		
27.00	32.60		Sqm	1	5.60	1.35	1.35	1.35		7.56		
43.70	48.60		Sqm	1	4.90	1.35	1.35	1.35		6.62		
51.70	54.00		Sqm	1	2.30	1.35	1.35	1.35		3.11		
60.00	64.30		Sqm	1	4.30	1.35	1.35	1.35		5.81		
74.10	77.00		Sqm	1	2.90	1.35	1.35	1.35		3.92		
87.60	93.00		Sqm	1	5.40	1.35	1.35	1.35		7.29		
104.60	106.00		Sqm	1	1.40	1.35	1.35	1.35		1.89		
		Total Executed Quantity								**2408.27**	**749.42**	**1804802.00**
		Tender Quantity								**5378.02**		
Item no. 4		KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs. with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, I.No. 4.3)										
		C.C Drain										
		Palanahalli Road										
		L.H.S										
		West To East										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90.00	105.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105.00	112.35		Cum	1	7.35	1.10	1.10	1.10	0.15	1.21		
112.35	116.75	Culvert	Cum	0	0.00	1.10	1.10	1.10	0.15	0.00		
116.75	126.75		Cum	1	10.00	1.10	1.10	1.10	0.15	1.65		
		R.H.S										
		West To East										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60.00	75.10		Cum	1	15.10	1.10	1.10	1.10	0.15	2.49		
75.10	80.75	Culvert	Cum	0	0.00	1.10	1.10	1.10	0.15	0.00		
80.75	84.90		Cum	1	4.15	1.10	1.10	1.10	0.15	0.68		
84.90	90.35	No Work	Cum	0	0.00	1.10	1.10	1.10	0.15	0.00		
90.35	105.35		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105.35	120.35		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
120.35	125.35		Cum	1	5.00	1.10	1.10	1.10	0.15	0.83		
125.35	130.15	Existing S.S.M Culvert	Cum	0	0.00	1.10	1.10	1.10	0.15	0.00		
		Katgenahalli, Venkatappa Building To Medical Shop										
		R.H.S										
		West To East										
0.00	14.90		Cum	1	14.90	1.10	1.10	1.10	0.15	2.46		
14.90	21.50		Cum	1	6.60	1.10	1.10	1.10	0.15	1.09		
21.50	31.70		Cum	1	10.20	1.10	1.10	1.10	0.15	1.68		
31.70	46.70		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
46.70	50.70		Cum	1	4.00	1.10	1.10	1.10	0.15	0.66		
		From Kamal House To Shiva House										
		R.H.S										
		North To South										
0.00	9.20		Cum	1	9.20	1.00	1.00	1.00	0.15	1.38		
		R.H.S										
		East To West										
0.00	15.00		Cum	1	15.00	1.00	1.00	1.00	0.15	2.25		
15.00	30.00		Cum	1	15.00	1.00	1.00	1.00	0.15	2.25		
30.00	33.75		Cum	1	3.75	1.00	1.00	1.00	0.15	0.56		
		R.H.S										
		South To North										
0.00	9.40		Cum	1	9.40	1.00	1.00	1.00	0.15	1.41		
		Sri Channa Keshava Swami Provision Store										
		L.H.S										
		North To South										
0.00	14.50		Cum	1	14.50	0.95	0.95	0.95	0.15	2.07		
		L.H.S										
		East To West										
0.00	15.00	0.75m Drain	Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
15.00	26.20		Cum	1	11.20	0.95	0.95	0.95	0.15	1.60		
		L.H.S										
		West To East										
0.00	4.90		Cum	1	4.90	0.95	0.95	0.95	0.15	0.70		
		L.H.S										
		South To North										
0.00	8.50		Cum	1	8.50	0.95	0.95	0.95	0.15	1.21		
		L.H.S										
		West To East										
0.00	13.20		Cum	1	13.20	0.95	0.95	0.95	0.15	1.88		
		Cross Road										
		South To North										
0.00	15.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
15.00	30.20		Cum	1	15.20	0.95	0.95	0.95	0.15	2.17		
		Cross Road 1										
		LHS										
		(From East to West)										
0.00	12.10		Cum	1	12.10	1.00	1.00	1.00	0.15	1.82		
12.10	27.10		Cum	1	15.00	1.00	1.00	1.00	0.15	2.25		
27.10	30.00		Cum	1	2.90	1.00	1.00	1.00	0.15	0.44		
		RHS										
		(From East to West)										
0.00	15.00		Cum	1	15.00	1.00	1.00	1.00	0.15	2.25		
15.00	29.80		Cum	1	14.80	1.00	1.00	1.00	0.15	2.22		
		Cross Road 2										
		LHS										
		(From East to West)										
0.00	15.00		Cum	1	15.00	1.00	1.00	1.00	0.15	2.25		
15.00	30.00		Cum	1	15.00	1.00	1.00	1.00	0.15	2.25		
30.00	31.70		Cum	1	1.70	1.00	1.00	1.00	0.15	0.26		
		Culvert										
		Sri Channa Keshava Swami Provision Store										
		RHS										
		East To West										
			Cum	1	6.30	1.40	1.40	1.40	0.15	1.32		
		Palanahalli main Road										
		LHS	Cuim	1	4.40	1.40	1.40	1.40	0.15	0.92		
		RHS	Cuim	1	5.65	1.40	1.40	1.40	0.15	1.19		
		MS Nagar										
		2nd main Bande Road										
			Cum	1	8.40	1.30	1.30	1.30	0.15	1.64		
		Masjid Road										
			Cum	1	3.60	1.60	1.60	1.60	0.15	0.86		
		Kodigenahalli government School Road										
			Cum	1	6.70	1.30	1.30	1.30	0.15	1.31		
		Total Executed Quantity								**90.12**	**5675.99**	**511508.00**
		Tender Quantity								**103.74**		
Item no. 5		Providing laying plain/ reinforced cement concrete for side Drains Using M20 nominal mix Concrete with OPC at 300kgs.With 20mm and Down size granite metal coarse aggregate at 0.69cum and fine aggregate at 0.43cum Machne mixed, well compacted for wall and Bottom including centering shuttering,cost of materials,HOM of Machinery,Curing Etc.,Complete Excluding cost of Steel as per morth MORTH specification No. 1500, 1700, 2200. Including Cost of material, Labour, HOM complete as per Specification-WALL & Bottom thickness 15Cm(Item No 37.59.2 page no 271)											
		C.C Drain										
		Bottom Raft										
		Palanahalli Road										
		L.H.S										
		West To East										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45.00	60.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60.00	75.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75.00	90.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
90.00	105.00		Cum	1	15.00	1.00	1.00	1.00	0.15	2.25		
105.00	112.35		Cum	1	7.35	1.00	1.00	1.00	0.15	1.10		
112.35	116.75	Culvert	Cum	0	0.00	1.00	1.00	1.00	0.15	0.00		
116.75	126.75		Cum	1	10.00	1.00	1.00	1.00	0.15	1.50		
		R.H.S										
		West To East										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45.00	60.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60.00	75.10		Cum	1	15.10	0.90	0.90	0.90	0.15	2.04		
75.10	80.75	Culvert	Cum	0	0.00	0.90	0.90	0.90	0.15	0.00		
80.75	84.90		Cum	1	4.15	0.90	0.90	0.90	0.15	0.56		
84.90	90.35	No Work	Cum	0	0.00	0.90	0.90	0.90	0.15	0.00		
90.35	105.35		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
105.35	120.35		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
120.35	125.35		Cum	1	5.00	0.90	0.90	0.90	0.15	0.68		
125.35	130.15	Existing S.S.M Culvert	Cum	0	0.00	0.90	0.90	0.90	0.15	0.00		
		Katgenahalli, Venkatappa Building To Medical Shop										
		R.H.S										
		West To East										
0.00	14.90		Cum	1	14.90	0.90	0.90	0.90	0.15	2.01		
14.90	21.50		Cum	1	6.60	0.90	0.90	0.90	0.15	0.89		
21.50	31.70		Cum	1	10.20	0.90	0.90	0.90	0.15	1.38		
31.70	46.70		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
46.70	50.70		Cum	1	4.00	0.90	0.90	0.90	0.15	0.54		
		From Kamal House To Shiva House										
		R.H.S										
		North To South										
0.00	9.20		Cum	1	9.20	0.90	0.90	0.90	0.15	1.24		
		R.H.S										
		East To West										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30.00	33.75		Cum	1	3.75	0.90	0.90	0.90	0.15	0.51		
		R.H.S										
		South To North										
0.00	9.40		Cum	1	9.40	0.90	0.90	0.90	0.15	1.27		
		Sri Channa Keshava Swami Provision Store										
		L.H.S										
		North To South										
0.00	14.50		Cum	1	14.50	0.75	0.75	0.75	0.15	1.63		
		L.H.S										
		East To West										
0.00	15.00	0.75m Drain	Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
15.00	26.20		Cum	1	11.20	0.75	0.75	0.75	0.15	1.26		
		L.H.S										
		West To East										
0.00	4.90		Cum	1	4.90	0.75	0.75	0.75	0.15	0.55		
		L.H.S										
		South To North										
0.00	8.50		Cum	1	8.50	0.75	0.75	0.75	0.15	0.96		
		L.H.S										
		West To East										
0.00	13.20		Cum	1	13.20	0.75	0.75	0.75	0.15	1.49		
		Cross Road										
		South To North										
0.00	15.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
15.00	30.20		Cum	1	15.20	0.75	0.75	0.75	0.15	1.71		
		Cross Road 1										
		LHS										
		(From East to West)										
0.00	12.10		Cum	1	12.10	0.90	0.90	0.90	0.15	1.63		
12.10	27.10		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
27.10	30.00		Cum	1	2.90	0.90	0.90	0.90	0.15	0.39		
		RHS										
		(From East to West)										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
15.00	29.80		Cum	1	14.80	0.90	0.90	0.90	0.15	2.00		
		Cross Road 2										
		LHS										
		(From East to West)										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30.00	31.70		Cum	1	1.70	0.90	0.90	0.90	0.15	0.23		
		Side wall										
		Palanahalli Road										
		L.H.S										
		West To East										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30.00	45.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45.00	60.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60.00	75.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75.00	90.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90.00	105.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105.00	112.35		Cum	2	7.35	0.15	0.15	0.15	0.60	1.32		
112.35	116.75	Culvert	Cum	0	0.00	0.15	0.15	0.15	0.60	0.00		
116.75	126.75		Cum	2	10.00	0.15	0.15	0.15	0.60	1.80		
		R.H.S										
		West To East										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30.00	45.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45.00	60.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60.00	75.10		Cum	2	15.10	0.15	0.15	0.15	0.60	2.72		
75.10	80.75	Culvert	Cum	0	0.00	0.15	0.15	0.15	0.60	0.00		
80.75	84.90		Cum	2	4.15	0.15	0.15	0.15	0.60	0.75		
84.90	90.35	No Work	Cum	0	0.00	0.15	0.15	0.15	0.60	0.00		
90.35	105.35		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105.35	120.35		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
120.35	125.35		Cum	2	5.00	0.15	0.15	0.15	0.60	0.90		
125.35	130.15	Existing S.S.M Culvert	Cum	0	0.00	0.15	0.15	0.15	0.60	0.00		
		Katgenahalli, Venkatappa Building To Medical Shop										
		R.H.S										
		West To East										
0.00	14.90		Cum	2	14.90	0.15	0.15	0.15	0.15	0.67		
14.90	21.50		Cum	2	6.60	0.15	0.15	0.15	0.50	0.99		
21.50	31.70		Cum	2	10.20	0.15	0.15	0.15	0.50	1.53		
31.70	46.70		Cum	2	15.00	0.15	0.15	0.15	0.50	2.25		
46.70	50.70		Cum	2	4.00	0.15	0.15	0.15	0.50	0.60		
		From Kamal House To Shiva House										
		R.H.S										
		North To South										
0.00	9.20		Cum	2	9.20	0.15	0.15	0.15	0.45	1.24		
		R.H.S										
		East To West										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.45	2.03		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.45	2.03		
30.00	33.75		Cum	2	3.75	0.15	0.15	0.15	0.45	0.51		
		R.H.S										
		South To North										
0.00	9.40		Cum	2	9.40	0.15	0.15	0.15	0.45	1.27		
		Sri Channa Keshava Swami Provision Store										
		L.H.S										
		North To South										
0.00	14.50		Cum	2	14.50	0.15	0.15	0.15	0.45	1.96		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		L.H.S										
		East To West										
		0.75m Drain										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.45	2.03		
15.00	26.20		Cum	2	11.20	0.15	0.15	0.15	0.45	1.51		
		L.H.S										
		West To East								0.00		
0.00	4.90		Cum	2	4.90	0.15	0.15	0.15	0.45	0.66		
		L.H.S										
		South To North										
0.00	8.50		Cum	2	8.50	0.15	0.15	0.15	0.45	1.15		
		L.H.S										
		West To East										
0.00	13.20		Cum	2	13.20	0.15	0.15	0.15	0.45	1.78		
		Cross Road										
		South To North										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.45	2.03		
15.00	30.20		Cum	2	15.20	0.15	0.15	0.15	0.45	2.05		
		Cross Road 1										
		LHS										
		(From East to West)										
0.00	12.10		Cum	2	12.10	0.15	0.15	0.15	0.60	2.18		
12.10	27.10		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
27.10	30.00		Cum	2	2.90	0.15	0.15	0.15	0.60	0.52		
		RHS										
		(From East to West)										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15.00	29.80		Cum	2	14.80	0.15	0.15	0.15	0.60	2.66		
		Cross Road 2										
		LHS										
		(From East to West)										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30.00	31.70		Cum	2	1.70	0.15	0.15	0.15	0.60	0.31		
									Sub total	**154.99**		
		Culvert										
		Bottom Raft										
		Sri Channa Keshava Swami Provision Store										
		RHS										
		East To West										
			Cum	1	6.30	1.20	1.20	1.20	0.20	1.51		
		Palanahalli main Road										
		LHS	Cuim	1	4.40	1.20	1.20	1.20	0.20	1.06		
		RHS	Cuim	1	5.65	1.20	1.20	1.20	0.20	1.36		
		ms nagar										
		2nd main Bande Road										
			Cum	1	8.40	1.20	1.20	1.20	0.20	2.02		
		Masjid Road										
			Cum	1	3.60	1.50	1.50	1.50	0.20	1.08		
		Kodigenahalli government School Road										
			Cum	1	6.70	1.20	1.20	1.20	0.20	1.61		
		Side Wall										
		Sri Channa Keshava Swami Provision Store										
		RHS										
		East To West										
			Cum	2	6.30	0.20	0.20	0.20	0.60	1.51		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Palanahalli main Road										
		LHS	Cuim	2	4.40	0.20	0.20	0.20	0.60	1.06		
		RHS	Cuim	2	5.65	0.20	0.20	0.20	0.60	1.36		
		ms nagar										
		2nd main Bande Road										
			Cum	2	8.40	0.20	0.20	0.20	0.90	3.02		
		Masjid Road										
			Cum	2	3.60	0.20	0.20	0.20	0.90	1.30		
		Kodigenahalli government School Road										
			Cum	2	6.70	0.20	0.20	0.20	0.90	2.41		
									Sub total	**19.28**		
		Total Executed Quantity								**174.27**	**7497.22**	**1306552.00**
		Tender Quantity								**208.73**		
Item no. 6		KSRB M2200-6 Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. MORTH Specification NO.1600&2200Specification No. Pg No.229 Item No.28.8.2										
		For Drain	Tonne		154.99			0.06		**9.34**		
		For Culvert	Tonne		19.28			0.09		**1.76**		
		Total Executed Quantity								**11.10**	**80948.07**	**898349.00**
		Tender Quantity								**14.04**		
Item no. 7		Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift, transportation etc ,copmplete. (Data Rate)										
		Palanahalli Road										
		L.H.S										
		West To East										
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	30.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30.00	45.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
45.00	60.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
60.00	75.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
75.00	90.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
90.00	105.00		Sqm	1	15.00	1.00	1.00	1.00		15.00		
105.00	112.35		Sqm	1	7.35	1.00	1.00	1.00		7.35		
112.35	116.75	Culvert	Sqm	0	0.00	1.00	1.00	1.00		0.00		
116.75	126.75		Sqm	1	10.00	1.00	1.00	1.00		10.00		
		R.H.S										
		West To East										
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	30.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30.00	45.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
45.00	60.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
60.00	75.10		Sqm	1	15.10	0.90	0.90	0.90		13.59		
75.10	80.75	Culvert	Sqm	0	0.00	0.90	0.90	0.90		0.00		
80.75	84.90		Sqm	1	4.15	0.90	0.90	0.90		3.74		
84.90	90.35	No Work	Sqm	0	0.00	0.90	0.90	0.90		0.00		
90.35	105.35		Sqm	1	15.00	0.90	0.90	0.90		13.50		
105.35	120.35		Sqm	1	15.00	0.90	0.90	0.90		13.50		
120.35	125.35		Sqm	1	5.00	0.90	0.90	0.90		4.50		
125.35	130.15	Existing S.S.M Culvert Coping,Slabs	Sqm	0	0.00	0.90	0.90	0.90				
		Katgenahalli, Venkatappa Building To Medical Shop										
		R.H.S										
		West To East										
0.00	14.90		Sqm	1	14.90	0.90	0.90	0.90		13.41		
14.90	21.50		Sqm	1	6.60	0.90	0.90	0.90		5.94		
21.50	31.70		Sqm	1	10.20	0.90	0.90	0.90		9.18		
31.70	46.70		Sqm	1	15.00	0.90	0.90	0.90		13.50		
46.70	50.70		Sqm	1	4.00	0.90	0.90	0.90		3.60		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		From Kamal House To Shiva House										
		R.H.S										
		North To South										
0.00	9.20		Sqm	1	9.20	0.90	0.90	0.90		8.28		
		R.H.S										
		East To West										
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	30.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30.00	33.75		Sqm	1	3.75	0.90	0.90	0.90		3.38		
		R.H.S										
		South To North										
0.00	9.40		Sqm	1	9.40	0.90	0.90	0.90		8.46		
		Sri Channa Keshava Swami Provision Store										
		L.H.S										
		North To South										
0.00	14.50		Sqm	1	14.50	0.75	0.75	0.75		10.88		
		L.H.S										
		East To West										
0.00	15.00	0.75m Drain	Sqm	1	15.00	0.75	0.75	0.75		11.25		
15.00	26.20		Sqm	1	11.20	0.75	0.75	0.75		8.40		
		L.H.S										
		West To East										
0.00	4.90		Sqm	1	4.90	0.75	0.75	0.75		3.68		
		L.H.S										
		South To North										
0.00	8.50		Sqm	1	8.50	0.75	0.75	0.75		6.38		
0.00	0.00	L.H.S										
0.00	0.00	West To East										
0.00	13.20		Sqm	1	13.20	0.75	0.75	0.75		9.90		
		Cross Road										
		South To North										
0.00	15.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15.00	30.20		Sqm	1	15.20	0.75	0.75	0.75		11.40		
		Cross Road 1										
		LHS										
		(From East to West)										
0.00	12.10	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
12.10	27.10		Sqm	1	15.00	0.90	0.90	0.90		13.50		
27.10	30.00		Sqm	1	2.90	0.90	0.90	0.90		2.61		
		RHS										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	29.80		Sqm	1	14.80	0.90	0.90	0.90		13.32		
		Vinayak nagar										
		6thB Main Road										
		LHS										
		South to North										
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	28.70		Sqm	1	13.70	0.90	0.90	0.90		12.33		
28.70	43.70	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
43.70	55.30	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
55.30	62.60		Sqm	1	7.30	0.90	0.90	0.90		6.57		
62.60	77.60	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
77.60	90.00	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
90.00	93.70		Sqm	1	3.70	0.90	0.90	0.90		3.33		
93.70	99.10	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
99.10	107.40		Sqm	1	8.30	0.90	0.90	0.90		7.47		
		LHS										
		South to North										
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	16.10		Sqm	1	1.10	0.90	0.90	0.90		0.99		
16.10	31.10	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
31.10	46.60	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
46.60	56.40		Sqm	1	9.80	0.90	0.90	0.90		8.82		
56.40	61.50		Sqm	1	5.10	0.90	0.90	0.90		4.59		
61.50	68.20	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
68.20	72.00		Sqm	1	3.80	0.90	0.90	0.90		3.42		
72.00	75.40	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
75.40	90.40		Sqm	1	15.00	0.90	0.90	0.90		13.50		
90.40	105.40		Sqm	1	15.00	0.90	0.90	0.90		13.50		
105.40	107.60		Sqm	1	2.20	0.90	0.90	0.90		1.98		
		Missing Cover Slab	Sqm	93	0.90	0.60	0.60	0.60		50.22		
		Total Executed Quantity								**578.70**	**1941.22**	**1123375.00**
		Tender Quantity								**647.28**		
Item no. 8		Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge										
		Sri Channa Keshava Swami Provision Store										
		RHS										
		East To West										
			Sqm	1	6.30	1.20	1.20	1.20		7.56		
		Palanahalli main Road										
		LHS	Sqm	1	4.40	1.20	1.20	1.20		5.28		
		RHS	Sqm	1	5.65	1.20	1.20	1.20		6.78		
		ms nagar										
		2nd main Bande Road										
			Sqm	1	8.30	1.16	1.16	1.16		9.63		
		Masjid Road										
			Sqm	1	3.50	1.46	1.46	1.46		5.11		
		Kodigenahalli government School Road										
			Sqm	1	6.40	1.16	1.16	1.16		7.42		
		Total Executed Quantity								**41.78**	**5472.18**	**228639.00**
		Tender Quantity								**120.30**		
Item no. 9		Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specification and directions of the Engineer in charge.										
		Palanahalli										
		For Cut Portions										
		(From West to East)										
0.00	8.40		Cum	1	8.40	1.30	1.30	1.30	0.20	2.18		
8.40	24.00		Cum	1	15.60	2.50	3.10	2.80	0.20	8.74		
24.00	27.60	No Work	Cum	1	0.00	0.00	0.00	0.00	0.20	0.00		
27.60	42.60		Cum	1	15.00	3.35	2.52	2.94	0.20	8.81		
42.60	45.00		Cum	1	2.40	2.52	2.50	2.51	0.20	1.20		
45.00	60.00		Cum	1	15.00	2.50	2.50	2.50	0.20	7.50		
60.00	75.00		Cum	1	15.00	2.50	1.95	2.23	0.20	6.68		
75.00	90.00		Cum	1	15.00	1.95	2.50	2.23	0.20	6.68		
90.00	105.00		Cum	1	15.00	2.50	1.85	2.18	0.20	6.53		
105.00	115.80		Cum	1	10.80	1.85	3.00	2.43	0.20	5.24		
115.80	119.00		Cum	1	3.20	3.00	4.30	3.65	0.20	2.34		
119.00	125.50		Cum	1	6.50	1.30	0.85	1.08	0.20	1.40		
125.50	132.60	No Work	Cum	1	0.00	0.00	0.00	0.00	0.20	0.00		
132.60	135.60		Cum	1	3.00	1.50	1.65	1.58	0.20	0.95		
135.60	150.60		Cum	1	15.00	1.65	1.20	1.43	0.20	4.28		
150.60	152.60		Cum	1	2.00	4.10	4.10	4.10	0.20	1.64		
152.60	159.50		Cum	1	6.90	2.10	2.10	2.10	0.20	2.90		
159.50	174.50		Cum	1	15.00	2.10	1.00	1.55	0.20	4.65		
174.50	183.90		Cum	1	9.40	1.00	1.00	1.00	0.20	1.88		
183.90	198.90		Cum	1	15.00	1.00	1.00	1.00	0.20	3.00		
198.90	213.90		Cum	1	15.00	1.00	1.00	1.00	0.20	3.00		
213.90	214.30		Cum	1	0.40	1.00	1.70	1.35	0.20	0.11		
214.30	229.30		Cum	1	15.00	1.83	1.50	1.67	0.20	5.00		
229.30	243.20		Cum	1	13.90	1.83	1.50	1.67	0.20	4.63		
243.20	246.30		Cum	1	3.10	1.95	1.90	1.93	0.20	1.19		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		For Road Cutting										
0.00	4.50		Cum	1	4.50	0.40	0.25	0.33	0.20	0.29		
0.00	5.00		Cum	1	5.00	0.40	0.20	0.30	0.20	0.30		
0.00	2.80		Cum	1	2.80	3.20	3.25	3.23	0.20	1.81		
0.00	4.70		Cum	1	4.70	0.70	0.45	0.58	0.20	0.54		
0.00	2.60		Cum	1	2.60	1.20	1.25	1.23	0.20	0.64		
		Deducation										
		Chamber	Cum	-1	1.90			1.40	0.20	-0.53		
		Tree Pot	Cum	-9	0.20			0.10	0.20	-0.04		
		Electric Pole	Cum	-1	0.90			0.50	0.20	-0.09		
		Man Hole (1m Dia)	Cum	-1	Area = 0.25*3.142*1^2=0.785				0.20	-0.16		
		7th Main Road										
		(From North to South)										
2.10	5.60		Cum	1	3.50	1.90	2.10	2.00	0.20	1.40		
12.50	16.20		Cum	1	3.70	1.50	1.80	1.65	0.20	1.22		
24.20	28.00		Cum	1	3.80	2.50	2.10	2.30	0.20	1.75		
31.80	38.00		Cum	1	6.20	1.20	1.20	1.20	0.20	1.49		
40.00	42.60		Cum	1	2.60	1.90	1.70	1.80	0.20	0.94		
44.90	49.00		Cum	1	4.10	2.30	2.50	2.40	0.20	1.97		
81.70	88.00		Cum	1	6.30	2.80	2.80	2.80	0.20	3.53		
92.00	96.40		Cum	1	4.40	1.60	2.40	2.90	0.20	2.55		
99.30	101.80		Cum	1	2.50	2.30	2.40	2.35	0.20	1.18		
		2nd Cross										
		(From North to South)										
4.00	11.00		Cum	1	7.00	1.20	1.20	1.20	0.20	1.68		
17.00	27.00		Cum	1	10.00	1.30	1.30	1.30	0.20	2.60		
34.00	41.00		Cum	1	7.00	1.60	1.60	1.60	0.20	2.24		
48.00	56.00		Cum	1	8.00	1.50	1.50	1.50	0.20	2.40		
61.00	67.00		Cum	1	6.00	1.20	1.20	1.20	0.20	1.44		
71.00	78.00		Cum	1	7.00	1.80	1.80	1.80	0.20	2.52		
82.00	88.00		Cum	1	6.00	2.10	2.10	2.10	0.20	2.52		
92.00	96.40		Cum	1	4.40	1.10	1.10	1.10	0.20	0.97		
		8th Main Road										
		North to South										
6.00	8.00		Cum	1	2.00	1.10	1.10	1.10	0.20	0.44		
12.00	16.00		Cum	1	4.00	1.30	1.30	1.30	0.20	1.04		
26.00	29.00		Cum	1	3.00	1.00	1.00	1.00	0.20	0.60		
42.00	47.00		Cum	1	5.00	1.20	1.20	1.20	0.20	1.20		
88.00	93.00		Cum	1	5.00	0.90	0.90	0.90	0.20	0.90		
		Vinayak Nagar										
		6th B Main Road										
		North to South										
8.00	11.00		Cum	1	3.00	1.30	1.30	1.30	0.20	0.78		
55.00	59.00		Cum	1	4.00	1.40	1.40	1.40	0.20	1.12		
63.00	67.00		Cum	1	4.00	1.20	1.20	1.20	0.20	0.96		
76.00	79.00		Cum	1	3.00	0.85	0.85	0.85	0.20	0.51		
		M S Nagar										
		2nd Main Road										
		(From West to East)										
		Cut Portion										
0.00	2.60		Cum	1	2.60	2.10	2.10	2.10	0.20	1.09		
		5th Cross Road										
		(From North to South)										
		Cut Portion										
0.00	12.10		Cum	1	12.10	2.40	2.40	2.40	0.20	5.81		
		Hegde Nagara										
		Win Field Garden										
		5th Cross Road (W1941)										
		(From South to North)										
1.50	2.80		Cum	1	1.30	6.10	6.80	6.45	0.20	1.68		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
3.20	6.00		Cum	1	2.80	4.60	5.20	4.90	0.20	2.74		
9.00	13.10		Cum	1	4.10	4.00	3.80	3.90	0.20	3.20		
16.00	19.60		Cum	1	3.60	3.50	4.40	3.95	0.20	2.84		
25.00	30.00		Cum	1	5.00	2.60	3.20	2.90	0.20	2.90		
32.00	35.00		Cum	1	3.00	3.10	2.00	2.55	0.20	1.53		
39.00	43.00		Cum	1	4.00	4.50	3.00	3.75	0.20	3.00		
46.00	49.00		Cum	1	3.00	2.60	2.90	2.75	0.20	1.65		
51.00	52.50		Cum	1	1.50	1.30	1.80	1.55	0.20	0.47		
54.60	57.20		Cum	1	2.60	2.60	3.50	3.05	0.20	1.59		
60.10	65.00		Cum	1	4.90	4.00	5.10	4.55	0.20	4.46		
75.00	79.30		Cum	1	4.30	2.90	3.50	3.20	0.20	2.75		
83.00	87.00		Cum	1	4.00	1.80	2.30	2.05	0.20	1.64		
90.30	95.00		Cum	1	4.70	3.20	4.00	3.60	0.20	3.38		
103.00	105.80		Cum	1	2.80	2.30	3.50	2.90	0.20	1.62		
109.40	113.00		Cum	1	3.60	4.80	5.20	5.00	0.20	3.60		
120.30	125.10		Cum	1	4.80	2.60	3.60	3.10	0.20	2.98		
138.00	143.60		Cum	1	5.60	1.20	2.00	1.60	0.20	1.79		
152.00	155.70		Cum	1	3.70	2.40	2.60	2.50	0.20	1.85		
160.00	161.00		Cum	1	1.00	1.90	2.40	2.15	0.20	0.43		
170.00	175.60		Cum	1	5.60	2.00	2.80	2.40	0.20	2.69		
180.00	182.00		Cum	1	2.00	5.30	6.10	5.70	0.20	2.28		
186.00	187.20		Cum	1	1.20	5.40	4.60	5.00	0.20	1.20		
		9th Cross Road										
		(From South to North)										
2.80	6.30		Cum	1	3.50	2.40	3.10	2.75	0.20	1.93		
8.00	10.00		Cum	1	2.00	3.00	2.80	2.90	0.20	1.16		
13.00	16.30		Cum	1	3.30	1.75	2.40	2.08	0.20	1.37		
20.50	27.00		Cum	1	6.50	3.10	3.50	3.30	0.20	4.29		
28.00	32.00		Cum	1	4.00	3.30	4.00	3.65	0.20	2.92		
37.30	40.20		Cum	1	2.90	4.10	3.00	3.55	0.20	2.06		
41.00	42.00		Cum	1	1.00	1.65	2.40	2.03	0.20	0.41		
45.00	49.70		Cum	1	4.70	2.10	2.10	2.10	0.20	1.97		
52.90	59.30		Cum	1	6.40	3.00	3.40	3.20	0.20	4.10		
66.00	69.20		Cum	1	3.20	3.65	3.90	3.78	0.20	2.42		
74.00	78.00		Cum	1	4.00	3.70	3.90	3.80	0.20	3.04		
80.80	84.50		Cum	1	3.70	2.90	3.80	3.35	0.20	2.48		
91.60	99.10		Cum	1	7.50	4.20	3.00	3.60	0.20	5.40		
101.00	104.80		Cum	1	3.80	2.80	2.40	2.60	0.20	1.98		
108.00	117.80		Cum	1	9.80	3.50	3.80	3.65	0.20	7.15		
119.40	124.10		Cum	1	4.70	4.00	3.20	3.60	0.20	3.38		
126.50	130.40		Cum	1	3.90	2.90	3.40	3.15	0.20	2.46		
132.00	136.20		Cum	1	4.20	4.10	3.70	3.90	0.20	3.28		
		Venkateshwara Layout										
		3rd Cross Road										
		South to North										
0.00	15.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
15.00	30.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
30.00	45.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
45.00	60.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
60.00	75.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
75.00	90.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
90.00	105.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
105.00	120.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
120.00	135.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
135.00	150.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
150.00	165.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
165.00	180.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
180.00	195.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
195.00	210.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
210.00	220.00		Cum	1	10.00	1.20	1.20	1.20	0.23	2.76		
		4th Cross Road										
		North to South										
0.00	15.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.00	15.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
15.00	30.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
30.00	45.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
45.00	60.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
60.00	75.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
75.00	90.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
90.00	105.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
105.00	120.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
120.00	135.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
135.00	150.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
150.00	165.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
165.00	180.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
180.00	195.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
195.00	210.00		Cum	1	10.00	1.20	1.20	1.20	0.23	2.76		
210.00	220.00											
		5th Cross Road										
		North to South										
0.00	15.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
15.00	30.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
30.00	45.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
45.00	60.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
60.00	75.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
75.00	90.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
90.00	105.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
105.00	120.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
120.00	135.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
135.00	150.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
150.00	165.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
165.00	180.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
180.00	195.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
195.00	210.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
210.00	220.00		Cum	1	10.00	1.20	1.20	1.20	0.20	2.40		
		Katgenahalli										
		Mk Provision Store Road										
		(From East to West)										
4.00	8.00		Cum	1	4.00	1.20	1.20	1.20	0.20	0.96		
14.00	16.00		Cum	1	2.00	0.90	0.90	0.90	0.20	0.36		
22.00	28.00		Cum	1	6.00	1.30	1.30	1.30	0.20	1.56		
33.00	39.00		Cum	1	6.00	1.10	1.10	1.10	0.20	1.32		
42.00	44.00		Cum	1	2.00	0.60	0.60	0.60	0.20	0.24		
50.00	57.00		Cum	1	7.00	0.90	0.90	0.90	0.20	1.26		
62.60	67.20		Cum	1	4.60	1.10	1.10	1.10	0.20	1.01		
78.30	88.00		Cum	1	9.70	1.30	1.30	1.30	0.20	2.52		
93.00	101.00		Cum	1	8.00	1.10	1.10	1.10	0.20	1.76		
108.00	117.00		Cum	1	9.00	1.20	1.20	1.20	0.20	2.16		
124.60	133.00		Cum	1	8.40	1.40	1.40	1.40	0.20	2.35		
137.90	148.00		Cum	1	10.10	1.20	1.20	1.20	0.20	2.42		
		Form mrd Main To										
0.00	1.70		Cum	1	1.70	5.05	5.05	5.05	0.20	1.72		
1.70	15.00		Cum	1	13.30	7.30	7.40	7.35	0.20	19.55		
15.00	30.00		Cum	1	15.00	7.40	7.10	7.25	0.20	21.75		
30.00	45.00		Cum	1	15.00	7.10	6.75	6.93	0.20	20.78		
45.00	60.00		Cum	1	15.00	6.75	7.55	7.15	0.20	21.45		
60.00	75.00		Cum	1	15.00	7.55	6.45	7.00	0.20	21.00		
75.00	77.80		Cum	1	2.80	6.45	5.70	6.08	0.20	3.40		
77.80	90.00		Cum	1	12.20	6.80	7.15	6.98	0.20	17.02		
90.00	95.90		Cum	1	5.90	7.15	6.95	7.05	0.20	8.32		
95.90	105.00		Cum	1	9.10	6.25	6.30	6.28	0.20	11.42		
105.00	117.90		Cum	1	12.90	6.30	5.90	6.10	0.20	15.74		
117.90	120.00		Cum	1	2.10	6.75	6.80	6.78	0.20	2.85		
120.00	124.80		Cum	1	4.80	6.80	5.80	6.30	0.20	6.05		
			Cum	1	Triangular Portion 9.5*8.2*12.55=977.65			977.65	0.20	195.53		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Cum	1	Triangular Portion 10.5*3.3*11=381.15			381.15	0.20	76.23		
		Deduction										
0.00	1.40		Cum	-1	1.40	1.00	1.00	1.00	0.20	-0.28		
		Cross Road 3 Near Pyramid apartment (North to South)										
0.00	2.90		Cum	1	2.90	6.40	6.35	6.38	0.23	4.25		
2.90	15.00		Cum	1	12.10	6.35	5.75	6.05	0.23	16.84		
15.00	30.00		Cum	1	15.00	5.75	5.70	5.73	0.23	19.75		
30.00	44.00		Cum	1	14.00	5.70	5.10	5.40	0.23	17.39		
		For Road Cut portion Green Garden Main Road (West to East)										
2.00	4.00		Cum	1	2.00	1.60	1.60	1.60	0.23	0.74		
7.00	11.00		Cum	1	4.00	1.20	1.20	1.20	0.23	1.10		
13.00	15.00		Cum	1	2.00	1.30	1.30	1.30	0.23	0.60		
17.00	22.00		Cum	1	5.00	1.10	1.10	1.10	0.23	1.27		
25.00	29.00		Cum	1	4.00	2.00	2.00	2.00	0.23	1.84		
30.00	42.70		Cum	1	12.70	1.60	1.60	1.60	0.23	4.67		
42.70	45.00		Cum	1	2.30	2.10	2.10	2.10	0.23	1.11		
45.00	53.70		Cum	1	8.70	1.10	1.10	1.10	0.23	2.20		
53.70	60.00		Cum	1	6.30	1.60	1.60	1.60	0.23	2.32		
62.00	66.00		Cum	1	4.00	1.60	1.60	1.60	0.23	1.47		
68.00	70.00		Cum	1	2.00	1.80	1.80	1.80	0.23	0.83		
72.00	75.00		Cum	1	3.00	1.40	1.40	1.40	0.23	0.97		
77.00	88.00		Cum	1	11.00	1.20	1.20	1.20	0.23	3.04		
93.80	103.00		Cum	1	9.20	1.00	1.00	1.00	0.23	2.12		
107.00	117.00		Cum	1	10.00	1.70	1.70	1.70	0.23	3.91		
120.00	126.90		Cum	1	6.90	1.30	1.30	1.30	0.23	2.06		
128.00	130.00		Cum	1	2.00	1.40	1.40	1.40	0.23	0.64		
132.00	140.00		Cum	1	8.00	1.60	1.60	1.60	0.23	2.94		
148.00	152.00		Cum	1	4.00	2.10	2.10	2.10	0.23	1.93		
154.30	160.00		Cum	1	5.70	1.60	1.60	1.60	0.23	2.10		
163.00	169.00		Cum	1	6.00	1.30	1.30	1.30	0.23	1.79		
		Cross Road-4 (South to North)										
0.00	1.60		Cum	1	1.60	1.30	1.30	1.30	0.23	0.48		
4.00	12.00		Cum	1	8.00	2.00	2.00	2.00	0.23	3.68		
15.00	21.00		Cum	1	6.00	1.60	1.60	1.60	0.23	2.21		
23.50	30.00		Cum	1	6.50	2.60	2.60	2.60	0.23	3.89		
30.00	33.70		Cum	1	3.70	3.00	3.00	3.00	0.23	2.55		
		Sri Ganga House Road East to West										
3.80	13.20		Cum	1	9.40	1.00	1.00	1.00	0.23	2.16		
13.20	15.00		Cum	1	1.80	3.00	3.00	3.00	0.23	1.24		
17.00	26.00		Cum	1	9.00	2.40	2.40	2.40	0.23	4.97		
27.40	30.00		Cum	1	2.60	1.60	1.60	1.60	0.23	0.96		
33.00	41.00		Cum	1	8.00	1.90	1.90	1.90	0.23	3.50		
47.00	57.60		Cum	1	10.60	3.00	3.00	3.00	0.23	7.31		
62.00	66.00		Cum	1	4.00	1.70	1.70	1.70	0.23	1.56		
		Cross Road-3 (North to South)										
0.00	1.70		Cum	1	1.70	3.00	3.00	3.00	0.23	1.17		
3.30	10.00		Cum	1	6.70	1.30	1.30	1.30	0.23	2.00		
12.00	14.00		Cum	1	2.00	0.90	0.90	0.90	0.23	0.41		
17.00	21.00		Cum	1	4.00	1.70	1.70	1.70	0.23	1.56		
24.00	29.00		Cum	1	5.00	2.20	2.20	2.20	0.23	2.53		
33.00	38.00		Cum	1	5.00	1.70	1.70	1.70	0.23	1.96		
40.00	44.00		Cum	1	4.00	1.10	1.10	1.10	0.23	1.01		
45.00	46.10		Cum	1	1.10	1.70	1.70	1.70	0.23	0.43		
46.10	48.90		Cum	1	2.80	2.00	2.00	2.00	0.23	1.29		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Cross Road 2										
		(South to North)										
			Cum	1	6.00	1.90	1.90	1.90	0.23	2.62		
3.00	9.00		Cum	1	3.00	2.20	2.20	2.20	0.23	1.52		
12.00	15.00		Cum	1	3.10	3.10	3.10	3.10	0.23	2.21		
18.00	21.10		Cum	1	7.00	1.75	1.75	1.75	0.23	2.82		
23.00	30.00		Cum	1	12.00	2.00	2.00	2.00	0.23	5.52		
33.00	45.00		Cum	1	3.00	1.00	1.00	1.00	0.23	0.69		
48.00	51.00		Cum	1	5.00	1.85	1.85	1.85	0.23	2.13		
53.00	58.00		Cum	1	7.80	1.50	1.50	1.50	0.23	2.69		
64.20	72.00		Cum	1	9.00	2.10	2.10	2.10	0.23	4.35		
78.00	87.00		Cum	1	5.40	1.70	1.70	1.70	0.23	2.11		
92.60	98.00											
		Cross Road 1										
		(North to South)										
			Cum	1	7.60	1.20	1.20	1.20	0.23	2.10		
4.60	12.20		Cum	1	9.40	1.80	1.80	1.80	0.23	3.89		
17.60	27.00		Cum	1	8.00	2.30	2.30	2.30	0.23	4.23		
33.00	41.00		Cum	1	11.00	2.70	2.70	2.70	0.23	6.83		
47.00	58.00		Cum	1	8.20	1.60	1.60	1.60	0.23	3.02		
62.80	71.00		Cum	1	9.00	1.50	1.50	1.50	0.23	3.11		
79.00	88.00		Cum	1	4.00	1.70	1.70	1.70	0.23	1.56		
94.00	98.00											
		Pyramid apartment main road										
		(East to West)										
			Cum	1	1.10	8.16	8.15	8.16	0.23	2.06		
0.00	1.10		Cum	1	1.30	8.15	6.80	7.48	0.23	2.24		
1.10	2.40		Cum	1	2.30	6.80	6.60	6.70	0.23	3.54		
2.40	4.70		Cum	1	7.70	7.65	7.85	7.75	0.23	13.73		
4.70	12.40		Cum	1	2.60	7.85	7.70	7.78	0.23	4.65		
12.40	15.00		Cum	1	15.00	7.70	8.35	8.03	0.23	27.69		
15.00	30.00		Cum	1	2.00	8.35	8.35	8.35	0.23	3.84		
30.00	32.00		Cum	1	13.00	8.35	8.50	8.43	0.23	25.19		
32.00	45.00		Cum	1	15.00	8.50	8.65	8.58	0.23	29.58		
45.00	60.00		Cum	1	15.00	8.65	8.70	8.68	0.23	29.93		
60.00	75.00		Cum	1	6.10	8.70	8.75	8.73	0.23	12.24		
75.00	81.10		Cum	1	8.90	8.75	8.20	8.48	0.23	17.35		
81.10	90.00		Cum	1	15.00	8.20	8.45	8.33	0.23	28.72		
90.00	105.00		Cum	1	15.00	8.45	8.38	8.42	0.23	29.03		
105.00	120.00		Cum	1	8.00	8.38	8.40	8.39	0.23	15.44		
120.00	128.00											
		Cross Road 2 Near Pyramid apartment										
		(North to South)										
			Cum	1	5.40	1.40	1.40	1.40	0.23	1.74		
5.60	11.00		Cum	1	10.00	1.80	1.80	1.80	0.23	4.14		
17.00	27.00		Cum	1	2.80	1.70	1.70	1.70	0.23	1.09		
30.00	32.80		Cum	1	9.50	2.00	2.00	2.00	0.23	4.37		
32.80	42.30		Cum	1	2.80	1.30	1.30	1.30	0.23	0.84		
42.30	45.10		Cum	1	3.20	1.00	1.00	1.00	0.23	0.74		
45.10	48.30											
		Cross Road 1 Near Pyramid apartment										
		(North to South)										
			Cum	1	8.50	1.70	1.70	1.70	0.23	3.32		
4.50	13.00		Cum	1	11.00	1.40	1.40	1.40	0.23	3.54		
16.00	27.00		Cum	1	7.00	1.70	1.70	1.70	0.23	2.74		
34.00	41.00		Cum	1	3.70	1.25	1.25	1.25	0.23	1.06		
48.00	51.70		Cum	1	5.70	2.10	2.10	2.10	0.23	2.75		
53.00	58.70		Cum	1	8.00	1.70	1.70	1.70	0.23	3.13		
63.00	71.00		Cum	1	7.00	1.40	1.40	1.40	0.23	2.25		
79.00	86.00		Cum	1	9.00	2.00	2.00	2.00	0.23	4.14		
93.00	102.00		Cum	1	10.60	1.80	1.80	1.80	0.23	4.39		
106.40	117.00		Cum	1	3.00	1.20	1.20	1.20	0.23	0.83		
122.00	125.00											

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Car 24 Beside Road										
		From Agrahara Main Road to Lake										
		East to West										
0.00	15.00		Cum	1	15.00	4.80	4.60	4.70	0.25	17.63		
15.00	27.00		Cum	1	12.00	4.60	4.65	4.63	0.25	13.88		
27.00	30.00		Cum	1	3.00	5.40	5.70	5.55	0.25	4.16		
30.00	45.00		Cum	1	15.00	5.70	5.70	5.70	0.25	21.38		
45.00	60.00		Cum	1	15.00	5.70	6.30	6.00	0.25	22.50		
60.00	75.00		Cum	1	15.00	6.30	6.30	6.30	0.25	23.63		
75.00	90.00		Cum	1	15.00	6.30	6.50	6.40	0.25	24.00		
90.00	105.00		Cum	1	15.00	6.50	6.65	6.58	0.25	24.66		
105.00	120.00		Cum	1	15.00	6.65	6.40	6.53	0.25	24.47		
120.00	135.00		Cum	1	15.00	6.40	6.20	6.30	0.25	23.63		
135.00	150.00		Cum	1	15.00	6.20	6.10	6.15	0.25	23.06		
150.00	165.00		Cum	1	15.00	6.10	6.30	6.20	0.25	23.25		
165.00	180.00		Cum	1	15.00	6.30	6.10	6.20	0.25	23.25		
180.00	195.00		Cum	1	15.00	6.10	6.25	6.18	0.25	23.16		
195.00	210.00		Cum	1	15.00	6.25	6.50	6.38	0.25	23.91		
210.00	225.00		Cum	1	15.00	6.50	6.40	6.45	0.25	24.19		
225.00	240.00		Cum	1	15.00	6.40	6.50	6.45	0.25	24.19		
240.00	255.00		Cum	1	15.00	6.50	6.65	6.58	0.25	24.66		
255.00	270.00		Cum	1	15.00	6.65	6.70	6.68	0.25	25.03		
270.00	285.00		Cum	1	15.00	6.70	6.45	6.58	0.25	24.66		
285.00	300.00		Cum	1	15.00	6.45	6.20	6.33	0.25	23.72		
300.00	315.00		Cum	1	15.00	6.20	6.10	6.15	0.25	23.06		
315.00	330.00		Cum	1	15.00	6.10	6.10	6.10	0.25	22.88		
330.00	345.00		Cum	1	15.00	6.10	6.00	6.05	0.25	22.69		
345.00	360.00		Cum	1	15.00	6.00	6.60	6.30	0.25	23.63		
360.00	375.00		Cum	1	15.00	6.60	6.00	6.30	0.25	23.63		
375.00	390.00		Cum	1	15.00	6.00	6.10	6.05	0.25	22.69		
390.00	405.00		Cum	1	15.00	6.10	6.30	6.20	0.25	23.25		
405.00	410.00		Cum	1	5.00	6.30	6.40	6.35	0.25	7.94		
410.00	419.00		Cum	1	9.00	4.70	4.50	4.60	0.25	10.35		
419.00	420.00		Cum	1	1.00	6.30	6.30	6.30	0.25	1.58		
420.00	435.00		Cum	1	15.00	6.30	6.30	6.30	0.25	23.63		
435.00	450.00		Cum	1	15.00	6.30	6.80	6.55	0.25	24.56		
450.00	465.00		Cum	1	15.00	6.80	7.10	6.95	0.25	26.06		
465.00	480.00		Cum	1	15.00	7.10	5.80	6.45	0.25	24.19		
480.00	495.00		Cum	1	15.00	5.80	5.20	5.50	0.25	20.63		
495.00	510.00		Cum	1	15.00	5.20	3.95	4.58	0.25	17.16		
510.00	512.00		Cum	1	2.00	3.95	3.80	3.88	0.25	1.94		
512.00	525.00		Cum	1	13.00	4.70	5.45	5.08	0.25	16.49		
525.00	540.00		Cum	1	15.00	5.45	6.10	5.78	0.25	21.66		
540.00	546.00		Cum	1	6.00	6.10	5.50	5.80	0.25	8.70		
		Cross Road-1										
		South to North										
0.00	6.00		Cum	1	6.00	12.00	5.90	8.95	0.25	13.43		
6.00	12.00		Cum	1	6.00	5.90	5.00	5.45	0.25	8.18		
12.00	15.00		Cum	1	3.00	6.00	6.00	6.00	0.25	4.50		
15.00	19.00		Cum	1	4.00	6.00	5.70	5.85	0.25	5.85		
		Cross Road-2										
		South to north										
0.00	15.00		Cum	1	15.00	6.50	6.00	6.25	0.25	23.44		
15.00	30.00		Cum	1	15.00	6.00	6.00	6.00	0.25	22.50		
30.00	45.00		Cum	1	15.00	6.00	6.00	6.00	0.25	22.50		
45.00	60.00		Cum	1	15.00	6.00	6.30	6.15	0.25	23.06		
60.00	67.70		Cum	1	7.70	6.30	6.60	6.45	0.25	12.42		
67.70	69.70		Cum	1	2.00	6.60	7.30	6.95	0.25	3.48		
		MCECHS layout										
		22nd Cross Road										
		North to South										
0.00	15.00		Cum	1	15.00	0.75	0.75	0.75	0.20	2.25		
15.00	30.00		Cum	1	15.00	0.75	0.75	0.75	0.20	2.25		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
30.00	45.00		Cum	1	15.00	0.75	0.75	0.75	0.20	2.25		
45.00	60.00		Cum	1	15.00	0.75	0.75	0.75	0.20	2.25		
60.00	75.00		Cum	1	15.00	0.75	0.75	0.75	0.20	2.25		
75.00	90.00		Cum	1	15.00	0.75	0.75	0.75	0.20	2.25		
90.00	105.00		Cum	1	15.00	0.75	0.75	0.75	0.20	2.25		
105.00	120.00		Cum	1	15.00	0.75	0.75	0.75	0.20	2.25		
120.00	135.00		Cum	1	15.00	0.75	0.75	0.75	0.20	2.25		
135.00	141.10		Cum	1	6.10	0.75	0.75	0.75	0.20	0.91		
		Total Executed Quantity								**2351.43**		
		Tender Quantity								**1318.47**		
		Quantity Upto 125%								**1648.09**	**56.82**	**93645.00**
		Quantity Above 125%								**703.35**	**56.82**	**39966.00**
Item no. 10		Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by road roller attached with scarifier without disturbing the base and stacking the debris including cost of all labour charges, HOM of machineries complete as per specification and directions of the Engineer in charge.										
		Defence Colony										
		6th Main Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	4.95	5.20	5.08		76.13		
15.00	30.00		Sqm	1	15.00	5.20	5.20	5.20		78.00		
30.00	40.10		Sqm	1	10.10	5.20	5.50	5.35		54.04		
40.10	43.70		Sqm	1	3.60	4.32	4.75	4.54		16.33		
43.70	45.00		Sqm	1	1.30	5.28	5.20	5.24		6.81		
45.00	60.00		Sqm	1	15.00	5.20	4.90	5.05		75.75		
60.00	75.00		Sqm	1	15.00	4.90	5.50	5.20		78.00		
75.00	90.00		Sqm	1	15.00	5.50	5.10	5.30		79.50		
90.00	105.00		Sqm	1	15.00	5.10	5.00	5.05		75.75		
105.00	110.80		Sqm	1	5.80	5.00	5.10	5.05		29.29		
		8th Main Road										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	4.40	4.45	4.43		66.38		
15.00	30.00		Sqm	1	15.00	4.45	4.90	4.68		70.13		
30.00	45.00		Sqm	1	15.00	4.95	5.10	5.03		75.38		
45.00	60.00		Sqm	1	15.00	5.10	5.00	5.05		75.75		
60.00	75.00		Sqm	1	15.00	4.95	5.10	5.03		75.38		
75.00	90.00		Sqm	1	15.00	5.10	5.05	5.08		76.13		
90.00	105.00		Sqm	1	15.00	4.95	5.20	5.08		76.13		
105.00	120.00		Sqm	1	15.00	5.20	5.05	5.13		76.88		
120.00	131.00		Sqm	1	11.00	4.95	4.95	4.95		54.45		
		Cross Road 2										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	4.25	4.10	4.18		62.63		
15.00	30.00		Sqm	1	15.00	4.10	4.00	4.05		60.75		
30.00	31.50		Sqm	1	1.50	4.00	4.00	4.00		6.00		
		Cross Road 1										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	4.40	4.48	4.44		66.60		
15.00	29.50		Sqm	1	14.50	4.48	4.65	4.57		66.19		
		Nithish Central Park Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	5.80	5.40	5.60		84.00		
15.00	21.40		Sqm	1	6.40	5.40	5.70	5.55		35.52		
21.40	29.60		Sqm	1	8.20	5.05	4.80	4.93		40.39		
29.60	30.00		Sqm	1	0.40	5.52	5.50	5.51		2.20		
30.00	45.00		Sqm	1	15.00	5.50	5.15	5.33		79.88		
45.00	60.00		Sqm	1	15.00	5.15	5.15	5.15		77.25		
60.00	75.00		Sqm	1	15.00	5.15	5.04	5.10		76.43		
75.00	80.00		Sqm	1	5.00	5.04	6.00	5.52		27.60		
80.00	83.70		Sqm	1	3.70	6.00	5.95	5.98		22.11		
83.70	87.60		Sqm	1	3.90	5.30	5.30	5.30		20.67		
87.60	93.20		Sqm	1	5.60	6.30	6.20	6.25		35.00		
93.20	96.20		Sqm	1	3.00	5.40	5.00	5.20		15.60		
		Anand Nagar										
		1st Cross Road										
		Royal ACE Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	4.80	5.30	5.05		75.75		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
15.00	22.80		Sqm	1	7.80	5.30	5.40	5.35		41.73		
22.80	32.00		Sqm	1	9.20	4.95	4.80	4.88		44.85		
32.00	45.00		Sqm	1	13.00	4.75	5.03	4.89		63.57		
45.00	60.00		Sqm	1	15.00	5.03	4.95	4.99		74.85		
60.00	75.00		Sqm	1	15.00	4.95	5.30	5.13		76.88		
75.00	90.00		Sqm	1	15.00	4.95	5.45	5.20		78.00		
90.00	95.10		Sqm	1	5.10	5.45	5.65	5.55		28.31		
		1st Cross Road										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	6.50	5.40	5.95		89.25		
15.00	25.40		Sqm	1	10.40	5.40	6.00	5.70		59.28		
		M S Nagar										
		11th A Cross/2nd Main Road										
		(From South to North)										
0.00	15.00		Sqm	1	15.00	4.80	5.80	5.30		79.50		
15.00	30.00		Sqm	1	15.00	5.80	5.30	5.55		83.25		
30.00	45.00		Sqm	1	15.00	5.30	6.15	5.73		85.88		
45.00	60.00		Sqm	1	15.00	6.15	6.48	6.32		94.73		
60.00	65.80		Sqm	1	5.80	6.48	6.49	6.49		37.61		
		11th Cross Road										
		(From South to North)										
0.00	15.00		Sqm	1	15.00	4.20	4.10	4.15		62.25		
15.00	30.00		Sqm	1	15.00	4.10	3.80	3.95		59.25		
30.00	45.00		Sqm	1	15.00	3.80	3.65	3.73		55.88		
45.00	60.00		Sqm	1	15.00	3.65	4.00	3.83		57.38		
60.00	70.00		Sqm	1	10.00	4.00	4.10	4.05		40.50		
70.00	75.00		Sqm	1	5.00	4.10	4.00	4.05		20.25		
75.00	90.00		Sqm	1	15.00	4.00	4.64	4.32		64.80		
90.00	105.00		Sqm	1	15.00	4.64	4.90	4.77		71.55		
105.00	120.00		Sqm	1	15.00	4.90	4.90	4.90		73.50		
120.00	135.00		Sqm	1	15.00	4.90	4.90	4.90		73.50		
135.00	150.00		Sqm	1	15.00	4.90	5.00	4.95		74.25		
150.00	165.00		Sqm	1	15.00	5.00	4.90	4.95		74.25		
165.00	168.00		Sqm	1	3.00	4.90	4.75	4.83		14.48		
		10th Cross Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	5.35	5.30	5.33		79.88		
15.00	30.00		Sqm	1	15.00	5.30	5.10	5.20		78.00		
30.00	45.00		Sqm	1	15.00	5.10	4.40	4.75		71.25		
45.00	60.00		Sqm	1	15.00	4.40	4.50	4.45		66.75		
60.00	75.00		Sqm	1	15.00	4.50	4.60	4.55		68.25		
75.00	90.00		Sqm	1	15.00	4.60	4.48	4.54		68.10		
90.00	105.00		Sqm	1	15.00	4.48	4.84	4.66		69.90		
105.00	108.60		Sqm	1	3.60	4.84	4.85	4.85		17.44		
108.60	117.40		Sqm	1	8.80	5.35	4.80	5.08		44.66		
117.40	120.00		Sqm	1	2.60	4.50	4.60	4.55		11.83		
120.00	135.00		Sqm	1	15.00	4.60	4.49	4.55		68.18		
135.00	150.00		Sqm	1	15.00	4.49	4.67	4.58		68.70		
150.00	165.00		Sqm	1	15.00	4.67	4.55	4.61		69.15		
165.00	167.60		Sqm	1	2.60	4.55	4.90	4.73		12.29		
		10th A Cross										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	6.00	5.75	5.88		88.13		
15.00	30.00		Sqm	1	15.00	5.75	5.40	5.58		83.63		
30.00	45.00		Sqm	1	15.00	5.40	5.40	5.40		81.00		
45.00	60.00		Sqm	1	15.00	5.40	5.10	5.25		78.75		
60.00	75.00		Sqm	1	15.00	5.10	5.35	5.23		78.38		
75.00	90.00		Sqm	1	15.00	5.35	5.55	5.45		81.75		
90.00	105.00		Sqm	1	15.00	5.55	6.00	5.78		86.63		
105.00	120.00		Sqm	1	15.00	6.00	6.10	6.05		90.75		
120.00	134.70		Sqm	1	14.70	6.10	6.20	6.15		90.40		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		10th A Cross										
		(From West to East)										
0.00	2.80		Sqm	1	2.80	4.80	4.50	4.65		13.02		
		2nd Main Road										
		(From West to East)										
0.00	15.00		Sqm	1	15.00	8.80	8.70	8.75		131.25		
15.00	30.00		Sqm	1	15.00	8.70	9.13	8.92		133.73		
30.00	45.00		Sqm	1	15.00	9.13	8.50	8.82		132.23		
45.00	60.00		Sqm	1	15.00	8.50	8.40	8.45		126.75		
60.00	75.00		Sqm	1	15.00	8.40	8.55	8.48		127.13		
75.00	90.00		Sqm	1	15.00	8.55	8.10	8.33		124.88		
90.00	105.00		Sqm	1	15.00	8.10	7.60	7.85		117.75		
105.00	114.30		Sqm	1	9.30	7.60	8.00	7.80		72.54		
114.30	129.30		Sqm	1	15.00	8.00	7.45	7.73		115.88		
129.30	144.30		Sqm	1	15.00	7.45	6.85	7.15		107.25		
144.30	159.30		Sqm	1	15.00	6.85	6.80	6.83		102.38		
159.30	174.30		Sqm	1	15.00	6.80	6.90	6.85		102.75		
174.30	189.30		Sqm	1	15.00	6.90	7.65	7.28		109.13		
189.30	192.60		Sqm	1	3.30	7.65	7.40	7.53		24.83		
		Cut Portion										
0.00	2.60		Sqm	1	2.60	2.10	2.10	2.10		5.46		
		2nd Main Road To M S Nagar Road										
		(From West to East)										
0.00	15.00		Sqm	1	15.00	5.10	4.36	4.73		70.95		
15.00	30.00		Sqm	1	15.00	4.36	4.40	4.38		65.70		
30.00	33.70		Sqm	1	3.70	4.40	4.60	4.50		16.65		
		(From South to North)										
0.00	15.00		Sqm	1	15.00	5.45	5.20	5.33		79.88		
15.00	30.00		Sqm	1	15.00	5.20	5.40	5.30		79.50		
30.00	45.00		Sqm	1	15.00	5.40	5.70	5.55		83.25		
45.00	60.00		Sqm	1	15.00	5.70	5.25	5.48		82.13		
60.00	75.00		Sqm	1	15.00	5.25	5.40	5.33		79.88		
75.00	90.00		Sqm	1	15.00	5.40	5.40	5.40		81.00		
90.00	105.00		Sqm	1	15.00	5.40	5.40	5.40		81.00		
105.00	120.00		Sqm	1	15.00	5.40	5.58	5.49		82.35		
120.00	135.00		Sqm	1	15.00	5.58	5.40	5.49		82.35		
135.00	150.00		Sqm	1	15.00	5.40	5.35	5.38		80.63		
150.00	165.00		Sqm	1	15.00	5.35	5.20	5.28		79.13		
165.00	180.00		Sqm	1	15.00	5.20	5.20	5.20		78.00		
180.00	195.00		Sqm	1	15.00	5.20	5.54	5.37		80.55		
195.00	197.80		Sqm	1	2.80	5.54	6.40	5.97		16.72		
		(From East to West)										
0.00	15.00		Sqm	1	15.00	3.90	3.65	3.78		56.63		
15.00	30.00		Sqm	1	15.00	3.65	3.68	3.67		54.98		
30.00	45.00		Sqm	1	15.00	3.68	3.98	3.83		57.45		
45.00	49.80		Sqm	1	4.80	3.98	4.20	4.09		19.63		
49.80	51.90		Sqm	1	2.10	4.20	7.50	5.85		12.29		
		3A Cross Road										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	3.85	3.63	3.74		56.10		
15.00	30.00		Sqm	1	15.00	3.63	3.63	3.63		54.45		
30.00	41.40		Sqm	1	11.40	3.63	4.32	3.98		45.32		
41.40	44.50		Sqm	1	3.10	4.32	7.35	5.84		18.09		
		(From North to South)										
0.00	15.00		Sqm	1	15.00	4.10	3.60	3.85		57.75		
15.00	18.60		Sqm	1	3.60	3.60	3.65	3.63		13.05		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		5th Cross Road										
		(From North to South)										
0.00	3.40		Sqm	1	3.40	8.20	6.80	7.50		25.50		
3.40	15.00		Sqm	1	11.60	6.80	6.70	6.75		78.30		
15.00	30.00		Sqm	1	15.00	6.70	6.10	6.40		96.00		
30.00	45.00		Sqm	1	15.00	6.10	6.20	6.15		92.25		
45.00	56.60		Sqm	1	11.60	6.20	6.15	6.18		71.63		
		Cut Portion										
0.00	12.10		Sqm	1	12.10	2.40	2.40	2.40		29.04		
		6th Cross Road (W1935)										
		(From South to North)										
0.00	2.00		Sqm	1	2.00	7.50	5.90	6.70		13.40		
2.00	15.00		Sqm	1	13.00	5.90	5.95	5.93		77.03		
15.00	30.00		Sqm	1	15.00	5.95	6.00	5.98		89.63		
30.00	45.00		Sqm	1	15.00	6.00	5.50	5.75		86.25		
45.00	60.00		Sqm	1	15.00	5.50	5.35	5.43		81.38		
60.00	75.00		Sqm	1	15.00	5.35	5.55	5.45		81.75		
75.00	90.00		Sqm	1	15.00	5.55	5.55	5.55		83.25		
90.00	105.00		Sqm	1	15.00	5.55	5.60	5.58		83.63		
105.00	120.00		Sqm	1	15.00	5.60	5.60	5.60		84.00		
120.00	135.00		Sqm	1	15.00	5.60	5.75	5.68		85.13		
135.00	150.00		Sqm	1	15.00	5.75	4.85	5.30		79.50		
150.00	165.00		Sqm	1	15.00	4.85	4.80	4.83		72.38		
165.00	180.00		Sqm	1	15.00	4.80	6.10	5.45		81.75		
180.00	181.50		Sqm	1	1.50	6.10	5.40	5.75		8.63		
		MSR Mansion Road										
		(North to South)										
0.00	5.80		Sqm	1	5.80	5.75	7.15	6.45		37.41		
5.80	9.70		Sqm	1	3.90	10.70	8.40	9.55		37.25		
9.70	15.00		Sqm	1	5.30	8.40	8.25	8.33		44.12		
15.00	30.00		Sqm	1	15.00	8.25	7.40	7.83		117.38		
30.00	45.00		Sqm	1	15.00	7.40	6.85	7.13		106.88		
45.00	50.00		Sqm	1	5.00	6.85	7.10	6.98		34.88		
		Nisarga Layout										
		7th Cross, Zayan Travels Car Service Centre Road,										
		North To South										
0.00	15.00		Sqm	1	15.00	5.00	4.85	4.93		73.88		
15.00	30.00		Sqm	1	15.00	4.85	4.60	4.73		70.88		
30.00	45.00		Sqm	1	15.00	4.60	5.15	4.88		73.13		
45.00	60.00		Sqm	1	15.00	5.15	5.00	5.08		76.13		
60.00	75.00		Sqm	1	15.00	5.00	5.10	5.05		75.75		
75.00	90.00		Sqm	1	15.00	5.10	5.00	5.05		75.75		
90.00	101.50		Sqm	1	11.50	5.00	4.70	4.85		55.78		
		West To East										
0.00	15.00		Sqm	1	15.00	4.90	4.80	4.85		72.75		
15.00	15.70		Sqm	1	0.70	4.80	4.80	4.80		3.36		
15.70	30.00		Sqm	1	14.30	5.30	5.60	5.45		77.94		
30.00	45.00		Sqm	1	15.00	5.60	5.15	5.38		80.63		
45.00	46.70		Sqm	1	1.70	5.15	5.15	5.15		8.76		
46.70	51.60		Sqm	1	4.90	4.15	3.95	4.05		19.85		
51.60	56.20		Sqm	1	4.60	5.30	5.25	5.28		24.27		
56.20	64.60		Sqm	1	8.40	4.20	4.30	4.25		35.70		
64.60	75.00		Sqm	1	10.40	5.30	5.35	5.33		55.38		
75.00	76.60		Sqm	1	1.60	5.35	5.36	5.36		8.57		
		5th Cross Road,										
		North To South										
0.00	11.10		Sqm	1	11.10	5.70	5.90	5.80		64.38		
11.10	20.00		Sqm	1	8.90	5.10	5.35	5.23		46.50		
20.00	23.80		Sqm	1	3.80	7.00	6.95	6.98		26.51		
23.80	30.00		Sqm	1	6.20	6.05	5.95	6.00		37.20		
30.00	45.00		Sqm	1	15.00	5.95	5.50	5.73		85.88		
45.00	60.00		Sqm	1	15.00	5.50	6.00	5.75		86.25		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
60.00	66.90		Sqm	1	6.90	6.00	6.30	6.15		42.44		
66.90	75.00		Sqm	1	8.10	4.90	5.70	5.30		42.93		
75.00	75.60		Sqm	1	0.60	5.70	5.65	5.68		3.40		
75.60	76.80		Sqm	1	1.20	2.95	3.00	2.98		3.57		
		Mithun White Pearl Apartment Road										
		(East To West)										
0.00	15.00		Sqm	1	15.00	6.60	6.75	6.68		100.13		
15.00	30.00		Sqm	1	15.00	6.75	6.50	6.63		99.38		
30.00	45.00		Sqm	1	15.00	6.50	6.45	6.48		97.13		
45.00	60.00		Sqm	1	15.00	6.45	6.45	6.45		96.75		
60.00	75.00		Sqm	1	15.00	6.45	6.25	6.35		95.25		
75.00	90.00		Sqm	1	15.00	6.25	6.20	6.23		93.38		
90.00	96.40		Sqm	1	6.40	6.20	5.85	6.03		38.56		
		Chembar	Sqm	-1	0.64					-0.64		
								Area of				
			Sqm	-4	0.70	1.00	1.00	1.00		-2.80		
			Sqm	-3	0.90	0.80	0.80	0.80		-2.70		
		Katgenahalli										
		Muneshwara Provision Store Beside Road										
		Kalidas Layout										
		3rd Main Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	6.70	6.65	6.68		100.13		
15.00	30.00		Sqm	1	15.00	6.65	6.65	6.65		99.75		
30.00	45.00		Sqm	1	15.00	6.65	6.00	6.33		94.88		
45.00	60.00		Sqm	1	15.00	6.00	5.80	5.90		88.50		
60.00	66.40		Sqm	1	6.40	5.80	5.60	5.70		36.48		
66.40	75.00		Sqm	1	8.60	5.60	5.60	5.60		48.16		
75.00	90.00		Sqm	1	15.00	5.60	5.50	5.55		83.25		
90.00	105.00		Sqm	1	15.00	5.50	5.80	5.65		84.75		
105.00	113.00		Sqm	1	8.00	5.80	4.30	5.05		40.40		
		Cross Road - 2										
		(From North to South)										
0.00	4.30		Sqm	1	4.30	5.10	5.00	5.05		21.72		
4.30	15.00		Sqm	1	10.70	5.00	5.10	5.05		54.04		
15.00	20.60		Sqm	1	5.60	5.10	5.30	5.20		29.12		
20.60	30.00		Sqm	1	9.40	6.65	6.20	6.43		60.40		
30.00	40.60		Sqm	1	10.60	6.20	6.60	6.40		67.84		
40.60	45.00		Sqm	1	4.40	6.60	5.90	6.25		27.50		
45.00	60.00		Sqm	1	15.00	5.90	5.95	5.93		88.88		
60.00	75.00		Sqm	1	15.00	5.95	5.85	5.90		88.50		
75.00	90.00		Sqm	1	15.00	5.85	6.38	6.12		91.73		
90.00	105.00		Sqm	1	15.00	6.38	5.50	5.94		89.10		
105.00	120.00		Sqm	1	15.00	5.50	5.69	5.60		83.93		
120.00	123.00		Sqm	1	3.00	5.69	5.00	5.35		16.04		
		Cross Road - 1										
		(From South to North)										
0.00	15.00		Sqm	1	15.00	4.75	4.55	4.65		69.75		
15.00	30.00		Sqm	1	15.00	4.55	5.10	4.83		72.38		
30.00	45.00		Sqm	1	15.00	5.10	4.80	4.95		74.25		
45.00	60.00		Sqm	1	15.00	4.80	4.55	4.68		70.13		
60.00	75.00		Sqm	1	15.00	4.55	5.00	4.78		71.63		
75.00	88.60		Sqm	1	13.60	5.00	4.50	4.75		64.60		
		Kattigenahalli										
		Durgamba Layout										
		Amulya Family Restaurant Road (N-S)										
0.00	15.00		Sqm	1	15.00	6.90	6.40	6.65		99.75		
15.00	30.00		Sqm	1	15.00	6.40	6.05	6.23		93.38		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.00	45.00		Sqm	1	15.00	5.60	5.30	5.45		81.75		
30.00	60.00		Sqm	1	15.00	5.30	4.95	5.13		76.88		
45.00	75.00		Sqm	1	15.00	4.95	5.05	5.00		75.00		
60.00	81.00		Sqm	1	6.00	5.05	5.05	5.05		30.30		
75.00	90.00		Sqm	1	9.00	5.70	5.90	5.80		52.20		
81.00	105.00		Sqm	1	15.00	5.90	5.30	5.60		84.00		
90.00	118.80		Sqm	1	13.80	5.30	4.60	4.95		68.31		
105.00	127.90		Sqm	1	9.10	5.80	5.85	5.83		53.01		
118.80	135.00		Sqm	1	7.10	4.95	4.85	4.90		34.79		
127.90	137.10		Sqm	1	2.10	4.85	5.05	4.95		10.40		
135.00	150.00		Sqm	1	12.90	4.35	4.95	4.65		59.99		
137.10	150.00		Sqm	1	15.00	4.95	4.60	4.78		71.63		
150.00	165.00		Sqm	1	15.00	4.60	5.25	4.93		73.88		
165.00	180.00		Sqm	1	2.50	5.25	5.15	5.20		13.00		
180.00	182.50		Sqm	1	12.50	5.85	6.60	6.23		77.81		
182.50	195.00		Sqm	1	15.00	6.60	6.15	6.38		95.63		
195.00	210.00		Sqm	1	8.00	6.15	6.00	6.08		48.60		
210.00	218.00											
		Kaustaba House Road #33 (W-E)										
0.00	6.30		Sqm	1	6.30	7.45	7.55	7.50		47.25		
6.30	15.00		Sqm	1	8.70	6.80	6.48	6.64		57.77		
15.00	30.00		Sqm	1	15.00	6.48	6.00	6.24		93.60		
30.00	45.00		Sqm	1	15.00	6.00	5.70	5.85		87.75		
45.00	57.90		Sqm	1	12.90	5.70	6.05	5.88		75.79		
57.90	60.00		Sqm	1	2.10	6.95	7.70	7.33		15.38		
60.00	63.60		Sqm	1	3.60	7.70	7.65	7.68		27.63		
		Sukruthi House Road #26 (S-N)										
0.00	8.30		Sqm	1	8.30	5.60	5.90	5.75		47.73		
8.30	15.00		Sqm	1	6.70	5.35	4.90	5.13		34.34		
15.00	30.00		Sqm	1	15.00	4.90	5.80	5.35		80.25		
30.00	45.00		Sqm	1	15.00	5.80	5.35	5.58		83.63		
45.00	60.00		Sqm	1	15.00	5.35	5.30	5.33		79.88		
60.00	60.50		Sqm	1	0.50	5.30	5.30	5.30		2.65		
60.50	75.00		Sqm	1	14.50	5.85	6.20	6.03		87.36		
75.00	90.00		Sqm	1	15.00	6.20	5.40	5.80		87.00		
90.00	98.70		Sqm	1	8.70	5.40	5.20	5.30		46.11		
98.70	105.00		Sqm	1	6.30	4.40	4.95	4.68		29.45		
105.00	108.20		Sqm	1	3.20	4.95	4.95	4.95		15.84		
108.20	112.20		Sqm	1	4.00	5.50	5.20	5.35		21.40		
112.20	120.00		Sqm	1	7.80	4.40	4.60	4.50		35.10		
120.00	125.80		Sqm	1	5.80	4.60	4.50	4.55		26.39		
125.80	135.70		Sqm	1	9.90	4.00	4.45	4.23		41.83		
135.70	143.90		Sqm	1	8.20	5.60	5.95	5.78		47.36		
143.90	150.00		Sqm	1	6.10	6.65	5.75	6.20		37.82		
150.00	164.30		Sqm	1	14.30	5.75	5.85	5.80		82.94		
		SP Singh House Road (E-W)										
0.00	15.00		Sqm	1	15.00	6.35	5.65	6.00		90.00		
15.00	19.10		Sqm	1	4.10	5.65	6.00	5.83		23.88		
19.10	30.00		Sqm	1	10.90	5.20	5.65	5.43		59.13		
30.00	34.20		Sqm	1	4.20	5.65	6.10	5.88		24.68		
		Deduction										
		Chamber	Sqm	-1	0.70	1.00	1.00	1.00		-0.70		
		Manhole	Sqm	-1	0.64					-0.64		
							Area of Circle =					
		Manhole	Sqm	-1	1.13					-1.13		
							Area of Circle =					
		Vidhana Soudha Layout (From North to South)										
0.00	15.00		Sqm	1	15.00	6.10	5.45	5.78		86.63		
15.00	29.30		Sqm	1	14.30	5.45	8.30	6.88		98.31		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		(From East to West)										
0.00	15.00		Sqm	1	15.00	9.40	8.90	9.15		137.25		
15.00	30.00		Sqm	1	15.00	8.90	8.60	8.75		131.25		
30.00	45.00		Sqm	1	15.00	8.60	8.90	8.75		131.25		
45.00	60.00		Sqm	1	15.00	8.90	8.20	8.55		128.25		
60.00	75.00		Sqm	1	15.00	8.20	8.25	8.23		123.38		
75.00	90.00		Sqm	1	15.00	8.25	8.50	8.38		125.63		
90.00	105.00		Sqm	1	15.00	8.50	8.30	8.40		126.00		
105.00	117.80		Sqm	1	12.80	8.30	8.25	8.28		105.92		
117.80	125.10		Sqm	1	7.30	11.35	11.25	11.30		82.49		
125.10	135.00		Sqm	1	9.90	8.20	8.05	8.13		80.44		
135.00	150.00		Sqm	1	15.00	8.05	8.05	8.05		120.75		
150.00	150.90		Sqm	1	0.90	10.95	10.95	10.95		9.86		
150.90	165.00		Sqm	1	14.10	8.30	8.35	8.33		117.38		
165.00	180.00		Sqm	1	15.00	8.35	8.42	8.39		125.78		
180.00	184.90		Sqm	1	4.90	8.42	8.55	8.49		41.58		
184.90	193.50		Sqm	1	8.60	11.20	11.30	11.25		96.75		
193.50	195.00		Sqm	1	1.50	8.30	8.30	8.30		12.45		
195.00	210.00		Sqm	1	15.00	8.30	8.15	8.23		123.38		
210.00	225.00		Sqm	1	15.00	8.15	8.30	8.23		123.38		
225.00	240.00		Sqm	1	15.00	8.30	9.00	8.65		129.75		
240.00	255.00		Sqm	1	15.00	9.00	8.85	8.93		133.88		
255.00	258.00		Sqm	1	3.00	8.85	8.25	8.55		25.65		
258.00	265.10		Sqm	1	7.10	9.70	9.80	9.75		69.23		
265.10	270.00		Sqm	1	4.90	8.40	8.35	8.38		41.04		
270.00	285.00		Sqm	1	15.00	8.35	8.25	8.30		124.50		
285.00	291.00		Sqm	1	6.00	8.25	8.20	8.23		49.35		
291.00	299.80		Sqm	1	8.80	9.55	9.40	9.48		83.38		
299.80	300.00		Sqm	1	0.20	8.15	8.14	8.15		1.63		
300.00	301.00		Sqm	1	1.00	8.14	8.15	8.15		8.15		
301.00	307.30		Sqm	1	6.30	9.81	9.80	9.81		61.77		
307.30	315.00		Sqm	1	7.70	8.10	8.15	8.13		62.56		
315.00	323.00		Sqm	1	8.00	8.15	8.25	8.20		65.60		
323.00	332.00		Sqm	1	9.00	9.60	9.60	9.60		86.40		
332.00	343.00		Sqm	1	11.00	9.40	9.60	9.50		104.50		
343.00	345.00		Sqm	1	2.00	8.10	8.20	8.15		16.30		
345.00	358.90		Sqm	1	13.90	8.20	8.15	8.18		113.63		
358.90	368.10		Sqm	1	9.20	9.70	9.71	9.71		89.29		
368.10	375.00		Sqm	1	6.90	8.15	8.15	8.15		56.23		
375.00	382.60		Sqm	1	7.60	8.15	8.30	8.23		62.51		
382.60	391.90		Sqm	1	9.30	9.90	9.50	9.70		90.21		
391.90	393.30		Sqm	1	1.40	7.90	8.00	7.95		11.13		
393.30	400.00		Sqm	1	6.70	9.20	9.20	9.20		61.64		
400.00	405.00		Sqm	1	5.00	7.90	7.40	7.65		38.25		
405.00	420.00		Sqm	1	15.00	7.40	7.60	7.50		112.50		
420.00	435.00		Sqm	1	15.00	7.60	7.40	7.50		112.50		
435.00	444.20		Sqm	1	9.20	9.00	9.10	9.05		83.26		
444.20	446.30		Sqm	1	2.10	7.30	7.45	7.38		15.49		
446.30	456.40		Sqm	1	10.10	9.15	9.10	9.13		92.16		
456.40	465.00		Sqm	1	8.60	7.45	7.35	7.40		63.64		
465.00	480.00		Sqm	1	15.00	7.35	7.25	7.30		109.50		
480.00	495.00		Sqm	1	15.00	7.25	7.65	7.45		111.75		
495.00	510.00		Sqm	1	15.00	7.65	8.50	8.08		121.13		
510.00	525.20		Sqm	1	15.20	10.00	10.60	10.30		156.56		
525.20	540.00		Sqm	1	14.80	8.50	7.60	8.05		119.14		
540.00	555.00		Sqm	1	15.00	7.60	7.50	7.55		113.25		
555.00	560.90		Sqm	1	5.90	7.50	7.50	7.50		44.25		
560.90	562.70		Sqm	1	1.80	4.80	4.80	4.80		8.64		
		Total Executed Quantity								**21720.42**	**41.75**	**906828.00**
		Tender Quantity								**26339.70**		
Item no. 11		Supplying and laying Sand / Crushed Sand complete as per specification and directions of the Engineer in charge.										
		Item is Not Operated										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
Item no. 12		Extra for watering the earth to bring the earth upto required optimum moisture content manually including cost of all labour complete as per specification and directions of the Engineer in charge.										
		Item is Not Operated										
Item no. 13		Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specification and directions of the Engineer in charge.										
		Defence Colony										
		6th Main Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	4.95	5.20	5.08		76.13		
15.00	30.00		Sqm	1	15.00	5.20	5.20	5.20		78.00		
30.00	40.10		Sqm	1	10.10	5.20	5.50	5.35		54.04		
40.10	43.70		Sqm	1	3.60	4.32	4.75	4.54		16.33		
43.70	45.00		Sqm	1	1.30	5.28	5.20	5.24		6.81		
45.00	60.00		Sqm	1	15.00	5.20	4.90	5.05		75.75		
60.00	75.00		Sqm	1	15.00	4.90	5.50	5.20		78.00		
75.00	90.00		Sqm	1	15.00	5.50	5.10	5.30		79.50		
90.00	105.00		Sqm	1	15.00	5.10	5.00	5.05		75.75		
105.00	110.80		Sqm	1	5.80	5.00	5.10	5.05		29.29		
		8th Main Road										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	4.40	4.45	4.43		66.38		
15.00	30.00		Sqm	1	15.00	4.45	4.90	4.68		70.13		
30.00	45.00		Sqm	1	15.00	4.95	5.10	5.03		75.38		
45.00	60.00		Sqm	1	15.00	5.10	5.00	5.05		75.75		
60.00	75.00		Sqm	1	15.00	4.95	5.10	5.03		75.38		
75.00	90.00		Sqm	1	15.00	5.10	5.05	5.08		76.13		
90.00	105.00		Sqm	1	15.00	4.95	5.20	5.08		76.13		
105.00	120.00		Sqm	1	15.00	5.20	5.05	5.13		76.88		
120.00	131.00		Sqm	1	11.00	4.95	4.95	4.95		54.45		
		Cross Road 2										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	4.25	4.10	4.18		62.63		
15.00	30.00		Sqm	1	15.00	4.10	4.00	4.05		60.75		
30.00	31.50		Sqm	1	1.50	4.00	4.00	4.00		6.00		
		Cross Road 1										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	4.40	4.48	4.44		66.60		
15.00	29.50		Sqm	1	14.50	4.48	4.65	4.57		66.19		
		Nithish Central Park Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	5.80	5.40	5.60		84.00		
15.00	21.40		Sqm	1	6.40	5.40	5.70	5.55		35.52		
21.40	29.60		Sqm	1	8.20	5.05	4.80	4.93		40.39		
29.60	30.00		Sqm	1	0.40	5.52	5.50	5.51		2.20		
30.00	45.00		Sqm	1	15.00	5.50	5.15	5.33		79.88		
45.00	60.00		Sqm	1	15.00	5.15	5.15	5.15		77.25		
60.00	75.00		Sqm	1	15.00	5.15	5.04	5.10		76.43		
75.00	80.00		Sqm	1	5.00	5.04	6.00	5.52		27.60		
80.00	83.70		Sqm	1	3.70	6.00	5.95	5.98		22.11		
83.70	87.60		Sqm	1	3.90	5.30	5.30	5.30		20.67		
87.60	93.20		Sqm	1	5.60	6.30	6.20	6.25		35.00		
93.20	96.20		Sqm	1	3.00	5.40	5.00	5.20		15.60		
		Anand Nagar										
		1st Cross Road										
		Royal ACE Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	4.80	5.30	5.05		75.75		
15.00	22.80		Sqm	1	7.80	5.30	5.40	5.35		41.73		
22.80	32.00		Sqm	1	9.20	4.95	4.80	4.88		44.85		
32.00	45.00		Sqm	1	13.00	4.75	5.03	4.89		63.57		
45.00	60.00		Sqm	1	15.00	5.03	4.95	4.99		74.85		
60.00	75.00		Sqm	1	15.00	4.95	5.30	5.13		76.88		
75.00	90.00		Sqm	1	15.00	4.95	5.45	5.20		78.00		
90.00	95.10		Sqm	1	5.10	5.45	5.65	5.55		28.31		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		1st Cross Road										
		(From East to West)										
			Sqm	1	15.00	6.50	5.40	5.95		89.25		
0.00	15.00		Sqm	1	10.40	5.40	6.00	5.70		59.28		
15.00	25.40											
		M S Nagar										
		11th A Cross/2nd Main Road										
		(From South to North)										
			Sqm	1	15.00	4.80	5.80	5.30		79.50		
0.00	15.00		Sqm	1	15.00	5.80	5.30	5.55		83.25		
15.00	30.00		Sqm	1	15.00	5.30	6.15	5.73		85.88		
30.00	45.00		Sqm	1	15.00	6.15	6.48	6.32		94.73		
45.00	60.00		Sqm	1	5.80	6.48	6.49	6.49		37.61		
60.00	65.80											
		11th Cross Road										
		(From South to North)										
			Sqm	1	15.00	4.20	4.10	4.15		62.25		
0.00	15.00		Sqm	1	15.00	4.10	3.80	3.95		59.25		
15.00	30.00		Sqm	1	15.00	3.80	3.65	3.73		55.88		
30.00	45.00		Sqm	1	15.00	3.65	4.00	3.83		57.38		
45.00	60.00		Sqm	1	10.00	4.00	4.10	4.05		40.50		
60.00	70.00		Sqm	1	5.00	4.10	4.00	4.05		20.25		
70.00	75.00		Sqm	1	15.00	4.00	4.64	4.32		64.80		
75.00	90.00		Sqm	1	15.00	4.64	4.90	4.77		71.55		
90.00	105.00		Sqm	1	15.00	4.90	4.90	4.90		73.50		
105.00	120.00		Sqm	1	15.00	4.90	4.90	4.90		73.50		
120.00	135.00		Sqm	1	15.00	4.90	5.00	4.95		74.25		
135.00	150.00		Sqm	1	15.00	5.00	4.90	4.95		74.25		
150.00	165.00		Sqm	1	3.00	4.90	4.75	4.83		14.48		
165.00	168.00											
		10th Cross Road										
		(From North to South)										
			Sqm	1	15.00	5.35	5.30	5.33		79.88		
0.00	15.00		Sqm	1	15.00	5.30	5.10	5.20		78.00		
15.00	30.00		Sqm	1	15.00	5.10	4.40	4.75		71.25		
30.00	45.00		Sqm	1	15.00	4.40	4.50	4.45		66.75		
45.00	60.00		Sqm	1	15.00	4.50	4.60	4.55		68.25		
60.00	75.00		Sqm	1	15.00	4.60	4.48	4.54		68.10		
75.00	90.00		Sqm	1	15.00	4.48	4.84	4.66		69.90		
90.00	105.00		Sqm	1	3.60	4.84	4.85	4.85		17.44		
105.00	108.60		Sqm	1	8.80	5.35	4.80	5.08		44.66		
108.60	117.40		Sqm	1	2.60	4.50	4.60	4.55		11.83		
117.40	120.00		Sqm	1	15.00	4.60	4.49	4.55		68.18		
120.00	135.00		Sqm	1	15.00	4.49	4.67	4.58		68.70		
135.00	150.00		Sqm	1	15.00	4.67	4.55	4.61		69.15		
150.00	165.00		Sqm	1	2.60	4.55	4.90	4.73		12.29		
165.00	167.60											
		10th A Cross										
		(From North to South)										
			Sqm	1	15.00	6.00	5.75	5.88		88.13		
0.00	15.00		Sqm	1	15.00	5.75	5.40	5.58		83.63		
15.00	30.00		Sqm	1	15.00	5.40	5.40	5.40		81.00		
30.00	45.00		Sqm	1	15.00	5.40	5.10	5.25		78.75		
45.00	60.00		Sqm	1	15.00	5.10	5.35	5.23		78.38		
60.00	75.00		Sqm	1	15.00	5.35	5.55	5.45		81.75		
75.00	90.00		Sqm	1	15.00	5.55	6.00	5.78		86.63		
90.00	105.00		Sqm	1	15.00	6.00	6.10	6.05		90.75		
105.00	120.00		Sqm	1	14.70	6.10	6.20	6.15		90.40		
120.00	134.70											
		10th A Cross										
		(From West to East)										
0.00	2.80		Sqm	1	2.80	4.80	4.50	4.65		13.02		
		2nd Main Road										
		(From West to East)										
0.00	15.00		Sqm	1	15.00	8.80	8.70	8.75		131.25		
15.00	30.00		Sqm	1	15.00	8.70	9.13	8.92		133.73		
30.00	45.00		Sqm	1	15.00	9.13	8.50	8.82		132.23		
45.00	60.00		Sqm	1	15.00	8.50	8.40	8.45		126.75		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		1st Cross Road										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	6.50	5.40	5.95		89.25		
15.00	25.40		Sqm	1	10.40	5.40	6.00	5.70		59.28		
		M S Nagar										
		11th A Cross/2nd Main Road										
		(From South to North)										
0.00	15.00		Sqm	1	15.00	4.80	5.80	5.30		79.50		
15.00	30.00		Sqm	1	15.00	5.80	5.30	5.55		83.25		
30.00	45.00		Sqm	1	15.00	5.30	6.15	5.73		85.88		
45.00	60.00		Sqm	1	15.00	6.15	6.48	6.32		94.73		
60.00	65.80		Sqm	1	5.80	6.48	6.49	6.49		37.61		
		11th Cross Road										
		(From South to North)										
0.00	15.00		Sqm	1	15.00	4.20	4.10	4.15		62.25		
15.00	30.00		Sqm	1	15.00	4.10	3.80	3.95		59.25		
30.00	45.00		Sqm	1	15.00	3.80	3.65	3.73		55.88		
45.00	60.00		Sqm	1	15.00	3.65	4.00	3.83		57.38		
60.00	70.00		Sqm	1	10.00	4.00	4.10	4.05		40.50		
70.00	75.00		Sqm	1	5.00	4.10	4.00	4.05		20.25		
75.00	90.00		Sqm	1	15.00	4.00	4.64	4.32		64.80		
90.00	105.00		Sqm	1	15.00	4.64	4.90	4.77		71.55		
105.00	120.00		Sqm	1	15.00	4.90	4.90	4.90		73.50		
120.00	135.00		Sqm	1	15.00	4.90	4.90	4.90		73.50		
135.00	150.00		Sqm	1	15.00	4.90	5.00	4.95		74.25		
150.00	165.00		Sqm	1	15.00	5.00	4.90	4.95		74.25		
165.00	168.00		Sqm	1	3.00	4.90	4.75	4.83		14.48		
		10th Cross Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	5.35	5.30	5.33		79.88		
15.00	30.00		Sqm	1	15.00	5.30	5.10	5.20		78.00		
30.00	45.00		Sqm	1	15.00	5.10	4.40	4.75		71.25		
45.00	60.00		Sqm	1	15.00	4.40	4.50	4.45		66.75		
60.00	75.00		Sqm	1	15.00	4.50	4.60	4.55		68.25		
75.00	90.00		Sqm	1	15.00	4.60	4.48	4.54		68.10		
90.00	105.00		Sqm	1	15.00	4.48	4.84	4.66		69.90		
105.00	108.60		Sqm	1	3.60	4.84	4.85	4.85		17.44		
108.60	117.40		Sqm	1	8.80	5.35	4.80	5.08		44.66		
117.40	120.00		Sqm	1	2.60	4.50	4.60	4.55		11.83		
120.00	135.00		Sqm	1	15.00	4.60	4.49	4.55		68.18		
135.00	150.00		Sqm	1	15.00	4.49	4.67	4.58		68.70		
150.00	165.00		Sqm	1	15.00	4.67	4.55	4.61		69.15		
165.00	167.60		Sqm	1	2.60	4.55	4.90	4.73		12.29		
		10th A Cross										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	6.00	5.75	5.88		88.13		
15.00	30.00		Sqm	1	15.00	5.75	5.40	5.58		83.63		
30.00	45.00		Sqm	1	15.00	5.40	5.40	5.40		81.00		
45.00	60.00		Sqm	1	15.00	5.40	5.10	5.25		78.75		
60.00	75.00		Sqm	1	15.00	5.10	5.35	5.23		78.38		
75.00	90.00		Sqm	1	15.00	5.35	5.55	5.45		81.75		
90.00	105.00		Sqm	1	15.00	5.55	6.00	5.78		86.63		
105.00	120.00		Sqm	1	15.00	6.00	6.10	6.05		90.75		
120.00	134.70		Sqm	1	14.70	6.10	6.20	6.15		90.40		
		10th A Cross										
		(From West to East)										
0.00	2.80		Sqm	1	2.80	4.80	4.50	4.65		13.02		
		2nd Main Road										
		(From West to East)										
0.00	15.00		Sqm	1	15.00	8.80	8.70	8.75		131.25		
15.00	30.00		Sqm	1	15.00	8.70	9.13	8.92		133.73		
30.00	45.00		Sqm	1	15.00	9.13	8.50	8.82		132.23		
45.00	60.00		Sqm	1	15.00	8.50	8.40	8.45		126.75		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
60.00	75.00		Sqm	1	15.00	8.40	8.55	8.48		127.13		
75.00	90.00		Sqm	1	15.00	8.55	8.10	8.33		124.88		
90.00	105.00		Sqm	1	15.00	8.10	7.60	7.85		117.75		
105.00	114.30		Sqm	1	9.30	7.60	8.00	7.80		72.54		
114.30	129.30		Sqm	1	15.00	8.00	7.45	7.73		115.88		
129.30	144.30		Sqm	1	15.00	7.45	6.85	7.15		107.25		
144.30	159.30		Sqm	1	15.00	6.85	6.80	6.83		102.38		
159.30	174.30		Sqm	1	15.00	6.80	6.90	6.85		102.75		
174.30	189.30		Sqm	1	15.00	6.90	7.65	7.28		109.13		
189.30	192.60		Sqm	1	3.30	7.65	7.40	7.53		24.83		
		Cut Portion										
0.00	2.60		Sqm	1	2.60	2.10	2.10	2.10		5.46		
		2nd Main Road To M S Nagar Road										
		(From West to East)										
0.00	15.00		Sqm	1	15.00	5.10	4.36	4.73		70.95		
15.00	30.00		Sqm	1	15.00	4.36	4.40	4.38		65.70		
30.00	33.70		Sqm	1	3.70	4.40	4.60	4.50		16.65		
		(From South to North)										
0.00	15.00		Sqm	1	15.00	5.45	5.20	5.33		79.88		
15.00	30.00		Sqm	1	15.00	5.20	5.40	5.30		79.50		
30.00	45.00		Sqm	1	15.00	5.40	5.70	5.55		83.25		
45.00	60.00		Sqm	1	15.00	5.70	5.25	5.48		82.13		
60.00	75.00		Sqm	1	15.00	5.25	5.40	5.33		79.88		
75.00	90.00		Sqm	1	15.00	5.40	5.40	5.40		81.00		
90.00	105.00		Sqm	1	15.00	5.40	5.40	5.40		81.00		
105.00	120.00		Sqm	1	15.00	5.40	5.58	5.49		82.35		
120.00	135.00		Sqm	1	15.00	5.58	5.40	5.49		82.35		
135.00	150.00		Sqm	1	15.00	5.40	5.35	5.38		80.63		
150.00	165.00		Sqm	1	15.00	5.35	5.20	5.28		79.13		
165.00	180.00		Sqm	1	15.00	5.20	5.20	5.20		78.00		
180.00	195.00		Sqm	1	15.00	5.20	5.54	5.37		80.55		
195.00	197.80		Sqm	1	2.80	5.54	6.40	5.97		16.72		
		(From East to West)										
0.00	15.00		Sqm	1	15.00	3.90	3.65	3.78		56.63		
15.00	30.00		Sqm	1	15.00	3.65	3.68	3.67		54.98		
30.00	45.00		Sqm	1	15.00	3.68	3.98	3.83		57.45		
45.00	49.80		Sqm	1	4.80	3.98	4.20	4.09		19.63		
49.80	51.90		Sqm	1	2.10	4.20	7.50	5.85		12.29		
		3A Cross Road										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	3.85	3.63	3.74		56.10		
15.00	30.00		Sqm	1	15.00	3.63	3.63	3.63		54.45		
30.00	41.40		Sqm	1	11.40	3.63	4.32	3.98		45.32		
41.40	44.50		Sqm	1	3.10	4.32	7.35	5.84		18.09		
		(From North to South)										
0.00	15.00		Sqm	1	15.00	4.10	3.60	3.85		57.75		
15.00	18.60		Sqm	1	3.60	3.60	3.65	3.63		13.05		
		5th Cross Road										
		(From North to South)										
0.00	3.40		Sqm	1	3.40	8.20	6.80	7.50		25.50		
3.40	15.00		Sqm	1	11.60	6.80	6.70	6.75		78.30		
15.00	30.00		Sqm	1	15.00	6.70	6.10	6.40		96.00		
30.00	45.00		Sqm	1	15.00	6.10	6.20	6.15		92.25		
45.00	56.60		Sqm	1	11.60	6.20	6.15	6.18		71.63		
0.00	12.10	Cut Portion	Sqm	1	12.10	2.40	2.40	2.40		29.04		
		6th Cross Road (W1935)										
0.00	2.00	(From South to North)	Sqm	1	2.00	7.50	5.90	6.70		13.40		
2.00	15.00		Sqm	1	13.00	5.90	5.95	5.93		77.03		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.00	30.00		Sqm	1	15.00	5.95	6.00	5.98		89.63		
15.00	45.00		Sqm	1	15.00	6.00	5.50	5.75		86.25		
30.00	60.00		Sqm	1	15.00	5.50	5.35	5.43		81.38		
45.00	75.00		Sqm	1	15.00	5.35	5.55	5.45		81.75		
60.00	90.00		Sqm	1	15.00	5.55	5.55	5.55		83.25		
75.00	105.00		Sqm	1	15.00	5.55	5.60	5.58		83.63		
90.00	120.00		Sqm	1	15.00	5.60	5.60	5.60		84.00		
105.00	135.00		Sqm	1	15.00	5.60	5.75	5.68		85.13		
120.00	150.00		Sqm	1	15.00	5.75	4.85	5.30		79.50		
135.00	165.00		Sqm	1	15.00	4.85	4.80	4.83		72.38		
150.00	180.00		Sqm	1	15.00	4.80	6.10	5.45		81.75		
165.00	181.50		Sqm	1	1.50	6.10	5.40	5.75		8.63		
180.00												
		MSR Mansion Road										
		(North to South)										
0.00	5.80		Sqm	1	5.80	5.75	7.15	6.45		37.41		
5.80	9.70		Sqm	1	3.90	10.70	8.40	9.55		37.25		
9.70	15.00		Sqm	1	5.30	8.40	8.25	8.33		44.12		
15.00	30.00		Sqm	1	15.00	8.25	7.40	7.83		117.38		
30.00	45.00		Sqm	1	15.00	7.40	6.85	7.13		106.88		
45.00	50.00		Sqm	1	5.00	6.85	7.10	6.98		34.88		
		Nisarga Layout										
		7th Cross, Zayan Travels Car Service Centre Road, North To South										
0.00	15.00		Sqm	1	15.00	5.00	4.85	4.93		73.88		
15.00	30.00		Sqm	1	15.00	4.85	4.60	4.73		70.88		
30.00	45.00		Sqm	1	15.00	4.60	5.15	4.88		73.13		
45.00	60.00		Sqm	1	15.00	5.15	5.00	5.08		76.13		
60.00	75.00		Sqm	1	15.00	5.00	5.10	5.05		75.75		
75.00	90.00		Sqm	1	15.00	5.10	5.00	5.05		75.75		
90.00	101.50		Sqm	1	11.50	5.00	4.70	4.85		55.78		
		West To East										
0.00	15.00		Sqm	1	15.00	4.90	4.80	4.85		72.75		
15.00	15.70		Sqm	1	0.70	4.80	4.80	4.80		3.36		
15.70	30.00		Sqm	1	14.30	5.30	5.60	5.45		77.94		
30.00	45.00		Sqm	1	15.00	5.60	5.15	5.38		80.63		
45.00	46.70		Sqm	1	1.70	5.15	5.15	5.15		8.76		
46.70	51.60		Sqm	1	4.90	4.15	3.95	4.05		19.85		
51.60	56.20		Sqm	1	4.60	5.30	5.25	5.28		24.27		
56.20	64.60		Sqm	1	8.40	4.20	4.30	4.25		35.70		
64.60	75.00		Sqm	1	10.40	5.30	5.35	5.33		55.38		
75.00	76.60		Sqm	1	1.60	5.35	5.36	5.36		8.57		
		5th Cross Road,										
		North To South										
0.00	11.10		Sqm	1	11.10	5.70	5.90	5.80		64.38		
11.10	20.00		Sqm	1	8.90	5.10	5.35	5.23		46.50		
20.00	23.80		Sqm	1	3.80	7.00	6.95	6.98		26.51		
23.80	30.00		Sqm	1	6.20	6.05	5.95	6.00		37.20		
30.00	45.00		Sqm	1	15.00	5.95	5.50	5.73		85.88		
45.00	60.00		Sqm	1	15.00	5.50	6.00	5.75		86.25		
60.00	66.90		Sqm	1	6.90	6.00	6.30	6.15		42.44		
66.90	75.00		Sqm	1	8.10	4.90	5.70	5.30		42.93		
75.00	75.60		Sqm	1	0.60	5.70	5.65	5.68		3.40		
75.60	76.80		Sqm	1	1.20	2.95	3.00	2.98		3.57		
		Mithun White Pearl Apartment Road										
		(East To West)										
0.00	15.00		Sqm	1	15.00	6.60	6.75	6.68		100.13		
15.00	30.00		Sqm	1	15.00	6.75	6.50	6.63		99.38		
30.00	45.00		Sqm	1	15.00	6.50	6.45	6.48		97.13		
45.00	60.00		Sqm	1	15.00	6.45	6.45	6.45		96.75		
60.00	75.00		Sqm	1	15.00	6.45	6.25	6.35		95.25		
75.00	90.00		Sqm	1	15.00	6.25	6.20	6.23		93.38		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
90.00	96.40		Sqm	1	6.40	6.20	5.85	6.03		38.56		
		Chembar	Sqm	-1	0.64					-0.64		
								Area of				
			Sqm	-4	0.70	1.00	1.00	1.00		-2.80		
			Sqm	-3	0.90	0.80	0.80	0.80		-2.16		
		Katgenahalli										
		Muneshwara Provision Store Beside Road										
		Kalidas Layout										
		3rd Main Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	6.70	6.65	6.68		100.13		
15.00	30.00		Sqm	1	15.00	6.65	6.65	6.65		99.75		
30.00	45.00		Sqm	1	15.00	6.65	6.00	6.33		94.88		
45.00	60.00		Sqm	1	15.00	6.00	5.80	5.90		88.50		
60.00	66.40		Sqm	1	6.40	5.80	5.60	5.70		36.48		
66.40	75.00		Sqm	1	8.60	5.60	5.60	5.60		48.16		
75.00	90.00		Sqm	1	15.00	5.60	5.50	5.55		83.25		
90.00	105.00		Sqm	1	15.00	5.50	5.80	5.65		84.75		
105.00	113.00		Sqm	1	8.00	5.80	4.30	5.05		40.40		
		Cross Road - 2										
		(From North to South)										
0.00	4.30		Sqm	1	4.30	5.10	5.00	5.05		21.72		
4.30	15.00		Sqm	1	10.70	5.00	5.10	5.05		54.04		
15.00	20.60		Sqm	1	5.60	5.10	5.30	5.20		29.12		
20.60	30.00		Sqm	1	9.40	6.65	6.20	6.43		60.40		
30.00	40.60		Sqm	1	10.60	6.20	6.60	6.40		67.84		
40.60	45.00		Sqm	1	4.40	6.60	5.90	6.25		27.50		
45.00	60.00		Sqm	1	15.00	5.90	5.95	5.93		88.88		
60.00	75.00		Sqm	1	15.00	5.95	5.85	5.90		88.50		
75.00	90.00		Sqm	1	15.00	5.85	6.38	6.12		91.73		
90.00	105.00		Sqm	1	15.00	6.38	5.50	5.94		89.10		
105.00	120.00		Sqm	1	15.00	5.50	5.69	5.60		83.93		
120.00	123.00		Sqm	1	3.00	5.69	5.00	5.35		16.04		
		Cross Road - 1										
		(From South to North)										
0.00	15.00		Sqm	1	15.00	4.75	4.55	4.65		69.75		
15.00	30.00		Sqm	1	15.00	4.55	5.10	4.83		72.38		
30.00	45.00		Sqm	1	15.00	5.10	4.80	4.95		74.25		
45.00	60.00		Sqm	1	15.00	4.80	4.55	4.68		70.13		
60.00	75.00		Sqm	1	15.00	4.55	5.00	4.78		71.63		
75.00	88.60		Sqm	1	13.60	5.00	4.50	4.75		64.60		
		Kattigenahalli										
		Durgamba Layout										
		Amulya Family Restaurant Road (N-S)										
0.00	15.00		Sqm	1	15.00	6.90	6.40	6.65		99.75		
15.00	30.00		Sqm	1	15.00	6.40	6.05	6.23		93.38		
30.00	45.00		Sqm	1	15.00	5.60	5.30	5.45		81.75		
45.00	60.00		Sqm	1	15.00	5.30	4.95	5.13		76.88		
60.00	75.00		Sqm	1	15.00	4.95	5.05	5.00		75.00		
75.00	81.00		Sqm	1	6.00	5.05	5.05	5.05		30.30		
81.00	90.00		Sqm	1	9.00	5.70	5.90	5.80		52.20		
90.00	105.00		Sqm	1	15.00	5.90	5.30	5.60		84.00		
105.00	118.80		Sqm	1	13.80	5.30	4.60	4.95		68.31		
118.80	127.90		Sqm	1	9.10	5.80	5.85	5.83		53.01		
127.90	135.00		Sqm	1	7.10	4.95	4.85	4.90		34.79		
135.00	137.10		Sqm	1	2.10	4.85	5.05	4.95		10.40		
137.10	150.00		Sqm	1	12.90	4.35	4.95	4.65		59.99		
150.00	165.00		Sqm	1	15.00	4.95	4.60	4.78		71.63		
165.00	180.00		Sqm	1	15.00	4.60	5.25	4.93		73.88		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
180.00	182.50		Sqm	1	2.50	5.25	5.15	5.20		13.00		
182.50	195.00		Sqm	1	12.50	5.85	6.60	6.23		77.81		
195.00	210.00		Sqm	1	15.00	6.60	6.15	6.38		95.63		
210.00	218.00		Sqm	1	8.00	6.15	6.00	6.08		48.60		
		Kaustaba House Road #33 (W-E)										
0.00	6.30		Sqm	1	6.30	7.45	7.55	7.50		47.25		
6.30	15.00		Sqm	1	8.70	6.80	6.48	6.64		57.77		
15.00	30.00		Sqm	1	15.00	6.48	6.00	6.24		93.60		
30.00	45.00		Sqm	1	15.00	6.00	5.70	5.85		87.75		
45.00	57.90		Sqm	1	12.90	5.70	6.05	5.88		75.79		
57.90	60.00		Sqm	1	2.10	6.95	7.70	7.33		15.38		
60.00	63.60		Sqm	1	3.60	7.70	7.65	7.68		27.63		
		Sukruthi House Road #26 (S-N)										
0.00	8.30		Sqm	1	8.30	5.60	5.90	5.75		47.73		
8.30	15.00		Sqm	1	6.70	5.35	4.90	5.13		34.34		
15.00	30.00		Sqm	1	15.00	4.90	5.80	5.35		80.25		
30.00	45.00		Sqm	1	15.00	5.80	5.35	5.58		83.63		
45.00	60.00		Sqm	1	15.00	5.35	5.30	5.33		79.88		
60.00	60.50		Sqm	1	0.50	5.30	5.30	5.30		2.65		
60.50	75.00		Sqm	1	14.50	5.85	6.20	6.03		87.36		
75.00	90.00		Sqm	1	15.00	6.20	5.40	5.80		87.00		
90.00	98.70		Sqm	1	8.70	5.40	5.20	5.30		46.11		
98.70	105.00		Sqm	1	6.30	4.40	4.95	4.68		29.45		
105.00	108.20		Sqm	1	3.20	4.95	4.95	4.95		15.84		
108.20	112.20		Sqm	1	4.00	5.50	5.20	5.35		21.40		
112.20	120.00		Sqm	1	7.80	4.40	4.60	4.50		35.10		
120.00	125.80		Sqm	1	5.80	4.60	4.50	4.55		26.39		
125.80	135.70		Sqm	1	9.90	4.00	4.45	4.23		41.83		
135.70	143.90		Sqm	1	8.20	5.60	5.95	5.78		47.36		
143.90	150.00		Sqm	1	6.10	6.65	5.75	6.20		37.82		
150.00	164.30		Sqm	1	14.30	5.75	5.85	5.80		82.94		
		SP Singh House Road (E-W)										
0.00	15.00		Sqm	1	15.00	6.35	5.65	6.00		90.00		
15.00	19.10		Sqm	1	4.10	5.65	6.00	5.83		23.88		
19.10	30.00		Sqm	1	10.90	5.20	5.65	5.43		59.13		
30.00	34.20		Sqm	1	4.20	5.65	6.10	5.88		24.68		
		Deduction										
		Chamber	Sqm	-1	0.70	1.00	1.00	1.00		-0.70		
		Manhole	Sqm	-1	0.64					-0.64		
					Area of Circle =							
		Manhole	Sqm	-1	1.13					-1.13		
					Area of Circle =							
		Vidhana Soudha Layout (From North to South)										
0.00	15.00		Sqm	1	15.00	6.10	5.45	5.78		86.63		
15.00	29.30		Sqm	1	14.30	5.45	8.30	6.88		98.31		
		(From East to West)										
0.00	15.00		Sqm	1	15.00	9.40	8.90	9.15		137.25		
15.00	30.00		Sqm	1	15.00	8.90	8.60	8.75		131.25		
30.00	45.00		Sqm	1	15.00	8.60	8.90	8.75		131.25		
45.00	60.00		Sqm	1	15.00	8.90	8.20	8.55		128.25		
60.00	75.00		Sqm	1	15.00	8.20	8.25	8.23		123.38		
75.00	90.00		Sqm	1	15.00	8.25	8.50	8.38		125.63		
90.00	105.00		Sqm	1	15.00	8.50	8.30	8.40		126.00		
105.00	117.80		Sqm	1	12.80	8.30	8.25	8.28		105.92		
117.80	125.10		Sqm	1	7.30	11.35	11.25	11.30		82.49		
125.10	135.00		Sqm	1	9.90	8.20	8.05	8.13		80.44		
135.00	150.00		Sqm	1	15.00	8.05	8.05	8.05		120.75		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
150.00	150.90		Sqm	1	0.90	10.95	10.95	10.95		9.86		
150.90	165.00		Sqm	1	14.10	8.30	8.35	8.33		117.38		
165.00	180.00		Sqm	1	15.00	8.35	8.42	8.39		125.78		
180.00	184.90		Sqm	1	4.90	8.42	8.55	8.49		41.58		
184.90	193.50		Sqm	1	8.60	11.20	11.30	11.25		96.75		
193.50	195.00		Sqm	1	1.50	8.30	8.30	8.30		12.45		
195.00	210.00		Sqm	1	15.00	8.30	8.15	8.23		123.38		
210.00	225.00		Sqm	1	15.00	8.15	8.30	8.23		123.38		
225.00	240.00		Sqm	1	15.00	8.30	9.00	8.65		129.75		
240.00	255.00		Sqm	1	15.00	9.00	8.85	8.93		133.88		
255.00	258.00		Sqm	1	3.00	8.85	8.25	8.55		25.65		
258.00	265.10		Sqm	1	7.10	9.70	9.80	9.75		69.23		
265.10	270.00		Sqm	1	4.90	8.40	8.35	8.38		41.04		
270.00	285.00		Sqm	1	15.00	8.35	8.25	8.30		124.50		
285.00	291.00		Sqm	1	6.00	8.25	8.20	8.23		49.35		
291.00	299.80		Sqm	1	8.80	9.55	9.40	9.48		83.38		
299.80	300.00		Sqm	1	0.20	8.15	8.14	8.15		1.63		
300.00	301.00		Sqm	1	1.00	8.14	8.15	8.15		8.15		
301.00	307.30		Sqm	1	6.30	9.81	9.80	9.81		61.77		
307.30	315.00		Sqm	1	7.70	8.10	8.15	8.13		62.56		
315.00	323.00		Sqm	1	8.00	8.15	8.25	8.20		65.60		
323.00	332.00		Sqm	1	9.00	9.60	9.60	9.60		86.40		
332.00	343.00		Sqm	1	11.00	9.40	9.60	9.50		104.50		
343.00	345.00		Sqm	1	2.00	8.10	8.20	8.15		16.30		
345.00	358.90		Sqm	1	13.90	8.20	8.15	8.18		113.63		
358.90	368.10		Sqm	1	9.20	9.70	9.71	9.71		89.29		
368.10	375.00		Sqm	1	6.90	8.15	8.15	8.15		56.23		
375.00	382.60		Sqm	1	7.60	8.15	8.30	8.23		62.51		
382.60	391.90		Sqm	1	9.30	9.90	9.50	9.70		90.21		
391.90	393.30		Sqm	1	1.40	7.90	8.00	7.95		11.13		
393.30	400.00		Sqm	1	6.70	9.20	9.20	9.20		61.64		
400.00	405.00		Sqm	1	5.00	7.90	7.40	7.65		38.25		
405.00	420.00		Sqm	1	15.00	7.40	7.60	7.50		112.50		
420.00	435.00		Sqm	1	15.00	7.60	7.40	7.50		112.50		
435.00	444.20		Sqm	1	9.20	9.00	9.10	9.05		83.26		
444.20	446.30		Sqm	1	2.10	7.30	7.45	7.38		15.49		
446.30	456.40		Sqm	1	10.10	9.15	9.10	9.13		92.16		
456.40	465.00		Sqm	1	8.60	7.45	7.35	7.40		63.64		
465.00	480.00		Sqm	1	15.00	7.35	7.25	7.30		109.50		
480.00	495.00		Sqm	1	15.00	7.25	7.65	7.45		111.75		
495.00	510.00		Sqm	1	15.00	7.65	8.50	8.08		121.13		
510.00	525.20		Sqm	1	15.20	10.00	10.60	10.30		156.56		
525.20	540.00		Sqm	1	14.80	8.50	7.60	8.05		119.14		
540.00	555.00		Sqm	1	15.00	7.60	7.50	7.55		113.25		
555.00	560.90		Sqm	1	5.90	7.50	7.50	7.50		44.25		
560.90	562.70		Sqm	1	1.80	4.80	4.80	4.80		8.64		
		Car 24 Beside Road From Agrahara Main Road to Lake East to West										
0.00	15.00		Sqm	1	15.00	4.80	4.60	4.70		70.50		
5.00	27.00		Sqm	1	12.00	4.60	4.65	4.63		55.50		
7.00	30.00		Sqm	1	3.00	5.40	5.70	5.55		16.65		
0.00	45.00		Sqm	1	15.00	5.70	5.70	5.70		85.50		
5.00	60.00		Sqm	1	15.00	5.70	6.30	6.00		90.00		
0.00	75.00		Sqm	1	15.00	6.30	6.30	6.30		94.50		
5.00	90.00		Sqm	1	15.00	6.30	6.50	6.40		96.00		
0.00	105.00		Sqm	1	15.00	6.50	6.65	6.58		98.63		
5.00	120.00		Sqm	1	15.00	6.65	6.40	6.53		97.88		
0.00	135.00		Sqm	1	15.00	6.40	6.20	6.30		94.50		
5.00	150.00		Sqm	1	15.00	6.20	6.10	6.15		92.25		
0.00	165.00		Sqm	1	15.00	6.10	6.30	6.20		93.00		
5.00	180.00		Sqm	1	15.00	6.30	6.10	6.20		93.00		
0.00	195.00		Sqm	1	15.00	6.10	6.25	6.18		92.63		
5.00	210.00		Sqm	1	15.00	6.25	6.50	6.38		95.63		
0.00	225.00		Sqm	1	15.00	6.50	6.40	6.45		96.75		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
225.00	240.00		Sqm	1	15.00	6.40	6.50	6.45		96.75		
240.00	255.00		Sqm	1	15.00	6.50	6.65	6.58		98.63		
255.00	270.00		Sqm	1	15.00	6.65	6.70	6.68		100.13		
270.00	285.00		Sqm	1	15.00	6.70	6.45	6.58		98.63		
285.00	300.00		Sqm	1	15.00	6.45	6.20	6.33		94.88		
300.00	315.00		Sqm	1	15.00	6.20	6.10	6.15		92.25		
315.00	330.00		Sqm	1	15.00	6.10	6.10	6.10		91.50		
330.00	345.00		Sqm	1	15.00	6.10	6.00	6.05		90.75		
345.00	360.00		Sqm	1	15.00	6.00	6.60	6.30		94.50		
360.00	375.00		Sqm	1	15.00	6.60	6.00	6.30		94.50		
375.00	390.00		Sqm	1	15.00	6.00	6.10	6.05		90.75		
390.00	405.00		Sqm	1	15.00	6.10	6.30	6.20		93.00		
405.00	410.00		Sqm	1	5.00	6.30	6.40	6.35		31.75		
410.00	419.00		Sqm	1	9.00	4.70	4.50	4.60		41.40		
419.00	420.00		Sqm	1	1.00	6.30	6.30	6.30		6.30		
420.00	435.00		Sqm	1	15.00	6.30	6.30	6.30		94.50		
435.00	450.00		Sqm	1	15.00	6.30	6.80	6.55		98.25		
450.00	465.00		Sqm	1	15.00	6.80	7.10	6.95		104.25		
465.00	480.00		Sqm	1	15.00	7.10	5.80	6.45		96.75		
480.00	495.00		Sqm	1	15.00	5.80	5.20	5.50		82.50		
495.00	510.00		Sqm	1	15.00	5.20	3.95	4.58		68.63		
510.00	512.00		Sqm	1	2.00	3.95	3.80	3.88		7.75		
512.00	525.00		Sqm	1	13.00	4.70	5.45	5.08		65.98		
525.00	540.00		Sqm	1	15.00	5.45	6.10	5.78		86.63		
540.00	546.00		Sqm	1	6.00	6.10	5.50	5.80		34.80		
		Cross Road-1										
		South to North										
0.00	6.00		Sqm	1	6.00	12.00	5.90	8.95		53.70		
6.00	12.00		Sqm	1	6.00	5.90	5.00	5.45		32.70		
12.00	15.00		Sqm	1	3.00	6.00	6.00	6.00		18.00		
15.00	19.00		Sqm	1	4.00	6.00	5.70	5.85		23.40		
		Cross Road-2										
		South to north										
0.00	15.00		Sqm	1	15.00	6.50	6.00	6.25		93.75		
15.00	30.00		Sqm	1	15.00	6.00	6.00	6.00		90.00		
30.00	45.00		Sqm	1	15.00	6.00	6.00	6.00		90.00		
45.00	60.00		Sqm	1	15.00	6.00	6.30	6.15		92.25		
60.00	67.70		Sqm	1	7.70	6.30	6.60	6.45		49.67		
67.70	69.70		Sqm	1	2.00	6.60	7.30	6.95		13.90		
		Total Executed Quantity								**25596.95**	**6.42**	**164333.00**
		Tender Quantity								**26339.70**		
Item no. 14		Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specification and directions of the Engineer in charge.										
		Defence Colony										
		6th Main Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	4.95	5.20	5.08	0.20	15.23		
15.00	30.00		Cum	1	15.00	5.20	5.20	5.20	0.20	15.60		
30.00	40.10		Cum	1	10.10	5.20	5.50	5.35	0.20	10.81		
40.10	43.70		Cum	1	3.60	4.32	4.75	4.54	0.20	3.27		
43.70	45.00		Cum	1	1.30	5.28	5.20	5.24	0.20	1.36		
45.00	60.00		Cum	1	15.00	5.20	4.90	5.05	0.20	15.15		
60.00	75.00		Cum	1	15.00	4.90	5.50	5.20	0.20	15.60		
75.00	90.00		Cum	1	15.00	5.50	5.10	5.30	0.20	15.90		
90.00	105.00		Cum	1	15.00	5.10	5.00	5.05	0.20	15.15		
105.00	110.80		Cum	1	5.80	5.00	5.10	5.05	0.20	5.86		
		8th Main Road										
		(From East to West)										
0.00	15.00		Cum	1	15.00	4.40	4.45	4.43	0.20	13.28		
15.00	30.00		Cum	1	15.00	4.45	4.90	4.68	0.20	14.03		
30.00	45.00		Cum	1	15.00	4.95	5.10	5.03	0.20	15.08		
45.00	60.00		Cum	1	15.00	5.10	5.00	5.05	0.20	15.15		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
60.00	75.00		Cum	1	15.00	4.95	5.10	5.03	0.20	15.08		
75.00	90.00		Cum	1	15.00	5.10	5.05	5.08	0.20	15.23		
90.00	105.00		Cum	1	15.00	4.95	5.20	5.08	0.20	15.23		
105.00	120.00		Cum	1	15.00	5.20	5.05	5.13	0.20	15.38		
120.00	131.00		Cum	1	11.00	4.95	4.95	4.95	0.20	10.89		
		Cross Road 2										
		(From East to West)										
0.00	15.00		Cum	1	15.00	4.25	4.10	4.18	0.20	12.53		
15.00	30.00		Cum	1	15.00	4.10	4.00	4.05	0.20	12.15		
30.00	31.50		Cum	1	1.50	4.00	4.00	4.00	0.20	1.20		
		Cross Road 1										
		(From East to West)										
0.00	15.00		Cum	1	15.00	4.40	4.48	4.44	0.20	13.32		
15.00	29.50		Cum	1	14.50	4.48	4.65	4.57	0.20	13.24		
		Nithish Central Park Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	5.80	5.40	5.60	0.20	16.80		
15.00	21.40		Cum	1	6.40	5.40	5.70	5.55	0.20	7.10		
21.40	29.60		Cum	1	8.20	5.05	4.80	4.93	0.20	8.08		
29.60	30.00		Cum	1	0.40	5.52	5.50	5.51	0.20	0.44		
30.00	45.00		Cum	1	15.00	5.50	5.15	5.33	0.20	15.98		
45.00	60.00		Cum	1	15.00	5.15	5.15	5.15	0.20	15.45		
60.00	75.00		Cum	1	15.00	5.15	5.04	5.10	0.20	15.29		
75.00	80.00		Cum	1	5.00	5.04	6.00	5.52	0.20	5.52		
80.00	83.70		Cum	1	3.70	6.00	5.95	5.98	0.20	4.42		
83.70	87.60		Cum	1	3.90	5.30	5.30	5.30	0.20	4.13		
87.60	93.20		Cum	1	5.60	6.30	6.20	6.25	0.20	7.00		
93.20	96.20		Cum	1	3.00	5.40	5.00	5.20	0.20	3.12		
		Anand Nagar										
		1st Cross Road										
		Royal ACE Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	4.80	5.30	5.05	0.20	15.15		
15.00	22.80		Cum	1	7.80	5.30	5.40	5.35	0.20	8.35		
22.80	32.00		Cum	1	9.20	4.95	4.80	4.88	0.20	8.97		
32.00	45.00		Cum	1	13.00	4.75	5.03	4.89	0.20	12.71		
45.00	60.00		Cum	1	15.00	5.03	4.95	4.99	0.20	14.97		
60.00	75.00		Cum	1	15.00	4.95	5.30	5.13	0.20	15.38		
75.00	90.00		Cum	1	15.00	4.95	5.45	5.20	0.20	15.60		
90.00	95.10		Cum	1	5.10	5.45	5.65	5.55	0.20	5.66		
		Palanahalli										
		For Cut Portions										
		(From West to East)										
0.00	8.40		Cum	1	8.40	1.30	1.30	1.30	0.20	2.18		
8.40	24.00		Cum	1	15.60	2.50	3.10	2.80	0.20	8.74		
24.00	27.60	No Work	Cum	1	0.00	0.00	0.00	0.00	0.20	0.00		
27.60	42.60		Cum	1	15.00	3.35	2.52	2.94	0.20	8.81		
42.60	45.00		Cum	1	2.40	2.52	2.50	2.51	0.20	1.20		
45.00	60.00		Cum	1	15.00	2.50	2.50	2.50	0.20	7.50		
60.00	75.00		Cum	1	15.00	2.50	1.95	2.23	0.20	6.68		
75.00	90.00		Cum	1	15.00	1.95	2.50	2.23	0.20	6.68		
90.00	105.00		Cum	1	15.00	2.50	1.85	2.18	0.20	6.53		
105.00	115.80		Cum	1	10.80	1.85	3.00	2.43	0.20	5.24		
115.80	119.00		Cum	1	3.20	3.00	4.30	3.65	0.20	2.34		
119.00	125.50		Cum	1	6.50	1.30	0.85	1.08	0.20	1.40		
125.50	132.60	No Work	Cum	1	0.00	0.00	0.00	0.00	0.20	0.00		
132.60	135.60		Cum	1	3.00	1.50	1.65	1.58	0.20	0.95		
135.60	150.60		Cum	1	15.00	1.65	1.20	1.43	0.20	4.28		
150.60	152.60		Cum	1	2.00	4.10	4.10	4.10	0.20	1.64		
152.60	159.50		Cum	1	6.90	2.10	2.10	2.10	0.20	2.90		
159.50	174.50		Cum	1	15.00	2.10	1.00	1.55	0.20	4.65		
174.50	183.90		Cum	1	9.40	1.00	1.00	1.00	0.20	1.88		
183.90	198.90		Cum	1	15.00	1.00	1.00	1.00	0.20	3.00		
198.90	213.90		Cum	1	15.00	1.00	1.00	1.00	0.20	3.00		
213.90	214.30		Cum	1	0.40	1.00	1.70	1.35	0.20	0.11		
214.30	229.30		Cum	1	15.00	1.83	1.50	1.67	0.20	5.00		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Cum	1	13.90	1.83	1.50	1.67	0.20	4.63		
			Cum	1	3.10	1.95	1.90	1.93	0.20	1.19		
229.30	243.20											
243.20	246.30											
		For Road Cutting										
			Cum	1	4.50	0.40	0.25	0.33	0.20	0.29		
	4.50		Cum	1	5.00	0.40	0.20	0.30	0.20	0.30		
0.00	5.00		Cum	1	2.80	3.20	3.25	3.23	0.20	1.81		
0.00	2.80		Cum	1	4.70	0.70	0.45	0.58	0.20	0.54		
0.00	4.70		Cum	1	2.60	1.20	1.25	1.23	0.20	0.64		
0.00	2.60											
		Deducation										
		Chamber	Cum	-1	1.90			1.40	0.20	-0.53		
		Tree Pot	Cum	-9	0.20			0.10	0.20	-0.04		
		Electric Pole	Cum	-1	0.90			0.50	0.20	-0.09		
		Man Hole (1m Dia)	Cum	-1	Area = 0.25*3.142*1^2=0.785				0.20	-0.16		
		7th Main Road										
		(From North to South)										
			Cum	1	3.50	1.90	2.10	2.00	0.20	1.40		
2.10	5.60		Cum	1	2.50	2.40	2.80	2.60	0.20	1.30		
8.20	10.70		Cum	1	3.70	1.50	1.80	1.65	0.20	1.22		
12.50	16.20		Cum	1	4.00	2.90	2.70	2.80	0.20	2.24		
18.00	22.00		Cum	1	3.80	2.50	2.10	2.30	0.20	1.75		
24.20	28.00		Cum	1	6.20	1.20	1.20	1.20	0.20	1.49		
31.80	38.00		Cum	1	2.60	1.90	1.70	1.80	0.20	0.94		
40.00	42.60		Cum	1	4.10	2.30	2.50	2.40	0.20	1.97		
44.90	49.00		Cum	1	4.80	2.30	2.10	1.90	0.20	1.82		
51.20	56.00		Cum	1	3.50	2.30	2.70	2.20	0.20	1.54		
58.60	62.10		Cum	1	4.20	2.30	2.00	2.00	0.20	1.68		
67.00	71.20		Cum	1	3.20	2.30	2.00	2.00	0.20	1.28		
74.00	77.20		Cum	1	6.30	2.80	2.80	2.80	0.20	3.53		
81.70	88.00		Cum	1	4.40	1.60	2.40	2.90	0.20	2.55		
92.00	96.40		Cum	1	2.50	2.30	2.40	2.35	0.20	1.18		
99.30	101.80											
		2nd Cross										
		(From North to South)										
			Cum	1	7.00	1.20	1.20	1.20	0.20	1.68		
4.00	11.00		Cum	1	10.00	1.30	1.30	1.30	0.20	2.60		
17.00	27.00		Cum	1	7.00	1.60	1.60	1.60	0.20	2.24		
34.00	41.00		Cum	1	8.00	1.50	1.50	1.50	0.20	2.40		
48.00	56.00		Cum	1	6.00	1.20	1.20	1.20	0.20	1.44		
61.00	67.00		Cum	1	7.00	1.80	1.80	1.80	0.20	2.52		
71.00	78.00		Cum	1	6.00	2.10	2.10	2.10	0.20	2.52		
82.00	88.00		Cum	1	4.40	1.10	1.10	1.10	0.20	0.97		
92.00	96.40											
		1st Cross Road										
		(From East to West)										
			Cum	1	15.00	6.50	5.40	5.95	0.20	17.85		
0.00	15.00		Cum	1	10.40	5.40	6.00	5.70	0.20	11.86		
15.00	25.40											
		8th Main Road										
		North to South										
			Cum	1	2.00	1.10	1.10	1.10	0.20	0.44		
6.00	8.00		Cum	1	4.00	1.30	1.30	1.30	0.20	1.04		
12.00	16.00		Cum	1	3.00	1.00	1.00	1.00	0.20	0.60		
26.00	29.00		Cum	1	5.00	1.20	1.20	1.20	0.20	1.20		
42.00	47.00		Cum	1	5.00	0.90	0.90	0.90	0.20	0.90		
88.00	93.00											
		Vinayak Nagar										
		6th B Main Road										
		North to South										
			Cum	1	3.00	1.30	1.30	1.30	0.20	0.78		
8.00	11.00		Cum	1	4.00	1.40	1.40	1.40	0.20	1.12		
55.00	59.00		Cum	1	4.00	1.20	1.20	1.20	0.20	0.96		
63.00	67.00		Cum	1	3.00	0.85	0.85	0.85	0.20	0.51		
76.00	79.00											

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		M S Nagar										
		11th A Cross/2nd Main Road										
		(From South to North)										
			Cum	1	15.00	4.80	5.80	5.30	0.20	15.90		
0.00	15.00		Cum	1	15.00	5.80	5.30	5.55	0.20	16.65		
15.00	30.00		Cum	1	15.00	5.30	6.15	5.73	0.20	17.18		
30.00	45.00		Cum	1	15.00	6.15	6.48	6.32	0.20	18.95		
45.00	60.00		Cum	1	5.80	6.48	6.49	6.49	0.20	7.52		
60.00	65.80											
		11th Cross Road										
		(From South to North)										
			Cum	1	15.00	4.20	4.10	4.15	0.20	12.45		
0.00	15.00		Cum	1	15.00	4.10	3.80	3.95	0.20	11.85		
15.00	30.00		Cum	1	15.00	3.80	3.65	3.73	0.20	11.18		
30.00	45.00		Cum	1	15.00	3.65	4.00	3.83	0.20	11.48		
45.00	60.00		Cum	1	10.00	4.00	4.10	4.05	0.20	8.10		
60.00	70.00		Cum	1	5.00	4.10	4.00	4.05	0.20	4.05		
70.00	75.00		Cum	1	15.00	4.00	4.64	4.32	0.20	12.96		
75.00	90.00		Cum	1	15.00	4.64	4.90	4.77	0.20	14.31		
90.00	105.00		Cum	1	15.00	4.90	4.90	4.90	0.20	14.70		
105.00	120.00		Cum	1	15.00	4.90	4.90	4.90	0.20	14.70		
120.00	135.00		Cum	1	15.00	4.90	5.00	4.95	0.20	14.85		
135.00	150.00		Cum	1	15.00	5.00	4.90	4.95	0.20	14.85		
150.00	165.00		Cum	1	3.00	4.90	4.75	4.83	0.20	2.90		
165.00	168.00											
		10th Cross Road										
		(From North to South)										
			Cum	1	15.00	5.35	5.30	5.33	0.20	15.98		
0.00	15.00		Cum	1	15.00	5.30	5.10	5.20	0.20	15.60		
15.00	30.00		Cum	1	15.00	5.10	4.40	4.75	0.20	14.25		
30.00	45.00		Cum	1	15.00	4.40	4.50	4.45	0.20	13.35		
45.00	60.00		Cum	1	15.00	4.50	4.60	4.55	0.20	13.65		
60.00	75.00		Cum	1	15.00	4.60	4.48	4.54	0.20	13.62		
75.00	90.00		Cum	1	15.00	4.48	4.84	4.66	0.20	13.98		
90.00	105.00		Cum	1	3.60	4.84	4.85	4.85	0.20	3.49		
105.00	108.60		Cum	1	8.80	5.35	4.80	5.08	0.20	8.93		
108.60	117.40		Cum	1	2.60	4.50	4.60	4.55	0.20	2.37		
117.40	120.00		Cum	1	15.00	4.60	4.49	4.55	0.20	13.64		
120.00	135.00		Cum	1	15.00	4.49	4.67	4.58	0.20	13.74		
135.00	150.00		Cum	1	15.00	4.67	4.55	4.61	0.20	13.83		
150.00	165.00		Cum	1	2.60	4.55	4.90	4.73	0.20	2.46		
165.00	167.60											
		10th A Cross										
		(From North to South)										
0.00	15.00		Cum	1	15.00	6.00	5.75	5.88	0.20	17.63		
15.00	30.00		Cum	1	15.00	5.75	5.40	5.58	0.20	16.73		
30.00	45.00		Cum	1	15.00	5.40	5.40	5.40	0.20	16.20		
45.00	60.00		Cum	1	15.00	5.40	5.10	5.25	0.20	15.75		
60.00	75.00		Cum	1	15.00	5.10	5.35	5.23	0.20	15.68		
75.00	90.00		Cum	1	15.00	5.35	5.55	5.45	0.20	16.35		
90.00	105.00		Cum	1	15.00	5.55	6.00	5.78	0.20	17.33		
105.00	120.00		Cum	1	15.00	6.00	6.10	6.05	0.20	18.15		
120.00	134.70		Cum	1	14.70	6.10	6.20	6.15	0.20	18.08		
		10th A Cross										
		(From West to East)										
0.00	2.80		Cum	1	2.80	4.80	4.50	4.65	0.20	2.60		
		2nd Main Road										
		(From West to East)										
0.00	15.00		Cum	1	15.00	8.80	8.70	8.75	0.20	26.25		
15.00	30.00		Cum	1	15.00	8.70	9.13	8.92	0.20	26.75		
30.00	45.00		Cum	1	15.00	9.13	8.50	8.82	0.20	26.45		
45.00	60.00		Cum	1	15.00	8.50	8.40	8.45	0.20	25.35		
60.00	75.00		Cum	1	15.00	8.40	8.55	8.48	0.20	25.43		
75.00	90.00		Cum	1	15.00	8.55	8.10	8.33	0.20	24.98		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
90.00	105.00		Cum	1	15.00	8.10	7.60	7.85	0.20	23.55		
105.00	114.30		Cum	1	9.30	7.60	8.00	7.80	0.20	14.51		
114.30	129.30		Cum	1	15.00	8.00	7.45	7.73	0.20	23.18		
129.30	144.30		Cum	1	15.00	7.45	6.85	7.15	0.20	21.45		
144.30	159.30		Cum	1	15.00	6.85	6.80	6.83	0.20	20.48		
159.30	174.30		Cum	1	15.00	6.80	6.90	6.85	0.20	20.55		
174.30	189.30		Cum	1	15.00	6.90	7.65	7.28	0.20	21.83		
189.30	192.60		Cum	1	3.30	7.65	7.40	7.53	0.20	4.97		
		Cut Portion										
0.00	2.60		Cum	1	2.60	2.10	2.10	2.10	0.20	1.09		
		2nd Main Road To M S Nagar Road										
		(From West to East)										
0.00	15.00		Cum	1	15.00	5.10	4.36	4.73	0.20	14.19		
15.00	30.00		Cum	1	15.00	4.36	4.40	4.38	0.20	13.14		
30.00	33.70		Cum	1	3.70	4.40	4.60	4.50	0.20	3.33		
		(From South to North)										
0.00	15.00		Cum	1	15.00	5.45	5.20	5.33	0.20	15.98		
15.00	30.00		Cum	1	15.00	5.20	5.40	5.30	0.20	15.90		
30.00	45.00		Cum	1	15.00	5.40	5.70	5.55	0.20	16.65		
45.00	60.00		Cum	1	15.00	5.70	5.25	5.48	0.20	16.43		
60.00	75.00		Cum	1	15.00	5.25	5.40	5.33	0.20	15.98		
75.00	90.00		Cum	1	15.00	5.40	5.40	5.40	0.20	16.20		
90.00	105.00		Cum	1	15.00	5.40	5.40	5.40	0.20	16.20		
105.00	120.00		Cum	1	15.00	5.40	5.58	5.49	0.20	16.47		
120.00	135.00		Cum	1	15.00	5.58	5.40	5.49	0.20	16.47		
135.00	150.00		Cum	1	15.00	5.40	5.35	5.38	0.20	16.13		
150.00	165.00		Cum	1	15.00	5.35	5.20	5.28	0.20	15.83		
165.00	180.00		Cum	1	15.00	5.20	5.20	5.20	0.20	15.60		
180.00	195.00		Cum	1	15.00	5.20	5.54	5.37	0.20	16.11		
195.00	197.80		Cum	1	2.80	5.54	6.40	5.97	0.20	3.34		
		(From East to West)										
0.00	15.00		Cum	1	15.00	3.90	3.65	3.78	0.20	11.33		
15.00	30.00		Cum	1	15.00	3.65	3.68	3.67	0.20	11.00		
30.00	45.00		Cum	1	15.00	3.68	3.98	3.83	0.20	11.49		
45.00	49.80		Cum	1	4.80	3.98	4.20	4.09	0.20	3.93		
49.80	51.90		Cum	1	2.10	4.20	7.50	5.85	0.20	2.46		
		3A Cross Road										
		(From East to West)										
0.00	15.00		Cum	1	15.00	3.85	3.63	3.74	0.20	11.22		
15.00	30.00		Cum	1	15.00	3.63	3.63	3.63	0.20	10.89		
30.00	41.40		Cum	1	11.40	3.63	4.32	3.98	0.20	9.06		
41.40	44.50		Cum	1	3.10	4.32	7.35	5.84	0.20	3.62		
		(From North to South)										
0.00	15.00		Cum	1	15.00	4.10	3.60	3.85	0.20	11.55		
15.00	18.60		Cum	1	3.60	3.60	3.65	3.63	0.20	2.61		
		5th Cross Road										
		(From North to South)										
0.00	3.40		Cum	1	3.40	8.20	6.80	7.50	0.20	5.10		
3.40	15.00		Cum	1	11.60	6.80	6.70	6.75	0.20	15.66		
15.00	30.00		Cum	1	15.00	6.70	6.10	6.40	0.20	19.20		
30.00	45.00		Cum	1	15.00	6.10	6.20	6.15	0.20	18.45		
45.00	56.60		Cum	1	11.60	6.20	6.15	6.18	0.20	14.33		
		Hegde Nagara										
		Win Field Garden										
		5th Cross Road (W1941)										
		(From South to North)										
1.50	2.80		Cum	1	1.30	6.10	6.80	6.45	0.20	1.68		
3.20	6.00		Cum	1	2.80	4.60	5.20	4.90	0.20	2.74		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.00	13.10		Cum	1	4.10	4.00	3.80	3.90	0.20	3.20		
4.00	19.60		Cum	1	3.60	3.50	4.40	3.95	0.20	2.84		
16.00	30.00		Cum	1	5.00	2.60	3.20	2.90	0.20	2.90		
25.00	35.00		Cum	1	3.00	3.10	2.00	2.55	0.20	1.53		
32.00	43.00		Cum	1	4.00	4.50	3.00	3.75	0.20	3.00		
39.00	49.00		Cum	1	3.00	2.60	2.90	2.75	0.20	1.65		
46.00	52.50		Cum	1	1.50	1.30	1.80	1.55	0.20	0.47		
51.00	57.20		Cum	1	2.60	2.60	3.50	3.05	0.20	1.59		
54.60	65.00		Cum	1	4.90	4.00	5.10	4.55	0.20	4.46		
60.10	79.30		Cum	1	4.30	2.90	3.50	3.20	0.20	2.75		
75.00	87.00		Cum	1	4.00	1.80	2.30	2.05	0.20	1.64		
83.00	95.00		Cum	1	4.70	3.20	4.00	3.60	0.20	3.38		
90.30	105.80		Cum	1	2.80	2.30	3.50	2.90	0.20	1.62		
103.00	113.00		Cum	1	3.60	4.80	5.20	5.00	0.20	3.60		
109.40	125.10		Cum	1	4.80	2.60	3.60	3.10	0.20	2.98		
120.30	143.60		Cum	1	5.60	1.20	2.00	1.60	0.20	1.79		
138.00	155.70		Cum	1	3.70	2.40	2.60	2.50	0.20	1.85		
152.00	161.00		Cum	1	1.00	1.90	2.40	2.15	0.20	0.43		
160.00	175.60		Cum	1	5.60	2.00	2.80	2.40	0.20	2.69		
170.00	182.00		Cum	1	2.00	5.30	6.10	5.70	0.20	2.28		
180.00	187.20		Cum	1	1.20	5.40	4.60	5.00	0.20	1.20		
		6th Cross Road (W1935)										
		(From South to North)										
0.00	2.00		Cum	1	2.00	7.50	5.90	6.70	0.20	2.68		
2.00	15.00		Cum	1	13.00	5.90	5.95	5.93	0.20	15.41		
15.00	30.00		Cum	1	15.00	5.95	6.00	5.98	0.20	17.93		
30.00	45.00		Cum	1	15.00	6.00	5.50	5.75	0.20	17.25		
45.00	60.00		Cum	1	15.00	5.50	5.35	5.43	0.20	16.28		
60.00	75.00		Cum	1	15.00	5.35	5.55	5.45	0.20	16.35		
75.00	90.00		Cum	1	15.00	5.55	5.55	5.55	0.20	16.65		
90.00	105.00		Cum	1	15.00	5.55	5.60	5.58	0.20	16.73		
105.00	120.00		Cum	1	15.00	5.60	5.60	5.60	0.20	16.80		
120.00	135.00		Cum	1	15.00	5.60	5.75	5.68	0.20	17.03		
135.00	150.00		Cum	1	15.00	5.75	4.85	5.30	0.20	15.90		
150.00	165.00		Cum	1	15.00	4.85	4.80	4.83	0.20	14.48		
165.00	180.00		Cum	1	15.00	4.80	6.10	5.45	0.20	16.35		
180.00	181.50		Cum	1	1.50	6.10	5.40	5.75	0.20	1.73		
		9th Cross Road										
		(From South to North)										
2.80	6.30		Cum	1	3.50	2.40	3.10	2.75	0.20	1.93		
8.00	10.00		Cum	1	2.00	3.00	2.80	2.90	0.20	1.16		
13.00	16.30		Cum	1	3.30	1.75	2.40	2.08	0.20	1.37		
20.50	27.00		Cum	1	6.50	3.10	3.50	3.30	0.20	4.29		
28.00	32.00		Cum	1	4.00	3.30	4.00	3.65	0.20	2.92		
37.30	40.20		Cum	1	2.90	4.10	3.00	3.55	0.20	2.06		
41.00	42.00		Cum	1	1.00	1.65	2.40	2.03	0.20	0.41		
45.00	49.70		Cum	1	4.70	2.10	2.10	2.10	0.20	1.97		
52.90	59.30		Cum	1	6.40	3.00	3.40	3.20	0.20	4.10		
66.00	69.20		Cum	1	3.20	3.65	3.90	3.78	0.20	2.42		
74.00	78.00		Cum	1	4.00	3.70	3.90	3.80	0.20	3.04		
80.80	84.50		Cum	1	3.70	2.90	3.80	3.35	0.20	2.48		
91.60	99.10		Cum	1	7.50	4.20	3.00	3.60	0.20	5.40		
101.00	104.80		Cum	1	3.80	2.80	2.40	2.60	0.20	1.98		
108.00	117.80		Cum	1	9.80	3.50	3.80	3.65	0.20	7.15		
119.40	124.10		Cum	1	4.70	4.00	3.20	3.60	0.20	3.38		
126.50	130.40		Cum	1	3.90	2.90	3.40	3.15	0.20	2.46		
132.00	136.20		Cum	1	4.20	4.10	3.70	3.90	0.20	3.28		
		MSR Mansion Road										
		(North to South)										
0.00	5.80		Cum	1	5.80	5.75	7.15	6.45	0.20	7.48		
5.80	9.70		Cum	1	3.90	10.70	8.40	9.55	0.20	7.45		
9.70	15.00		Cum	1	5.30	8.40	8.25	8.33	0.20	8.82		
15.00	30.00		Cum	1	15.00	8.25	7.40	7.83	0.20	23.48		
30.00	45.00		Cum	1	15.00	7.40	6.85	7.13	0.20	21.38		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
45.00	50.00		Cum	1	5.00	6.85	7.10	6.98	0.20	6.98		
		Nisarga Layout										
		7th Cross, Zayan Travels Car Service Centre Road, North To South										
0.00	15.00		Cum	1	15.00	5.00	4.85	4.93	0.23	16.99		
15.00	30.00		Cum	1	15.00	4.85	4.60	4.73	0.23	16.30		
30.00	45.00		Cum	1	15.00	4.60	5.15	4.88	0.23	16.82		
45.00	60.00		Cum	1	15.00	5.15	5.00	5.08	0.23	17.51		
60.00	75.00		Cum	1	15.00	5.00	5.10	5.05	0.23	17.42		
75.00	90.00		Cum	1	15.00	5.10	5.00	5.05	0.23	17.42		
90.00	101.50		Cum	1	11.50	5.00	4.70	4.85	0.23	12.83		
		West To East										
0.00	15.00		Cum	1	15.00	4.90	4.80	4.85	0.23	16.73		
15.00	15.70		Cum	1	0.70	4.80	4.80	4.80	0.23	0.77		
15.70	30.00		Cum	1	14.30	5.30	5.60	5.45	0.23	17.93		
30.00	45.00		Cum	1	15.00	5.60	5.15	5.38	0.23	18.54		
45.00	46.70		Cum	1	1.70	5.15	5.15	5.15	0.23	2.01		
46.70	51.60		Cum	1	4.90	4.15	3.95	4.05	0.23	4.56		
51.60	56.20		Cum	1	4.60	5.30	5.25	5.28	0.23	5.58		
56.20	64.60		Cum	1	8.40	4.20	4.30	4.25	0.23	8.21		
64.60	75.00		Cum	1	10.40	5.30	5.35	5.33	0.23	12.74		
75.00	76.60		Cum	1	1.60	5.35	5.36	5.36	0.23	1.97		
		5th Cross Road, North To South										
0.00	11.10		Cum	1	11.10	5.70	5.90	5.80	0.23	14.81		
11.10	20.00		Cum	1	8.90	5.10	5.35	5.23	0.23	10.70		
20.00	23.80		Cum	1	3.80	7.00	6.95	6.98	0.23	6.10		
23.80	30.00		Cum	1	6.20	6.05	5.95	6.00	0.23	8.56		
30.00	45.00		Cum	1	15.00	5.95	5.50	5.73	0.23	19.75		
45.00	60.00		Cum	1	15.00	5.50	6.00	5.75	0.23	19.84		
60.00	66.90		Cum	1	6.90	6.00	6.30	6.15	0.23	9.76		
66.90	75.00		Cum	1	8.10	4.90	5.70	5.30	0.23	9.87		
75.00	75.60		Cum	1	0.60	5.70	5.65	5.68	0.23	0.78		
75.60	76.80		Cum	1	1.20	2.95	3.00	2.98	0.23	0.82		
		Mithun White Pearl Apartment Road (East To West)										
0.00	15.00		Cum	1	15.00	6.60	6.75	6.68	0.23	23.03		
15.00	30.00		Cum	1	15.00	6.75	6.50	6.63	0.23	22.86		
30.00	45.00		Cum	1	15.00	6.50	6.45	6.48	0.23	22.34		
45.00	60.00		Cum	1	15.00	6.45	6.45	6.45	0.23	22.25		
60.00	75.00		Cum	1	15.00	6.45	6.25	6.35	0.23	21.91		
75.00	90.00		Cum	1	15.00	6.25	6.20	6.23	0.23	21.48		
90.00	96.40		Cum	1	6.40	6.20	5.85	6.03	0.23	8.87		
		Venkateshwara Layout 3rd Cross Road South to North										
0.00	15.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
15.00	30.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
30.00	45.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
45.00	60.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
60.00	75.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
75.00	90.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
90.00	105.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
105.00	120.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
120.00	135.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
135.00	150.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
150.00	165.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
165.00	180.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
180.00	195.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.00	210.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
210.00	220.00		Cum	1	10.00	1.20	1.20	1.20	0.23	2.76		
		4th Cross Road										
		North to South										
0.00	15.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
15.00	30.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
30.00	45.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
45.00	60.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
60.00	75.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
75.00	90.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
90.00	105.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
105.00	120.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
120.00	135.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
135.00	150.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
150.00	165.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
165.00	180.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
180.00	195.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
195.00	210.00		Cum	1	15.00	1.20	1.20	1.20	0.23	4.14		
210.00	220.00		Cum	1	10.00	1.20	1.20	1.20	0.23	2.76		
		5th Cross Road										
		North to South										
0.00	15.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
15.00	30.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
30.00	45.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
45.00	60.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
60.00	75.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
75.00	90.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
90.00	105.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
105.00	120.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
120.00	135.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
135.00	150.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
150.00	165.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
165.00	180.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
180.00	195.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
195.00	210.00		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
210.00	220.00		Cum	1	10.00	1.20	1.20	1.20	0.20	2.40		
		Chembar	Cum	-1	0.64				0.20	-0.13		
								Area of				
			Cum	-4	0.70	1.00	1.00	1.00	0.23	-0.64		
			Cum	-3	0.90	0.80	0.80	0.80	0.23	-0.50		
		Katgenahalli										
		Muneshwara Provision Store										
		Beside Road										
		Kalidas Layout										
		3rd Main Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	6.70	6.65	6.68	0.20	20.03		
15.00	30.00		Cum	1	15.00	6.65	6.65	6.65	0.20	19.95		
30.00	45.00		Cum	1	15.00	6.65	6.00	6.33	0.20	18.98		
45.00	60.00		Cum	1	15.00	6.00	5.80	5.90	0.20	17.70		
60.00	66.40		Cum	1	6.40	5.80	5.60	5.70	0.20	7.30		
66.40	75.00		Cum	1	8.60	5.60	5.60	5.60	0.20	9.63		
75.00	90.00		Cum	1	15.00	5.60	5.50	5.55	0.20	16.65		
90.00	105.00		Cum	1	15.00	5.50	5.80	5.65	0.20	16.95		
105.00	113.00		Cum	1	8.00	5.80	4.30	5.05	0.20	8.08		
		Mk Provision Store Road										
		(From East to West)										
4.00	8.00		Cum	1	4.00	1.20	1.20	1.20	0.20	0.96		
14.00	16.00		Cum	1	2.00	0.90	0.90	0.90	0.20	0.36		
22.00	28.00		Cum	1	6.00	1.30	1.30	1.30	0.20	1.56		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
33.00	39.00		Cum	1	6.00	1.10	1.10	1.10	0.20	1.32		
42.00	44.00		Cum	1	2.00	0.60	0.60	0.60	0.20	0.24		
50.00	57.00		Cum	1	7.00	0.90	0.90	0.90	0.20	1.26		
62.60	67.20		Cum	1	4.60	1.10	1.10	1.10	0.20	1.01		
78.30	88.00		Cum	1	9.70	1.30	1.30	1.30	0.20	2.52		
93.00	101.00		Cum	1	8.00	1.10	1.10	1.10	0.20	1.76		
108.00	117.00		Cum	1	9.00	1.20	1.20	1.20	0.20	2.16		
124.60	133.00		Cum	1	8.40	1.40	1.40	1.40	0.20	2.35		
137.90	148.00		Cum	1	10.10	1.20	1.20	1.20	0.20	2.42		
			Cum	1	Triangular Portion 9.5*8.2*12.55=977.65			977.65	0.20	195.53		
			Cum	1	Triangular Portion 10.5*3.3*11=381.15			381.15	0.20	76.23		
		Deduction										
0.00	1.40		Cum	-1	1.40	1.00	1.00	1.00	0.20	-0.28		
		Deduction										
0.00	1.40		Cum	-1	1.40	1.00	1.00	1.00	0.20	-0.28		
		Cross Road - 2										
		(From North to South)										
0.00	4.30		Cum	1	4.30	5.10	5.00	5.05	0.20	4.34		
4.30	15.00		Cum	1	10.70	5.00	5.10	5.05	0.20	10.81		
15.00	20.60		Cum	1	5.60	5.10	5.30	5.20	0.20	5.82		
20.60	30.00		Cum	1	9.40	6.65	6.20	6.43	0.20	12.08		
30.00	40.60		Cum	1	10.60	6.20	6.60	6.40	0.20	13.57		
40.60	45.00		Cum	1	4.40	6.60	5.90	6.25	0.20	5.50		
45.00	60.00		Cum	1	15.00	5.90	5.95	5.93	0.20	17.78		
60.00	75.00		Cum	1	15.00	5.95	5.85	5.90	0.20	17.70		
75.00	90.00		Cum	1	15.00	5.85	6.38	6.12	0.20	18.35		
90.00	105.00		Cum	1	15.00	6.38	5.50	5.94	0.20	17.82		
105.00	120.00		Cum	1	15.00	5.50	5.69	5.60	0.20	16.79		
120.00	123.00		Cum	1	3.00	5.69	5.00	5.35	0.20	3.21		
		Cross Road - 1										
		(From South to North)										
0.00	15.00		Cum	1	15.00	4.75	4.55	4.65	0.20	13.95		
15.00	30.00		Cum	1	15.00	4.55	5.10	4.83	0.20	14.48		
30.00	45.00		Cum	1	15.00	5.10	4.80	4.95	0.20	14.85		
45.00	60.00		Cum	1	15.00	4.80	4.55	4.68	0.20	14.03		
60.00	75.00		Cum	1	15.00	4.55	5.00	4.78	0.20	14.33		
75.00	88.60		Cum	1	13.60	5.00	4.50	4.75	0.20	12.92		
		Kattigenahalli										
		Durgamba Layout										
		Amulya Family Restaurant Road (N-S)										
0.00	15.00		Cum	1	15.00	6.90	6.40	6.65	0.20	19.95		
15.00	30.00		Cum	1	15.00	6.40	6.05	6.23	0.20	18.68		
30.00	45.00		Cum	1	15.00	5.60	5.30	5.45	0.20	16.35		
45.00	60.00		Cum	1	15.00	5.30	4.95	5.13	0.20	15.38		
60.00	75.00		Cum	1	15.00	4.95	5.05	5.00	0.20	15.00		
75.00	81.00		Cum	1	6.00	5.05	5.05	5.05	0.20	6.06		
81.00	90.00		Cum	1	9.00	5.70	5.90	5.80	0.20	10.44		
90.00	105.00		Cum	1	15.00	5.90	5.30	5.60	0.20	16.80		
105.00	118.80		Cum	1	13.80	5.30	4.60	4.95	0.20	13.66		
118.80	127.90		Cum	1	9.10	5.80	5.85	5.83	0.20	10.60		
127.90	135.00		Cum	1	7.10	4.95	4.85	4.90	0.20	6.96		
135.00	137.10		Cum	1	2.10	4.85	5.05	4.95	0.20	2.08		
137.10	150.00		Cum	1	12.90	4.35	4.95	4.65	0.20	12.00		
150.00	165.00		Cum	1	15.00	4.95	4.60	4.78	0.20	14.33		
165.00	180.00		Cum	1	15.00	4.60	5.25	4.93	0.20	14.78		
180.00	182.50		Cum	1	2.50	5.25	5.15	5.20	0.20	2.60		
182.50	195.00		Cum	1	12.50	5.85	6.60	6.23	0.20	15.56		
195.00	210.00		Cum	1	15.00	6.60	6.15	6.38	0.20	19.13		
210.00	218.00		Cum	1	8.00	6.15	6.00	6.08	0.20	9.72		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Kaustaba House Road #33 (W-E)										
0.00	6.30		Cum	1	6.30	7.45	7.55	7.50	0.20	9.45		
6.30	15.00		Cum	1	8.70	6.80	6.48	6.64	0.20	11.55		
15.00	30.00		Cum	1	15.00	6.48	6.00	6.24	0.20	18.72		
30.00	45.00		Cum	1	15.00	6.00	5.70	5.85	0.20	17.55		
45.00	57.90		Cum	1	12.90	5.70	6.05	5.88	0.20	15.16		
57.90	60.00		Cum	1	2.10	6.95	7.70	7.33	0.20	3.08		
60.00	63.60		Cum	1	3.60	7.70	7.65	7.68	0.20	5.53		
		Sukruthi House Road #26 (S-N)										
0.00	8.30		Cum	1	8.30	5.60	5.90	5.75	0.23	10.98		
8.30	15.00		Cum	1	6.70	5.35	4.90	5.13	0.23	7.90		
15.00	30.00		Cum	1	15.00	4.90	5.80	5.35	0.23	18.46		
30.00	45.00		Cum	1	15.00	5.80	5.35	5.58	0.23	19.23		
45.00	60.00		Cum	1	15.00	5.35	5.30	5.33	0.23	18.37		
60.00	60.50		Cum	1	0.50	5.30	5.30	5.30	0.23	0.61		
60.50	75.00		Cum	1	14.50	5.85	6.20	6.03	0.23	20.09		
75.00	90.00		Cum	1	15.00	6.20	5.40	5.80	0.23	20.01		
90.00	98.70		Cum	1	8.70	5.40	5.20	5.30	0.23	10.61		
98.70	105.00		Cum	1	6.30	4.40	4.95	4.68	0.23	6.77		
105.00	108.20		Cum	1	3.20	4.95	4.95	4.95	0.23	3.64		
108.20	112.20		Cum	1	4.00	5.50	5.20	5.35	0.23	4.92		
112.20	120.00		Cum	1	7.80	4.40	4.60	4.50	0.23	8.07		
120.00	125.80		Cum	1	5.80	4.60	4.50	4.55	0.23	6.07		
125.80	135.70		Cum	1	9.90	4.00	4.45	4.23	0.23	9.62		
135.70	143.90		Cum	1	8.20	5.60	5.95	5.78	0.23	10.89		
143.90	150.00		Cum	1	6.10	6.65	5.75	6.20	0.23	8.70		
150.00	164.30		Cum	1	14.30	5.75	5.85	5.80	0.23	19.08		
		SP Singh House Road (E-W)										
0.00	15.00		Cum	1	15.00	6.35	5.65	6.00	0.23	20.70		
15.00	19.10		Cum	1	4.10	5.65	6.00	5.83	0.23	5.49		
19.10	30.00		Cum	1	10.90	5.20	5.65	5.43	0.23	13.60		
30.00	34.20		Cum	1	4.20	5.65	6.10	5.88	0.23	5.68		
		Form mrd Main To Muneshwara provsion										
0.00	1.70		Cum	1	1.70	5.05	5.05	5.05	0.20	1.72		
1.70	15.00		Cum	1	13.30	7.30	7.40	7.35	0.20	19.55		
15.00	30.00		Cum	1	15.00	7.40	7.10	7.25	0.20	21.75		
30.00	45.00		Cum	1	15.00	7.10	6.75	6.93	0.20	20.78		
45.00	60.00		Cum	1	15.00	6.75	7.55	7.15	0.20	21.45		
60.00	75.00		Cum	1	15.00	7.55	6.45	7.00	0.20	21.00		
75.00	77.80		Cum	1	2.80	6.45	5.70	6.08	0.20	3.40		
77.80	90.00		Cum	1	12.20	6.80	7.15	6.98	0.20	17.02		
90.00	95.90		Cum	1	5.90	7.15	6.95	7.05	0.20	8.32		
95.90	105.00		Cum	1	9.10	6.25	6.30	6.28	0.20	11.42		
105.00	117.90		Cum	1	12.90	6.30	5.90	6.10	0.20	15.74		
117.90	120.00		Cum	1	2.10	6.75	6.80	6.78	0.20	2.85		
120.00	124.80		Cum	1	4.80	6.80	5.80	6.30	0.20	6.05		
		Deduction										
		Chamber	Cum	-1	0.70	1.00	1.00	1.00	0.20	-0.14		
		Manhole	Cum	-1	0.64				0.20	-0.13		
								Area of Circle =				
		Manhole	Cum	-1	1.13				0.20	-0.23		
								Area of Circle =				
		Cross Road 3 Near Pyramid apartment (North to South)										
0.00	2.90		Cum	1	2.90	6.40	6.35	6.38	0.23	4.25		
2.90	15.00		Cum	1	12.10	6.35	5.75	6.05	0.23	16.84		
15.00	30.00		Cum	1	15.00	5.75	5.70	5.73	0.23	19.75		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Cum	1	14.00	5.70	5.10	5.40	0.23	17.39		
30.00	44.00											
		For Road Cut portion										
		Green Garden Main Road										
		(West to East)										
			Cum	1	2.00	1.60	1.60	1.60	0.23	0.74		
2.00	4.00		Cum	1	4.00	1.20	1.20	1.20	0.23	1.10		
7.00	11.00		Cum	1	2.00	1.30	1.30	1.30	0.23	0.60		
13.00	15.00		Cum	1	5.00	1.10	1.10	1.10	0.23	1.27		
17.00	22.00		Cum	1	4.00	2.00	2.00	2.00	0.23	1.84		
25.00	29.00		Cum	1	12.70	1.60	1.60	1.60	0.23	4.67		
30.00	42.70		Cum	1	2.30	2.10	2.10	2.10	0.23	1.11		
42.70	45.00		Cum	1	8.70	1.10	1.10	1.10	0.23	2.20		
45.00	53.70		Cum	1	6.30	1.60	1.60	1.60	0.23	2.32		
53.70	60.00		Cum	1	4.00	1.60	1.60	1.60	0.23	1.47		
62.00	66.00		Cum	1	2.00	1.80	1.80	1.80	0.23	0.83		
68.00	70.00		Cum	1	3.00	1.40	1.40	1.40	0.23	0.97		
72.00	75.00		Cum	1	11.00	1.20	1.20	1.20	0.23	3.04		
77.00	88.00		Cum	1	9.20	1.00	1.00	1.00	0.23	2.12		
93.80	103.00		Cum	1	10.00	1.70	1.70	1.70	0.23	3.91		
107.00	117.00		Cum	1	6.90	1.30	1.30	1.30	0.23	2.06		
120.00	126.90		Cum	1	2.00	1.40	1.40	1.40	0.23	0.64		
128.00	130.00		Cum	1	8.00	1.60	1.60	1.60	0.23	2.94		
132.00	140.00		Cum	1	4.00	2.10	2.10	2.10	0.23	1.93		
148.00	152.00		Cum	1	5.70	1.60	1.60	1.60	0.23	2.10		
154.30	160.00		Cum	1	6.00	1.30	1.30	1.30	0.23	1.79		
163.00	169.00											
		Cross Road-4										
		(South to North)										
0.00	1.60		Cum	1	1.60	1.30	1.30	1.30	0.23	0.48		
4.00	12.00		Cum	1	8.00	2.00	2.00	2.00	0.23	3.68		
15.00	21.00		Cum	1	6.00	1.60	1.60	1.60	0.23	2.21		
23.50	30.00		Cum	1	6.50	2.60	2.60	2.60	0.23	3.89		
30.00	33.70		Cum	1	3.70	3.00	3.00	3.00	0.23	2.55		
		Sri Ganga House Road										
		East to West										
3.80	13.20		Cum	1	9.40	1.00	1.00	1.00	0.23	2.16		
13.20	15.00		Cum	1	1.80	3.00	3.00	3.00	0.23	1.24		
17.00	26.00		Cum	1	9.00	2.40	2.40	2.40	0.23	4.97		
27.40	30.00		Cum	1	2.60	1.60	1.60	1.60	0.23	0.96		
33.00	41.00		Cum	1	8.00	1.90	1.90	1.90	0.23	3.50		
47.00	57.60		Cum	1	10.60	3.00	3.00	3.00	0.23	7.31		
62.00	66.00		Cum	1	4.00	1.70	1.70	1.70	0.23	1.56		
		Cross Road-3										
		(North to South)										
0.00	1.70		Cum	1	1.70	3.00	3.00	3.00	0.23	1.17		
3.30	10.00		Cum	1	6.70	1.30	1.30	1.30	0.23	2.00		
12.00	14.00		Cum	1	2.00	0.90	0.90	0.90	0.23	0.41		
17.00	21.00		Cum	1	4.00	1.70	1.70	1.70	0.23	1.56		
24.00	29.00		Cum	1	5.00	2.20	2.20	2.20	0.23	2.53		
33.00	38.00		Cum	1	5.00	1.70	1.70	1.70	0.23	1.96		
40.00	44.00		Cum	1	4.00	1.10	1.10	1.10	0.23	1.01		
45.00	46.10		Cum	1	1.10	1.70	1.70	1.70	0.23	0.43		
46.10	48.90		Cum	1	2.80	2.00	2.00	2.00	0.23	1.29		
		Cross Road 2										
		(South to North)										
3.00	9.00		Cum	1	6.00	1.90	1.90	1.90	0.23	2.62		
12.00	15.00		Cum	1	3.00	2.20	2.20	2.20	0.23	1.52		
18.00	21.10		Cum	1	3.10	3.10	3.10	3.10	0.23	2.21		
23.00	30.00		Cum	1	7.00	1.75	1.75	1.75	0.23	2.82		
33.00	45.00		Cum	1	12.00	2.00	2.00	2.00	0.23	5.52		
48.00	51.00		Cum	1	3.00	1.00	1.00	1.00	0.23	0.69		
53.00	58.00		Cum	1	5.00	1.85	1.85	1.85	0.23	2.13		
68.20	72.00		Cum	1	7.80	1.50	1.50	1.50	0.23	2.69		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
	87.00		Cum	1	9.00	2.10	2.10	2.10	0.23	4.35		
78.00	98.00		Cum	1	5.40	1.70	1.70	1.70	0.23	2.11		
92.60												
		Cross Road 1										
		(North to South)										
			Cum	1	7.60	1.20	1.20	1.20	0.23	2.10		
4.60	12.20		Cum	1	9.40	1.80	1.80	1.80	0.23	3.89		
17.60	27.00		Cum	1	8.00	2.30	2.30	2.30	0.23	4.23		
33.00	41.00		Cum	1	11.00	2.70	2.70	2.70	0.23	6.83		
47.00	58.00		Cum	1	8.20	1.60	1.60	1.60	0.23	3.02		
62.80	71.00		Cum	1	9.00	1.50	1.50	1.50	0.23	3.11		
79.00	88.00		Cum	1	4.00	1.70	1.70	1.70	0.23	1.56		
94.00	98.00											
		Pyramid apartment main road										
		(East to West)										
			Cum	1	1.10	8.16	8.15	8.16	0.23	2.06		
0.00	1.10		Cum	1	1.30	8.15	6.80	7.48	0.23	2.24		
1.10	2.40		Cum	1	2.30	6.80	6.60	6.70	0.23	3.54		
2.40	4.70		Cum	1	7.70	7.65	7.85	7.75	0.23	13.73		
4.70	12.40		Cum	1	2.60	7.85	7.70	7.78	0.23	4.65		
12.40	15.00		Cum	1	15.00	7.70	8.35	8.03	0.23	27.69		
15.00	30.00		Cum	1	2.00	8.35	8.35	8.35	0.23	3.84		
30.00	32.00		Cum	1	13.00	8.35	8.50	8.43	0.23	25.19		
32.00	45.00		Cum	1	15.00	8.50	8.65	8.58	0.23	29.58		
45.00	60.00		Cum	1	15.00	8.65	8.70	8.68	0.23	29.93		
60.00	75.00		Cum	1	6.10	8.70	8.75	8.73	0.23	12.24		
75.00	81.10		Cum	1	8.90	8.75	8.20	8.48	0.23	17.35		
81.10	90.00		Cum	1	15.00	8.20	8.45	8.33	0.23	28.72		
90.00	105.00		Cum	1	15.00	8.45	8.38	8.42	0.23	29.03		
105.00	120.00		Cum	1	8.00	8.38	8.40	8.39	0.23	15.44		
120.00	128.00											
		Cross Road 2 Near Pyramid apartment										
		(North to South)										
5.60	11.00		Cum	1	5.40	1.40	1.40	1.40	0.23	1.74		
17.00	27.00		Cum	1	10.00	1.80	1.80	1.80	0.23	4.14		
30.00	32.80		Cum	1	2.80	1.70	1.70	1.70	0.23	1.09		
32.80	42.30		Cum	1	9.50	2.00	2.00	2.00	0.23	4.37		
42.30	45.10		Cum	1	2.80	1.30	1.30	1.30	0.23	0.84		
45.10	48.30		Cum	1	3.20	1.00	1.00	1.00	0.23	0.74		
		Cross Road 1 Near Pyramid apartment										
		(North to South)										
4.50	13.00		Cum	1	8.50	1.70	1.70	1.70	0.23	3.32		
16.00	27.00		Cum	1	11.00	1.40	1.40	1.40	0.23	3.54		
34.00	41.00		Cum	1	7.00	1.70	1.70	1.70	0.23	2.74		
48.00	51.70		Cum	1	3.70	1.25	1.25	1.25	0.23	1.06		
53.00	58.70		Cum	1	5.70	2.10	2.10	2.10	0.23	2.75		
63.00	71.00		Cum	1	8.00	1.70	1.70	1.70	0.23	3.13		
79.00	86.00		Cum	1	7.00	1.40	1.40	1.40	0.23	2.25		
93.00	102.00		Cum	1	9.00	2.00	2.00	2.00	0.23	4.14		
106.40	117.00		Cum	1	10.60	1.80	1.80	1.80	0.23	4.39		
122.00	125.00		Cum	1	3.00	1.20	1.20	1.20	0.23	0.83		
		Car 24 Beside Road From Agrahara Main Road to Lake										
		East to West										
0.00	15.00		Cum	1	15.00	4.80	4.60	4.70	0.25	17.63		
15.00	27.00		Cum	1	12.00	4.60	4.65	4.63	0.25	13.88		
27.00	30.00		Cum	1	3.00	5.40	5.70	5.55	0.25	4.16		
30.00	45.00		Cum	1	15.00	5.70	5.70	5.70	0.25	21.38		
45.00	60.00		Cum	1	15.00	5.70	6.30	6.00	0.25	22.50		
60.00	75.00		Cum	1	15.00	6.30	6.30	6.30	0.25	23.63		
75.00	90.00		Cum	1	15.00	6.30	6.50	6.40	0.25	24.00		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0m	105.00		Cum	1	15.00	6.50	6.65	6.58	0.25	24.66		
90.00	120.00		Cum	1	15.00	6.65	6.40	6.53	0.25	24.47		
105.00	135.00		Cum	1	15.00	6.40	6.20	6.30	0.25	23.63		
120.00	150.00		Cum	1	15.00	6.20	6.10	6.15	0.25	23.06		
135.00	165.00		Cum	1	15.00	6.10	6.30	6.20	0.25	23.25		
150.00	180.00		Cum	1	15.00	6.30	6.10	6.20	0.25	23.25		
165.00	195.00		Cum	1	15.00	6.10	6.25	6.18	0.25	23.16		
180.00	210.00		Cum	1	15.00	6.25	6.50	6.38	0.25	23.91		
195.00	225.00		Cum	1	15.00	6.50	6.40	6.45	0.25	24.19		
210.00	240.00		Cum	1	15.00	6.40	6.50	6.45	0.25	24.19		
225.00	255.00		Cum	1	15.00	6.50	6.65	6.58	0.25	24.66		
240.00	270.00		Cum	1	15.00	6.65	6.70	6.68	0.25	25.03		
255.00	285.00		Cum	1	15.00	6.70	6.45	6.58	0.25	24.66		
270.00	300.00		Cum	1	15.00	6.45	6.20	6.33	0.25	23.72		
285.00	315.00		Cum	1	15.00	6.20	6.10	6.15	0.25	23.06		
300.00	330.00		Cum	1	15.00	6.10	6.10	6.10	0.25	22.88		
315.00	345.00		Cum	1	15.00	6.10	6.00	6.05	0.25	22.69		
330.00	360.00		Cum	1	15.00	6.00	6.60	6.30	0.25	23.63		
345.00	375.00		Cum	1	15.00	6.60	6.00	6.30	0.25	23.63		
360.00	390.00		Cum	1	15.00	6.00	6.10	6.05	0.25	22.69		
375.00	405.00		Cum	1	15.00	6.10	6.30	6.20	0.25	23.25		
390.00	410.00		Cum	1	5.00	6.30	6.40	6.35	0.25	7.94		
405.00	419.00		Cum	1	9.00	4.70	4.50	4.60	0.25	10.35		
410.00	420.00		Cum	1	1.00	6.30	6.30	6.30	0.25	1.58		
419.00	435.00		Cum	1	15.00	6.30	6.30	6.30	0.25	23.63		
420.00	450.00		Cum	1	15.00	6.30	6.80	6.55	0.25	24.56		
435.00	465.00		Cum	1	15.00	6.80	7.10	6.95	0.25	26.06		
450.00	480.00		Cum	1	15.00	7.10	5.80	6.45	0.25	24.19		
465.00	495.00		Cum	1	15.00	5.80	5.20	5.50	0.25	20.63		
480.00	510.00		Cum	1	15.00	5.20	3.95	4.58	0.25	17.16		
495.00	512.00		Cum	1	2.00	3.95	3.80	3.88	0.25	1.94		
510.00	525.00		Cum	1	13.00	4.70	5.45	5.08	0.25	16.49		
512.00	540.00		Cum	1	15.00	5.45	6.10	5.78	0.25	21.66		
525.00	546.00		Cum	1	6.00	6.10	5.50	5.80	0.25	8.70		
		Cross Road-1										
		South to North										
0.00	6.00		Cum	1	6.00	12.00	5.90	8.95	0.25	13.43		
6.00	12.00		Cum	1	6.00	5.90	5.00	5.45	0.25	8.18		
12.00	15.00		Cum	1	3.00	6.00	6.00	6.00	0.25	4.50		
15.00	19.00		Cum	1	4.00	6.00	5.70	5.85	0.25	5.85		
		Cross Road-2										
		South to north										
0.00	15.00		Cum	1	15.00	6.50	6.00	6.25	0.25	23.44		
15.00	30.00		Cum	1	15.00	6.00	6.00	6.00	0.25	22.50		
30.00	45.00		Cum	1	15.00	6.00	6.00	6.00	0.25	22.50		
45.00	60.00		Cum	1	15.00	6.00	6.30	6.15	0.25	23.06		
60.00	67.70		Cum	1	7.70	6.30	6.60	6.45	0.25	12.42		
67.70	69.70		Cum	1	2.00	6.60	7.30	6.95	0.25	3.48		
		MCECHS layout										
		22nd Cross Road										
		North to South										
0.00	15.00		Cum	1	15.00	0.75	0.75	0.75	0.20	2.25		
15.00	30.00		Cum	1	15.00	0.75	0.75	0.75	0.20	2.25		
30.00	45.00		Cum	1	15.00	0.75	0.75	0.75	0.20	2.25		
45.00	60.00		Cum	1	15.00	0.75	0.75	0.75	0.20	2.25		
60.00	75.00		Cum	1	15.00	0.75	0.75	0.75	0.20	2.25		
75.00	90.00		Cum	1	15.00	0.75	0.75	0.75	0.20	2.25		
90.00	105.00		Cum	1	15.00	0.75	0.75	0.75	0.20	2.25		
105.00	120.00		Cum	1	15.00	0.75	0.75	0.75	0.20	2.25		
120.00	135.00		Cum	1	15.00	0.75	0.75	0.75	0.20	2.25		
135.00	141.10		Cum	1	6.10	0.75	0.75	0.75	0.20	0.91		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Vidhana Soudha Layout										
		(From North to South)										
			Cum	1	15.00	6.10	5.45	5.78	0.20	17.33		
0.00	15.00		Cum	1	14.30	5.45	8.30	6.88	0.20	19.66		
15.00	29.30											
		(From East to West)										
			Cum	1	15.00	9.40	8.90	9.15	0.20	27.45		
0.00	15.00		Cum	1	15.00	8.90	8.60	8.75	0.20	26.25		
15.00	30.00		Cum	1	15.00	8.60	8.90	8.75	0.20	26.25		
30.00	45.00		Cum	1	15.00	8.90	8.20	8.55	0.20	25.65		
45.00	60.00		Cum	1	15.00	8.20	8.25	8.23	0.20	24.68		
60.00	75.00		Cum	1	15.00	8.25	8.50	8.38	0.20	25.13		
75.00	90.00		Cum	1	15.00	8.50	8.30	8.40	0.20	25.20		
90.00	105.00		Cum	1	12.80	8.30	8.25	8.28	0.20	21.18		
105.00	117.80		Cum	1	7.30	11.35	11.25	11.30	0.20	16.50		
117.80	125.10		Cum	1	9.90	8.20	8.05	8.13	0.20	16.09		
125.10	135.00		Cum	1	15.00	8.05	8.05	8.05	0.20	24.15		
135.00	150.00		Cum	1	0.90	10.95	10.95	10.95	0.20	1.97		
150.00	150.90		Cum	1	14.10	8.30	8.35	8.33	0.20	23.48		
150.90	165.00		Cum	1	15.00	8.35	8.42	8.39	0.20	25.16		
165.00	180.00		Cum	1	4.90	8.42	8.55	8.49	0.20	8.32		
180.00	184.90		Cum	1	8.60	11.20	11.30	11.25	0.20	19.35		
184.90	193.50		Cum	1	1.50	8.30	8.30	8.30	0.20	2.49		
193.50	195.00		Cum	1	15.00	8.30	8.15	8.23	0.20	24.68		
195.00	210.00		Cum	1	15.00	8.15	8.30	8.23	0.20	24.68		
210.00	225.00		Cum	1	15.00	8.30	9.00	8.65	0.20	25.95		
225.00	240.00		Cum	1	15.00	9.00	8.85	8.93	0.20	26.78		
240.00	255.00		Cum	1	3.00	8.85	8.25	8.55	0.20	5.13		
255.00	258.00		Cum	1	7.10	9.70	9.80	9.75	0.20	13.85		
258.00	265.10		Cum	1	4.90	8.40	8.35	8.38	0.20	8.21		
265.10	270.00		Cum	1	15.00	8.35	8.25	8.30	0.20	24.90		
270.00	285.00		Cum	1	6.00	8.25	8.20	8.23	0.20	9.87		
285.00	291.00		Cum	1	8.80	9.55	9.40	9.48	0.20	16.68		
291.00	299.80		Cum	1	0.20	8.15	8.14	8.15	0.20	0.33		
299.80	300.00		Cum	1	1.00	8.14	8.15	8.15	0.20	1.63		
300.00	301.00		Cum	1	6.30	9.81	9.80	9.81	0.20	12.35		
301.00	307.30		Cum	1	7.70	8.10	8.15	8.13	0.20	12.51		
307.30	315.00		Cum	1	8.00	8.15	8.25	8.20	0.20	13.12		
315.00	323.00		Cum	1	9.00	9.60	9.60	9.60	0.20	17.28		
323.00	332.00		Cum	1	11.00	9.40	9.60	9.50	0.20	20.90		
332.00	343.00		Cum	1	2.00	8.10	8.20	8.15	0.20	3.26		
343.00	345.00		Cum	1	13.90	8.20	8.15	8.18	0.20	22.73		
345.00	358.90		Cum	1	9.20	9.70	9.71	9.71	0.20	17.86		
358.90	368.10		Cum	1	6.90	8.15	8.15	8.15	0.20	11.25		
368.10	375.00		Cum	1	7.60	8.15	8.30	8.23	0.20	12.50		
375.00	382.60		Cum	1	9.30	9.90	9.50	9.70	0.20	18.04		
382.60	391.90		Cum	1	1.40	7.90	8.00	7.95	0.20	2.23		
391.90	393.30		Cum	1	6.70	9.20	9.20	9.20	0.20	12.33		
393.30	400.00		Cum	1	5.00	7.90	7.40	7.65	0.20	7.65		
400.00	405.00		Cum	1	15.00	7.40	7.60	7.50	0.20	22.50		
405.00	420.00		Cum	1	15.00	7.60	7.40	7.50	0.20	22.50		
420.00	435.00		Cum	1	9.20	9.00	9.10	9.05	0.20	16.65		
435.00	444.20		Cum	1	2.10	7.30	7.45	7.38	0.20	3.10		
444.20	446.30		Cum	1	10.10	9.15	9.10	9.13	0.20	18.43		
446.30	456.40		Cum	1	8.60	7.45	7.35	7.40	0.20	12.73		
456.40	465.00		Cum	1	15.00	7.35	7.25	7.30	0.20	21.90		
465.00	480.00		Cum	1	15.00	7.25	7.65	7.45	0.20	22.35		
480.00	495.00		Cum	1	15.00	7.65	8.50	8.08	0.20	24.23		
495.00	510.00		Cum	1	15.20	10.00	10.60	10.30	0.20	31.31		
510.00	525.20		Cum	1	14.80	8.50	7.60	8.05	0.20	23.83		
525.20	540.00		Cum	1	15.00	7.60	7.50	7.55	0.20	22.65		
540.00	555.00		Cum	1	5.90	7.50	7.50	7.50	0.20	8.85		
555.00	560.90		Cum	1	1.80	4.80	4.80	4.80	0.20	1.73		
560.90	562.70											
		Total Executed Quantity								**6783.34**		
		Tender Quantity								**6149.61**		
		Quantity Upto 125%								**6783.34**	**2021.29**	**13711095.00**